

ROUTE NO.	SECTION	COUNTY	SHEET	TOTAL SHEETS
C.H. 12	00-00075-00-PV	MACOUPIN	37	4
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	

ENTRANCE SCHEDULE													
LOCATION	TYPE	EXISTING SURFACE	EXISTING WIDTH	PROPOSED WIDTH	TYPE	RADIUS	SHOULDER WIDTH	INCIDENTIAL BITUMINOUS SURFACING	AGGREGATE SURFACE COURSE TYPE B 6"	AGGREGATE SHOULDER TYPE A	BITUMINOUS MATERIALS (PRIME COAT) .1 GAL/SY	BITUMINOUS SURFACE REMOVAL BUTT-JOINT	
													FOOT
CH 12 MACOUPIN CO.													
LT. STA. 36+48	FE	EARTH	16	16	RURAL	15	6		4				
RT. STA. 36+83	FE	EARTH	16	16	RURAL	15	6		4				
RT. STA. 105+58	PE	AGG	12	12	RURAL	15	6	5		2	3	7	
RT. STA. 109+50	FE	AGG	16	16	RURAL	15	6		4				
RT. STA. 116+68	PE	AGG	12	12	RURAL	15	6	5		2	3	7	
RT. STA. 118+35	FE	AGG	16	16	RURAL	15	6		4				
RT. STA. 120+16	EARTH	AGG	18	18	RURAL	15	6		4				
LT. STA. 121+30	PE/MB	AGG	12	12	RURAL	15	6	5		2	3	7	
RT. STA. 121+75	FE	AGG	20	20	RURAL	15	6		4				
LT. STA. 129+91	FE	AGG	18	18	RURAL	15	6		4				
RT. STA. 129+92	FE	AGG	16	16	RURAL	15	6		4				
LT. STA. 143+21	FE	AGG	16	16	RURAL	15	6		4				
RT. STA. 143+21	FE	AGG	16	16	RURAL	15	6		4				
RT. STA. 153+55	PE	AGG	20	20	RURAL	15	6	7		2	4	11	
LT. STA. 156+32	FE	AGG	18	18	RURAL	15	6		4				
RT. STA. 161+46	FE	AGG	20	20	RURAL	15	6		4				
RT. STA. 169+65	EARTH	AGG	32	32	RURAL	15	6		7				
LT. STA. 171+37	PE/MB	AGG	12	12	RURAL	15	6	5		2	3	7	
RT. STA. 178+54	PE	AGG	12	12	RURAL	15	6	5		2	3	7	
RT. STA. 180+27	PE	AGG	12	12	RURAL	15	6	5		2	3	7	
RT. STA. 189+53	FE	AGG	16	16	RURAL	15	6		4				
LT. STA. 192+96	PE/MB	AGG	12	12	RURAL	15	6	5		2	3	7	
LT. STA. 200+62	PE/MB	AGG	14	14	RURAL	15	6	6		2	3	8	
RT. STA. 202+73	PE	AGG	14	14	RURAL	15	6	6		2	3	8	
RT. STA. 209+24	FE	AGG	20	20	RURAL	15	6		4				
LT. STA. 209+65	PE/MB	AGG	14	14	RURAL	15	6	6		2	3	8	
LT. STA. 211+03	FE	AGG	22	22	RURAL	15	6		5				
RT. STA. 211+05	PE	AGG	12	12	RURAL	15	6	5		2	3	7	
RT. STA. 223+07	FE	AGG	16	16	RURAL	15	6		4				
LT. STA. 235+90	FE	AGG	24	24	RURAL	15	6		5				
LT. STA. 105+30	MB					15	6	4			3		
LT. STA. 116+89	MB					15	6	4			3		
LT. STA. 153+00	MB					15	6	4			3		
LT. STA. 178+54	MB					15	6	4			3		
LT. STA. 180+14	MB					15	6	4			3		
LT. STA. 202+18	MB					15	6	4			3		
LT. STA. 121+30	PE/MB					15	6	2			1		
LT. STA. 171+37	PE/MB					15	6	2			1		
LT. STA. 192+96	PE/MB					15	6	2			1		
LT. STA. 200+62	PE/MB					15	6	2			1		
LT. STA. 209+65	PE/MB					15	6	2			1		
TOTAL ENTRANCE									101	77	24	61	91
SIDE ROADS													
RT. STA 49+83 (BENSTEAD)		OIL & CHIP	20		20	30		18			11	24	
RT. STA 103+32 (KREUS)			24		24	50		42			25	27	
LT. STA 103+36 (KIMES)			24		24	50		42			25	27	
RT. STA 182+94 (BOSTON CHAPEL)			20		20	30		18			11	24	
LT. STA 182+94 (BALL)			20		20	30		18			11	24	
TOTAL SIDE ROADS								138			83	126	

HLR
 Rice, Berry and Associates
 A Division of Hampton, Lenzini and Renwick, Inc.
 Civil & Structural Engineers
 801 S. Durkin Drive
 Springfield, Illinois 62704
 217-546-3400
 P.O. Box 1036
 DuQuoin, Illinois 62832
 618-190-4637
 Account Number 03-61-0002-1
 Date: 03/10/05
 DESIGNED: L.F.S. CHECKED: L.F.S. DRAWN: D.T.M.

ROADWAY SCHEDULE OF QUANTITIES
 SECTION 00-00075-00-PV
 C.H. 12 FARMERSVILLE ROAD
 MACOUPIN COUNTY