

ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
C.H. 12	00-00075-00-PV	MACOUPIN	37	7
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

SUBSURFACE DRAINAGE TABLE			
LOCATION	PIPE UNDER-DRAINS 4"	PIPE UNDERDRAINS SPECIAL 4"	CONCRETE HEADWALLS FOR PIPE DRAINS
	FOOT	FOOT	EACH
RT. STA. 36+60 TO RT. STA. 39+95	335		
RT. STA. 39+95		15	1
LT. STA. 36+60 TO LT. STA. 39+95	335		
LT. STA. 39+95		15	1
RT. STA. 40+00 TO RT. STA. 44+95	495		
RT. STA. 44+95		15	1
LT. STA. 40+00 TO LT. STA. 44+95	495		
LT. STA. 44+95		15	1
RT. STA. 45+00 TO RT. STA. 49+30	430		
RT. STA. 49+00		15	1
LT. STA. 45+00 TO LT. STA. 49+95	495		
LT. STA. 49+95		15	1
RT. STA. 50+30 TO RT. STA. 54+95	465		
RT. STA. 54+95		15	1
LT. STA. 50+00 TO LT. STA. 54+95	495		
LT. STA. 54+95		15	1
RT. STA. 55+00 TO RT. STA. 59+95	495		
RT. STA. 59+95		15	1
LT. STA. 55+00 TO LT. STA. 59+95	495		
LT. STA. 59+95		15	1
RT. STA. 60+00 TO RT. STA. 64+95	495		
RT. STA. 64+95		15	1
LT. STA. 60+00 TO LT. STA. 64+95	495		
LT. STA. 64+95		15	1
RT. STA. 65+00 TO RT. STA. 69+95	495		
RT. STA. 69+95		15	1
LT. STA. 65+00 TO LT. STA. 69+95	495		
LT. STA. 69+95		15	1
RT. STA. 70+00 TO RT. STA. 74+95	495		
RT. STA. 70+00		15	1
LT. STA. 70+00 TO LT. STA. 74+95	495		
LT. STA. 70+00		15	1
RT. STA. 75+00 TO RT. STA. 79+95	495	15	
RT. STA. 75+00			1
LT. STA. 75+00 TO LT. STA. 79+95	495	15	
LT. STA. 75+00			1
RT. STA. 80+00 TO RT. STA. 84+95	495		
RT. STA. 80+00		15	1
LT. STA. 80+00 TO LT. STA. 84+95	495		
LT. STA. 80+00		15	1
RT. STA. 85+00 TO RT. STA. 89+95	495		
RT. STA. 85+00		15	1
LT. STA. 85+00 TO LT. STA. 89+95	495		
LT. STA. 85+00		15	1
RT. STA. 90+00 TO RT. STA. 92+95	295		
RT. STA. 90+00		15	1
LT. STA. 90+00 TO LT. STA. 92+95	295		
LT. STA. 90+00		15	1
RT. STA. 93+05 TO RT. STA. 97+00	395		
RT. STA. 97+00		15	1
SUBTOTAL	11460	375	25

SUBSURFACE DRAINAGE TABLE			
LOCATION	PIPE UNDER-DRAINS 4"	PIPE UNDERDRAINS SPECIAL 4"	CONCRETE HEADWALLS FOR PIPE DRAINS
	FOOT	FOOT	EACH
LT. STA. 93+05 TO LT. STA. 97+00	395		
LT. STA. 97+00		15	1
RT. STA. 97+05 TO RT. STA. 100+00	295		
RT. STA. 100+00		30	1
LT. STA. 97+05 TO LT. STA. 100+00	295		
LT. STA. 100+00		30	1
RT. STA. 100+00 TO RT. STA. 103+00	300		
LT. STA. 100+00 TO LT. STA. 103+00	300		
RT. STA. 104+00 TO RT. STA. 108+00	400		
RT. STA. 108+00		15	1
LT. STA. 104+00 TO LT. STA. 108+00	400		
LT. STA. 108+00		15	1
RT. STA. 108+05 TO RT. STA. 110+50	245		
RT. STA. 110+50		30	1
LT. STA. 108+05 TO LT. STA. 110+50	245		
LT. STA. 110+50		30	1
RT. STA. 110+50 TO RT. STA. 112+95	245		
LT. STA. 110+50 TO LT. STA. 112+95	245		
RT. STA. 113+00 TO RT. STA. 115+00	200		
RT. STA. 115+00		30	1
LT. STA. 113+00 TO LT. STA. 115+00	200		
LT. STA. 115+00		30	1
RT. STA. 115+00 TO RT. STA. 117+00	200		
LT. STA. 115+00 TO LT. STA. 117+00	200		
RT. STA. 117+05 TO RT. STA. 122+00	495		
RT. STA. 122+00		15	1
LT. STA. 117+05 TO LT. STA. 122+00	495		
LT. STA. 122+00		15	1
RT. STA. 122+05 TO RT. STA. 127+00	495		
RT. STA. 127+00		15	1
LT. STA. 122+05 TO LT. STA. 127+00	495		
LT. STA. 127+00		15	1
RT. STA. 127+05 TO RT. STA. 132+00	495		
RT. STA. 132+00		15	1
LT. STA. 127+05 TO LT. STA. 132+00	495		
LT. STA. 132+00		15	1
RT. STA. 132+05 TO RT. STA. 137+00	495		
RT. STA. 137+00		15	1
LT. STA. 132+05 TO LT. STA. 137+00	495		
LT. STA. 137+00		15	1
RT. STA. 137+05 TO RT. STA. 142+00	495		
RT. STA. 142+00		15	1
LT. STA. 137+05 TO LT. STA. 142+00	495		
LT. STA. 142+00		15	1
RT. STA. 142+05 TO RT. STA. 147+00	495		
RT. STA. 147+00		15	1
SUBTOTAL	9610	390	20

HLR
 Rice, Berry and Associates
 A Division of Hampton, Lenzini and Renwick, Inc.
 Civil & Structural Engineers
 801 S. Durkin Drive
 Springfield, Illinois 62704
 217-546-3400
 P.O. BOX 1036
 DuQuoin, Illinois 62832
 618-790-4637
 Account Number 03-61-0002-1
 Date: 03/10/05
 DESIGNED: L.F.S. CHECKED: L.F.S. DRAWN: TWK

ROADWAY SCHEDULE OF QUANTITIES
 SECTION 00-00075-00-PV
 C.H. 12 FARMERSVILLE ROAD
 MACOUPIN COUNTY