

FAP NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	(1012)W,RS	WHITE/EDWARDS	198	8
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT NO.	CONTRACT NO. 94652	

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	801.FED./201.STATE		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		WHITE COUNTY 1000-2A	EDWARDS COUNTY 1000-2A	501.STATE 501.CITY WHITE SFTY-1B	501.STATE 501.CITY EDWARDS SFTY-1B			100% CITY EDWARDS SFTY-1B
* 56300100	ADJUSTING SANITARY SEWERS, 8-INCH DIAMETER OR LESS	FOOT	400	100	300					
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	18	2	16					
60218500	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 3 FRAME, AND GRATE	EACH	14	3	11					
60219000	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	4		4					
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3		3					
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	37	5	32					
60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	9	1	8					
60236700	INLETS, TYPE A, TYPE 10 FRAME AND GRATE	EACH	4		4					
60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	12	2	10					
60240301	INLETS, TYPE B, TYPE 8 GRATE	EACH	5		5					
60240305	INLETS, TYPE B, TYPE 10 FRAME AND GRATE	EACH	1		1					
60255500	MANHOLES TO BE ADJUSTED	EACH	7		7					
60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1						
60263100	INLETS TO BE RECONSTRUCTED WITH NEW TYPE 3 FRAME AND GRATE	EACH	1		1					
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	7	1	6					
60500040	REMOVING MANHOLES	EACH	8	1	7					
60500060	REMOVING INLETS	EACH	16	2	14					
60500070	REMOVING MANHOLES TO MAINTAIN FLOW	EACH	4	1	3					
60500090	REMOVING INLETS TO MAINTAIN FLOW	EACH	1	1						
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	0.7		0.7					
60603500	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.06	FOOT	619	236	383					
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	10679	1540	9139					
60608600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	FOOT	13.5	13.5						
60610400	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.24	FOOT	17.5	17.5						
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	78	78						
60621600	CONCRETE MEDIAN, TYPE SM	SQ FT	66	66						
63400205	GUARD POSTS REMOVAL	EACH	6	6						

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. _____
 HORIZ. _____
 DATE _____

DRAWN BY _____
 CHECKED BY _____

1 2 3 4 5 6 7 8 9 MKS 2/8/05
 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63

\94652\d0210\pa.dgn
 MKS 2/8/05