

1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63

c:\projects\94652\02101pa.dgn  
stef.fenmk\T\_DATE

FAP NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	(1012)W,RS	WHITE/EDWARDS	198	19

CONTRACT NO. 94652

THERMOPLASTIC PAVEMENT MARKING-LINE, 24" & TEMPORARY PAVEMENT MARKING -LINE 24"		
STATION	LOCATION	AMOUNT (FOOT)
848+97	IL 1	15
5+53	IL 1	18
LT 5+00	NORTH ST	20
RT 5+00	NORTH ST	28
LT 12+00	DIVISION	18
LT 12+00	DIVISION	12
WHITE COUNTY TOTAL		111
PROJECT TOTAL		111 FT

THERMOPLASTIC PAVEMENT MARKING-LINE, 12" & TEMPORARY PAVEMENT MARKING -LINE 12"			
STATION	TO	STATION	QUANTITY (FOOT)
48+69	TO	49+00	3.5
49+00	TO	49+35	11.5
49+35	TO	50+40	50.0
50+40	TO	51+05	44.3
51+05	TO	52+25	103.5
52+25	TO	52+85	55.5
52+85	TO	53+15	17.8
53+15	TO	54+05	65.0
54+05	TO	54+45	15.5
54+45	TO	54+80	8.5
56+81	TO	57+00	6.5
57+00	TO	57+30	27.5
57+30	TO	57+46	17.8
57+46	TO	58+40	92.5
58+40	TO	60+00	130.0
60+00	TO	61+00	53.8
61+00	TO	61+80	20.0
EDWARDS COUNTY TOTAL			723.0
PROJECT TOTAL			723.0 FT

THERMOPLASTIC PAVEMENT MARKING-LINE, 6" & TEMPORARY PAVEMENT MARKING - LINE 6"			
STATION	TO	STATION	AMOUNT (FOOT)
849+05		IL - 1	80 CROSS WALK
5+45		IL - 1	76 CROSS WALK
LT 5+00		NORTH ST.	98 CROSS WALK
RT 5+00		NORTH ST.	110 CROSS WALK
LT 12+00		DIVISION	36 CROSS WALK
LT 12+00		DIVISION	24 CROSS WALK
WHITE COUNTY TOTAL			424
16+50		VINE ST	84 CROSS WALK
54+90	TO	56+10	120 PASSING LANE
EDWARDS COUNTY TOTAL			204
PROJECT TOTAL			628 FT

THERMOPLASTIC PAVEMENT MARKING- & TEMPORARY PAVEMENT MARKING - LETTERS & SYMBOLS		
STATION	SYMBOL	QUANTITY (SQ FT)
55+28	ARROW	16
55+72	ARROW	16
EDWARDS COUNTY TOTAL		32
PROJECT TOTAL		32 SQ FT

PAVEMENT MARKING SCHEDULE									
STATION	TO	STATION	LENGTH (FOOT)	(FOOT)	(FOOT)	(FOOT)	(EACH)	(SQ FT)	
848+85	TO	849+15	30	7.5	9.0	7.5	1	1.0	
849+15	TO	849+30	15	3.8	4.5	3.8	0	0.5	
4+93	TO	12+28	734.97	183.7	220.5	183.7	9	24.5	
WHITE COUNTY TOTAL			779.97	195.0	234.0	195.0	10	26.0	
12+28	TO	24+50	1222	305.5	366.6	305.5	15	40.7	
14+55	TO	47+28	3272.91	818.2	981.9	818.2	41	109.1	
47+28	TO	48+28	100	25.0	30.0	25.0	3	3.3	
48+28	TO	48+68	40	80.0	12.0	80.0	6	1.3	
48+68	TO	54+80	612	2448.0	183.6	2448.0	35	20.4	
54+80	TO	56+10	130	260.0	39.0	260.0	12	4.3	
56+10	TO	56+80	70	0.0	21.0	0.0	0	2.3	
56+80	TO	57+60	80	320.0	24.0	320.0	8	2.7	
57+60	TO	61+80	420	1680.0	126.0	1680.0	23	14.0	
61+80	TO	62+20	40	80.0	12.0	80.0	6	1.3	
62+20	TO	63+25	105	26.3	31.5	26.3	3	3.5	
EDWARDS COUNTY TOTAL			6091.91	6043.0	1827.6	6043.0	152	203.1	
PROJECT TOTAL			6872	6238	2062	6238	162	229	

PATCHING SCHEDULE	
CLASS D PATCHES, TYPE 1, 10"	889 SQ YD
CLASS D PATCHES, TYPE 2, 10"	333 SQ YD
CLASS D PATCHES, TYPE 3, 10"	143 SQ YD

PROPERTY MARKERS AND PINS				
STATION	OFFSET LEFT	RIGHT	SAVE AND PROTECT PROPERTY PINS	FURNISH AND INSTALL PROPERTY MARKERS
6+98.515		39.016	X	
14+21.573	39.605		X	
14+37.607		29.974		1
18+94.839	33.059		X	
20+44.835	32.753			1
20+58.080		27.767		1
STA EQ: 24+50BK=14+55.09 AH				
16+43.934		24.178		1
19+70.860		37.092	X	
20+28.763		23.871		1
29+96.561	66.532		X	
30+04.597	55.607			1
30+20.077	42.943			1
38+23.246		32.421	X	
39+74.561		39.922	X	
40+52.372	40.689		X	
41+69.867		39.911	X	
44+81.721	22.975		X	
55+19.749		63.995	X	
EDWARDS CO. TOTAL				7 EACH

PCC SIDEWALK, 4"					
SIDE	STATION TO	STATION	100% STATE	50% CITY / 50% STATE	
LT	5+26	TO 5+48	110		
RT	5+35	TO 5+52	130		
RT	6+74	TO 7+08	128		
LT	6+82	TO 7+22	80		
LT	7+93	TO 8+81	335		
RT	8+52	TO 8+81	205		
LT	9+10	TO 9+75	325		
RT	9+12	TO 14+26	2570		
LT	10+10	TO 10+65		275	
LT	11+00	TO 11+82	410		
WHITE COUNTY TOTAL			4293		275
LT	13+13	TO 13+66			265
LT	14+06	TO 14+31			125
LT	14+73	TO 18+40			1835
RT	14+73	TO 18+40	1835		
RT	18+80	TO 19+65	425		
RT	19+80	TO 20+45	325		
LT	18+88	TO 20+25			685
RT	20+85	TO 21+40	275		
LT	20+72	TO 21+36			320
LT	21+80	TO 22+18			190
RT	21+80	TO 22+18	190		
LT	22+62	TO 24+50			940
LT	14+55	TO 14+61			30
RT	22+62	TO 24+22			800
RT	24+39	TO 24+50			55
RT	14+55	TO 16+03			740
LT	15+04	TO 16+03			495
LT	16+47	TO 16+81			295
RT	16+50	TO 17+93			715
LT	17+15	TO 17+51			180
LT	17+86	TO 18+09			115
LT	18+22	TO 18+61			195
RT	18+37	TO 18+74			185
LT	19+04	TO 19+70			330
RT	19+14	TO 19+75			305
LT	20+25	TO 22+13			925
RT	20+22	TO 20+98			375
RT	21+22	TO 21+55	165		
RT	21+82	TO 22+20	165		
LT	22+25	TO 22+78			260
RT	22+58	TO 24+16	790		
LT	22+97	TO 24+31			670
LT	24+50	TO 26+13			815
RT	24+60	TO 26+39	895		
LT	26+34	TO 27+22			440
RT	26+63	TO 30+04	1715		
LT	27+39	TO 27+74			175
LT	27+90	TO 28+90			500
LT	29+31	TO 29+50			95
LT	29+79	TO 30+00			110
LT	30+45	TO 31+70			625
RT	30+59	TO 31+28			345
RT	31+85	TO 32+32			225
LT	32+26	TO 33+07			405
RT	32+78	TO 34+32			770
LT	33+56	TO 33+93			185
LT	34+40	TO 34+55			50
EDWARDS COUNTY TOTAL			6780		15770
TOTALS =			11073		16045
TOTAL			27118		SQ FT

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**PAVEMENT MARKING & MISCELLANEOUS SCHEDULES**  
 SCALE: VERT. \_\_\_\_\_  
 HORIZ. \_\_\_\_\_  
 DATE \_\_\_\_\_  
 DRAWN BY \_\_\_\_\_  
 CHECKED BY \_\_\_\_\_