

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE						
PAY CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	1000-2A		X071-2A		X080-2A	Y007	
				RURAL	URBAN	RURAL	URBAN	RURAL	RURAL	URBAN
40600990	TEMPORARY RAMP	SQ YD	1,251	928	323					
42001165	BRIDGE APPROACH PAVEMENT	SQ YD	1,064	532	532					
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	212	106	106					
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	509	314	195					
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	30,740	21,882	8,858					
44000100	PAVEMENT REMOVAL	SQ YD	1,133	945	188					
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1,916	1,052	864					
44000400	GUTTER REMOVAL	FOOT	1,860	200	1,660					
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	664	151	513					
44001430	BITUMINOUS SHOULDER REMOVAL	SQ YD	3,793	2,333	1,460					
44002500	GUTTER OUTLET REMOVAL	EACH	3		3					
44002805	ISLAND REMOVAL	SQ FT	217	217						
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SQ FT	1,618		1,618					
44004000	PAVED DITCH REMOVAL	FOOT	365		365					
44004510	PORTLAND CEMENT CONCRETE SHOULDER REMOVAL	SQ YD	1,748	1,443	305					
48101500	AGGREGATE SHOULDERS, TYPE B 6'	SQ YD	7,953	7,133	820					
48101600	AGGREGATE SHOULDERS, TYPE B 8'	SQ YD	309	152	157					
48202600	BITUMINOUS SHOULDERS SUPERPAVE 8'	SQ YD	10,392	7,413	2,979					
48300100	PORTLAND CEMENT CONCRETE SHOULDER, 6'	SQ YD	173	173						
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	1							
50102400	CONCRETE REMOVAL	CU YD	135.9		77.0	58.9				
50104650	SLOPE WALL REMOVAL	SQ YD	1,502		642	860				
50105200	REMOVE EXISTING CULVERTS	EACH	24	19	5					
50200100	STRUCTURE EXCAVATION	CU YD	676		366	310				
50300100	FLOOR DRAINS	EACH	24		12	12				
50300225	CONCRETE STRUCTURES	CU YD	357.4		236.3	121.1				
50300255	CONCRETE SUPERSTRUCTURE	CU YD	1,249.8		676.2	573.6				
50300260	BRIDGE DECK GROOVING	SQ YD	4,105		2,213	1,892				
50300300	PROTECTIVE COAT	SQ YD	4,620		2,491	2,129				
50300310	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	40		20	20				
50300320	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	10		10					
50400405	PRECAST PRESTRESSED CONCRETE DECK BEAMS (21" DEPTH)	SQ FT	3,101							
50500105	FURNISHING AND ERECTING STRUCTURAL STEEL	L SUM	1		.48	.52				
50500505	STUD SHEAR CONNECTORS	EACH	4,260		2,460	1,800				
50800105	REINFORCEMENT BARS	POUND	10,796	66	130	7,160	3,440			
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	371,030		205,600	165,430				
50900205	STEEL RAILING, TYPE S1	FOOT	222							
51201400	FURNISHING STEEL PILES HP 10x42	FOOT	448		448					
51201500	FURNISHING STEEL PILES HP 10x57	FOOT	294			294				
51201600	FURNISHING STEEL PILES HP 12x53	FOOT	680							

NOTE:

RURAL STA. 942+50.00 TO STA. 1016+00.00
 URBAN STA. 1016+00.00 TO STA. 46+80.05

*DENOTES SPECIALTY ITEM

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SUMMARY OF QUANTITIES SHEET 2 OF 6

DATE 8/02
 DRAWN BY ASB
 CHECKED BY SJK

Rev. 6-3-05
 Rev.