teasleyck
3/31/2005
c:\projects\94905d\d04201pa.dgn
RSF

FAI RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	(41-7)RS-1	JEFFERSON	48	11
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT NO.		

CONTRACT NO. 94905

PAVING SCHEDULE - MAINLINE

STATION TO STATION	LENGTH	EXISTING PAVEMENT WIDTH	AREA	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, MIX "D" N105	POLYMERIZED BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE IL-19.0 N105	BITUMINOUS SURFACE REMOVAL 3 1/4"	BITUMINOUS SURFACE REMOVAL 1"	AGGREGATE SHOULDERS,TYPE B	BITUMINOUS SHOULDERS SUPERPAVE
	LIN FT	FEET	SQ YD	GALLON	TON	TON	TON	SQ YD	SQ YD	TON	TON
I-64 EB											
2085+70.47 TO 2119+25.00	3354.53	24	8945.4	1565.4	31.3	755.5	1127.1	8945.4	6709.1	285.1	563.6
2119+25.00 TO 2122+15.00	290	24	773.3	103.1	2.1	65.3	97.4	773.3	257.8	12.3	21.7
2122+15.00 TO 2125+90.00	375	24	1000	133.3	2.7	84.5	126	1000.0	333.3	15.9	28
2125+90.00 TO 2149+25.00	2335	24	6226.7	1089.7	21.8	525.9	784.6	6226.7	4670	198.5	392.3
2149+25.00 TO 2151+35.00	210	24	560	74.7	1.5	47.3	70.6	560.0	186.7	8.9	15.7
2151+35.00 TO 2160+65.00	930	24	2480	330.7	6.6	209.4	312.5	2480.0	826.7	39.5	69.4
2160+65.00 TO 2190+22.00	2957	24	7885.3	1379.9	27.6	666	993.6	7885.3	5914	251.4	496.8
2190+22.00 TO 2190+62.00	40	24	106.7	18.7	0.4	9	13.4	106.7	80	3.4	6.7
2190+62.00 TO 2198+28.00	766	24	2042.7	357.5	7.1	172.5	257.4	1962.7	1532	65.1	128.7
2198+28.00 TO 2199+92.00	164	Brdg Omission									
2199+92.00 TO 2203+45.00	353	24	941.3	164.7	3.3	79.5	118.6	861.3	706	30	59.3
2203+45.00 TO 2203+85.00	40	24	106.7	18.7	0.4	9	13.4	106.7	80	3.4	6.7
2203+85.00 TO 2362+11.77	15826.77	24	42204.7	7385.8	147.7	3564.4	5317.8	42124.7	31653.5	1345.3	2658.9
I-64 WB											
2085+70.47 TO 2115+25.00	2954.53	24	7878.7	1378.8	27.6	665.4	992.7	7878.7	5909.1	251.1	496.4
2115+25.00 TO 2124+75.00	950	24	2533.3	337.8	6.8	214	319.2	2533.3	844.4	40.4	70.9
2124+75.00 TO 2127+00.00	225	24	600	80	1.6	50.7	75.6	600.0	200	9.6	16.8
2127+00.00 TO 2150+00.00	2300	24	6133.3	1073.3	21.5	518	772.8	6133.3	4600	195.5	386.4
2150+00.00 TO 2154+00.00	400	24	1066.7	142.2	2.8	90.1	134.4	1066.7	355.6	17	29.9
2154+00.00 TO 2156+70.00	270	24	720	96	1.9	60.8	90.7	720.0	240	11.5	20.2
2156+70.00 TO 2194+31.00	3761	24	10029.3	1755.1	35.1	847	1263.7	10029.3	7522	319.7	631.8
2194+31.00 TO 2194+72.00	41	24	109.3	19.1	0.4	9.2	13.8	109.3	82	3.5	6.9
2194+72.00 TO 2198+28.00	356	24	949.3	166.1	3.3	80.2	119.6	869.3	712	30.3	59.8
2198+28.00 TO 2199+92.00	164	Brdg Omission									
2199+92.00 TO 2207+43.00	751	24	2002.7	333.8	6.7	169.1	252.3	1922.7	1335.1	63.8	112.1
2207+43.00 TO 2207+85.00	42	24	112	18.7	0.4	9.5	14.1	112.0	74.7	3.6	6.3
2207+85.00 TO 2362+11.77	15426.77	24	41138.1	6856.3	137.1	3474.3	5183.4	41058.1	27425.4	1311.3	2303.7
			TOTALS	24879	498	12377	18465	146066	102249	4516	8589

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

RESURFACING SCHEDULE

SCALE: VERT. HORIZ.
DATE
DRAWN BY
CHECKED BY