

teas.leyck
3/31/2005
c:\projects\94905d\04201pa.dgn
RSFR

FAI NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	(41-7)RS-1	JEFFERSON	48	12
FED. ROAD DIST. NO. 7	ILLINOIS	FED. AID PROJECT NO.		

CONTRACT NO. 94905

PAVING SCHEDULE - RAMPS

STATION TO STATION	LENGTH	EXISTING PAVEMENT WIDTH	AREA	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, MIX "D" NI05	POLYMERIZED BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE IL-19.0 NI05	BITUMINOUS SURFACE REMOVAL 3 1/4"	BITUMINOUS SURFACE REMOVAL 1"	AGGREGATE SHOULDERS, TYPE B	BITUMINOUS SHOULDERS SUPERPAVE
	LIN FT	FEET	SQ YD	GALLON	TON	TON	TON	SQ YD	SQ YD	TON	TON
RAMP A											
0+29.00 TO 1+10.00	81	-									
1+10.00 TO 13+80.01	1270.01	16	2257.8	366.9	7.3	191.2	284.5	2257.8	1411.1	161.9	118.5
13+80.01 TO 14+64.75	84.74	15	141.2	32	0.6	12	17.8	141.2	178.9	10.8	15
14A+64.75=2125+71.97											
2125+71.97 TO 2124+75.00	96.97	14	150.8	29.1	0.6	12.8	19	150.8	140.1	6.2	11.8
2124+75.00 TO 2116+50.00	825	21.25	1947.9	249.8	5	164.6	245.4	1947.9	550	52.6	46.2
2116+50.00 TO 2115+25.00	125	1.875	26	13.7	0.3	2.3	3.3	26.0	111.1	8	9.3
RAMP B											
14+22.00 TO 13+60.00	62	-									
13+60.00 TO 13+20.00	40	20	88.9	13.3	0.3	7.5	11.2	88.9	44.4	5.1	3.7
13+20.00 TO	1320	16	2346.7	381.3	7.6	198.7	295.7	2346.7	1466.7	168.3	123.2
OB+00=2150+15.72											
2150+15.72 TO 2150+90.00	74.28	16	132.1	33	0.7	11.2	16.6	132.1	198.1	4.7	16.6
2150+90.00 TO 2154+00.00	310	16	551.1	103.3	2.1	46.7	69.4	551.1	482.2	19.8	40.5
2154+00.00 TO 2156+00.00	200	10.5	233.3	36.7	0.7	19.8	29.4	233.3	133.3	12.8	11.2
2156+00.00 TO 2156+70.00	70	3	23.3	8.6	0.2	2	2.9	23.3	62.2	4.5	5.2
RAMP C											
0+19.00 TO 0+98.00	79	-									
0+98.00 TO 1+04.00	6	16	10.7	1.7		0.9	1.3	10.7	6.7	0.8	0.6
1+04.00 TO 13+59.88	1255.88	16	2232.7	362.8	7.3	189.1	281.3	2232.7	1395.4	160.1	117.2
13+59.88 TO 14+56.40	96.52	14.7	157.6	35.3	0.7	13.4	19.9	157.6	195.7	6.2	16.4
14C+56.40=2150+23.8											
2150+23.80 TO 2151+35.00	111.2	14	173	33.7	0.7	14.5	21.8	173.0	163.7	7.1	13.8
2151+35.00 TO 2159+00.00	765	12.25	1041.3	155.1	3.1	88.4	131.2	1041.3	510	48.8	42.8
2159+00.00 TO 2160+10.00	110	3.5	42.8	14.1	0.3	3.7	5.4	42.8	97.8	7	8.2
2160+10.00 TO 2160+65.00	55	1.75	10.7	7.2	0.1	1	1.3	10.7	61.1	3.5	5.1
RAMP D											
14+05.00 TO 13+40.00	65	-									
13+40.00 TO 13+00.00	40	20	88.9	13.3	0.3	7.5	11.2	88.9	44.4	5.1	3.7
13+00.00 TO	1300	16	2311.1	375.6	7.5	194.1	291.2	2311.1	1444.4	165.8	121.3
OD+00=2125+87.37											
2125+87.37 TO 2122+15.00	372.37	16	662	126.2	2.5	55.6	83.4	662.0	599.9	23.7	50.4
2122+15.00 TO 2120+00.00	215	10.5	250.8	39.4	0.8	21.1	31.6	250.8	143.3	13.7	12
2120+00.00 TO 2119+25.00	75	3	25	9.2	0.2	2.1	3.2	25.0	66.7	4.8	5.6
			TOTALS	2441	49	1260	1878	14906	9507	901	798

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
**RESURFACING
SCHEDULE -
RAMPS**
SCALE: VERT.
DATE HORIZ.
DRAWN BY
CHECKED BY