

teaslejack
 teaslejack+*.DATE_
 c:\projects\94905d\04201pa.dgn
QUSCH80

FAI RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
64	(41-7RS-1	JEFFERSON	48	40
FED. ROAD DIST. NO. 7		ILLINOIS	FED. AID PROJECT NO.	

CONTRACT NO. 94905

BITUMINOUS SCHEDULE

LOCATION	TEMPORARY RAMP SQ YD	BITUMINOUS SURFACE REMOVAL - BUTT JOINT SQ YD	BITUMINOUS MATERIALS (PRIME COAT) GAL	AGGREGATE (PRIME COAT) TON	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", NTO TON
041-0080					
STAGE I	18	140	18	2	14
STAGE II	18	140	18	2	14
TOTAL	36	280	36	4	28

BRIDGE REPAIR SCHEDULE

LOCATION	LENGTH FEET	BRIDGE DECK HYDRO- SCARIFICATION 1/2" SQ YD	DECK SLAB REPAIR (FULL DEPTH, TYPE I) SQ YD	DECK SLAB REPAIR (FULL DEPTH, TYPE II) SQ YD	BRIDGE DECK MICROSILOCA CONCRETE OVERLAY 2 1/4" SQ YD	BRIDGE DECK GROOVING SQ YD	PLUG EXISTING DECK DRAINS EACH	POLYMER CONCRETE CU FT	SILICONE JOINT SEALER LIN FT
041-0080									
Stage I	246	361	1	6	361	333	2	2.25	30
Stage II	246	361	0	0	361	333	2	2.25	30
TOTAL		722	1	6	722	666	4	4.5	60

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**QUANTITY SCHEDULES
 S.N. 041-0080**

SCALE: VERT.
 HORIZ.
 DATE

DRAWN BY
 CHECKED BY