

steffenmk  
6/2/2005  
c:\projects\94944\d01302pa.dgn  
SCH

HTL	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	(18,19,20) RS-2	CRAWFORD	21	7
FED. ROAD DIST. NO. 1		ILLINOIS	FED. AID PROJECT NO.	
CONTRACT NO. 94944				

RESURFACING SCHEDULE

STATION TO STATION	LENGTH	EXISTING PAVEMENT WIDTH	AREA	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	LEVELLING BINDER (MACHINE METHOD), SUPERPAVE N70	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE MIX C, N 70	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	BITUMINOUS SURFACE REMOVAL 2 1/4"	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	AGGREGATE SHOULDERS, TYPE B	TEMPORARY RAMP
	LIN FT	FEET	SQ YD	GALLON	TON	TON	TON	SQ YD	SQ YD	SQ YD	TON	SQ YD
ILL 1 440+50 TO 490+77	5027.0	30	16757	1675.7	33.5	703.8	1407.6	200		16556.7	547.6	33.4
490+77 TO 491+99		30						100				
491+99 TO 612+29.25	12030.3	30	40101	4010.1	80.2	1684.2	3368.5			40000.8	1317.9	16.7
612+29.25 TO 612+59.25	30.0	30	100	10.0	0.2	4.2	8.4		100.0		3.3	
612+59.25 TO 614+75	215.8	31.5	755	75.5	1.5	31.7	63.4			755.1	5.3	
614+75 TO 617+30	255.0	39	1105	110.5	2.2	46.4	92.8		1105.0		14.1	
617+30 TO 618+00	70.0	33	257	25.7	0.5	10.8	21.6		256.7		3.9	
618+00 TO 618+30	30.0	30	100	10.0	0.2	4.2	8.4		100.0		3.3	
618+30 TO 1000+16	38186.0	30	127287	12728.7	254.6	5346.0	10692.1			127286.7	4158.8	
1000+16 TO 1000+46	30.0	30	100	10.0	0.2	4.2	8.4		100.0		3.3	
1000+46 TO 1008+93.79	847.8	24	2261	226.1	4.5	95.0	189.9		2260.8		9.4	20.0
TOTALS				18883	378	7931	15862	300	4678	183845	6067	70

PAVEMENT MARKING SCHEDULE

STATION TO STATION	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	TEMPORARY PAVEMENT MARKING - LINE 4"	TEMPORARY PAVEMENT MARKING - LINE 6"	TEMPORARY PAVEMENT MARKING - LINE 24"	SHORT-TERM PAVEMENT MARKING	RAISED REFLECTIVE PAVEMENT MARKERS
	SO FT	FOOT	FOOT	SO FT	FOOT	FOOT	FOOT	FOOT	EACH
IL 1 440+50 TO 593+75					37740			6081.2	190
593+75 TO 618+12	46.8	170		46.8	9008	170		1042.8	36
618+12 TO 653+63					8863			1420.4	45
653+63 TO 660+60					2743			278.8	9
660+60 TO 1000+46					82751			13594.4	425
1000+46 TO 1002+15					212			67.6	3
1002+15 TO 1008+93	61.2		36	61.2	645		36	463.2	9
TOTALS	108	170	36	108	141962	170	36	22949	717

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: VERT. DATE  
HORIZ.

DRAWN BY  
CHECKED BY

Rev. Sheet 6-2-05