

steffenmk
3/31/2005
c:\projects\94944\d01302pa.dgn
SCH

RTL	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
332	(18,19,20) RS-2	CRAWFORD	21	7
FED. ROAD DIST. NO. 7		BLINDS	FED. AID PROJECT NO.	
CONTRACT NO. 94944				

RESURFACING SCHEDULE

STATION TO STATION	LENGTH	EXISTING PAVEMENT WIDTH	AREA	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	LEVELING BINDER (MACHINE METHOD), SUPERPAVE N70	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX C, N 70	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, MIX D, N 90	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE, N 90	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	BITUMINOUS SURFACE REMOVAL 2 1/4"	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	AGGREGATE SHOULDERS, TYPE B	TEMPORARY RAMP
	LIN FT	FEET	SQ YD	GALLON	TON	TON	TON	TON	TON	SQ YD	SQ YD	SQ YD	TON	SQ YD
ILL 1														
440+50 TO 490+77	5027.0	30	16757	3351.3	33.5	703.8	1407.6			200		16556	547.6	33.4
490+77 TO 491+99		30								100				
491+99 TO 612+29	12030.3	30	40101	8020.2	80.2	1684.2	3368.5					40000	1317.9	16.7
612+29 TO 612+59	30.0	30	100	20.0	0.2	4.2	8.4				100.0		3.3	
612+59 TO 614+75	215.8	31.5	755	151.0	1.5	31.7	63.4				755.1		5.3	
614+75 TO 617+30	255.0	39	1105	221.0	2.2	46.4	92.8				1105.0		14.1	
617+30 TO 618+00	70.0	33	257	51.3	0.5	10.8	21.6				256.7		3.9	
618+00 TO 618+30	30.0	30	100	20.0	0.2	4.2	8.4				100.0		3.3	
618+30 TO 1000+16	38186.0	30	127287	25457.3	254.6	5346.0	10692.1					127286	4158.8	
1000+16 TO 1000+46	30.0	30	100	20.0	0.2	4.2	8.4				100.0		3.3	
1000+46 TO 1008+93	847.8	24	2261	452.2	4.5			189.9	95.0		2260.8		9.4	20.0
1009+00 TO 1015+40	640.0	28	1991	398.2	4.0			167.3	83.6		1991.1			43.3
ILL 33														
1+00 TO 0+00	100.0	26	289	57.8	0.6			24.3	12.1		288.9			20.8
1021+23 TO 1023+70	247.0	26	714	142.7	1.4			59.9	30.0		713.6			
1023+94 TO 1027+00	306.0	25	850	170.0	1.7			71.4	35.7		850.0			21.7
4 CORNERS OF INTERSECTION		VAR	533	106.7	1.1			44.8	22.4		533.3			
				38640	387	7836	15672	558	279	300	9055	183845	6067	156

PAVEMENT MARKING SCHEDULE

STATION TO STATION	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	TEMPORARY PAVEMENT MARKING - LINE 4"	TEMPORARY PAVEMENT MARKING - LINE 6"	TEMPORARY PAVEMENT MARKING - LINE 24"	SHORT-TERM PAVEMENT MARKING	RAISED REFLECTIVE PAVEMENT MARKERS
	SO FT	FOOT	FOOT	SO FT	FOOT	FOOT	FOOT	FOOT	EACH
IL 1									
440+50 TO 593+75					37740			6081.2	191
593+75 TO 618+12	46.8	170		46.8	9008	170		1042.8	36
618+12 TO 653+63					8863			1420.4	45
653+63 TO 660+60					2743			278.8	9
660+60 TO 1000+46					82751			13594.4	425
1000+46 TO 1002+15					212			67.6	3
1002+15 TO 1008+93	61.2		36	61.2	645		36	463.2	9
1010+00 TO 1015+40			12		1755		12	408	7
IL 33									
1+00 TO 0+00					225			40	2
1021+23 TO 1027+00			48		1299		48	998.8	8
TOTALS	108	170	96	108	145241	170	96	24396	735

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES

SCALE: VERT. HORIZ.
DATE

DRAWN BY
CHECKED BY