SUMMARY OF QUANTITIES – BASE BID

ITEM NO.	DESCRIPTION	UNIT	AS AWARDED QUANTITIES	AS BUILT QUANTITIES
AR125941	ADJUST STAKE MOUNTED LIGHT	EA	46	
AR125942	ADJUST BASE MOUNTED LIGHT	EA	8	
AR150510	ENGINEER'S FIELD OFFICE	L.S.	1	
AR150540	HAUL ROAD	L.S.	1	
AR156520	INLET PROTECTION	EA	5	
AR201661	CLEAN & SEAL BITUMINOUS CRACKS	L.F.	5000	
AR401610	BITUMINOUS SURFACE COURSE	TON	2283	
AR401620	BITUMINOUS SURFACE COURSE, LEVELING	TON	2411	
AR401655	BUTT JOINT CONSTRUCTION	S.Y.	1065	
AR401910	REMOVE & REPLACE BIT. PAVEMENT	S.Y.	141	
AR402622	POROUS FRICTION COURSE, 0.10'	S.Y.	20723	
AR603510	BITUMINOUS TACK COAT	GAL.	14601	
AR620520	PAVEMENT MARKING-WATERBORNE	S.F.	13001	
AR705943	ADJUST UNDERDRAIN INSPECTION HOLE	EA	10	
AR901510	SEEDING	AC	5.0	
AR905520	TOPSOILING (FROM OFF SITE)	CY	2093	
AR908510	MULCHING	AC	5.0	

SUMMARY OF QUANTITIES – BID ALTERNATE NO. 1

ITEM NO.	DESCRIPTION	UNIT	AS AWARDED QUANTITIES	AS BUILT QUANTITIES
AR800530	TAXIWAY SIGN PANEL REPLACEMENT	EA	4	

INDEX TO SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	SUMMARY OF QUANTITIES & INDEX TO SHEETS
3	PROPOSED SAFETY PLAN
4	PROPOSED PAVEMENT REMOVAL AND REPLACEMENT
5	PROPOSED PLAN & PROFILE STA. 13+07.00 TO STA. 25+00.00
6	PROPOSED PLAN & PROFILE STA. 25+00.00 TO STA. 38+00.00
7	PROPOSED PLAN & PROFILE STA. 38+00.00 TO STA. 49+05.89
8	PROPOSED BUTT JOINT CONSTRUCTION DETAIL
9	PROPOSED EROSION CONTROL DETAIL
10	PROPOSED LIGHT ADJUSTMENT DETAIL
11	PROPOSED GENERAL NOTES
12	PROPOSED STAKING PLAN STA. 13+07.00 TO STA. 49+05.89
13	PROPOSED RUNWAY INTERSECTION STAKING PLAN STA. 34+50.00 TO STA. 40+00.00
14	PROPOSED MARKING PLAN STA. 13+07 TO 21+00
15	PROPOSED MARKING PLAN STA. 21+00 TO 28+00
16	PROPOSED MARKING PLAN STA. 28+00 TO 35+00
17	PROPOSED MARKING PLAN STA. 35+00 TO 42+00
18	PROPOSED MARKING PLAN STA. 42+00 TO 49+05.89
19	PROPOSED TAXIWAY SIGN PANEL REPLACEMENT
20	PROPOSED CROSS SECTIONS STA. 13+07.00 TO 15+00.00
21	PROPOSED CROSS SECTIONS STA. 15+50.00 TO 17+00.00
22	PROPOSED CROSS SECTIONS STA. 17+50.00 TO 19+00.00
23	PROPOSED CROSS SECTIONS STA. 19+50.00 TO 21+00.00
24	PROPOSED CROSS SECTIONS STA. 21+50.00 TO 23+00.00
25	PROPOSED CROSS SECTIONS STA. 23+50.00 TO 26+00.00
26	PROPOSED CROSS SECTIONS STA. 26+50.00 TO 29+00.00
27	PROPOSED CROSS SECTIONS STA. 26+50.00 TO 29+00.00
28	PROPOSED CROSS SECTIONS STA. 31+50.00 TO 33+34.00
29	PROPOSED CROSS SECTIONS STA. 33+50.00 TO 35+19.00
30	PROPOSED CROSS SECTIONS STA. 35+50.00 TO 39+00.00
31	PROPOSED CROSS SECTIONS STA. 39+23.00 TO 40+00.00
32	PROPOSED CROSS SECTIONS STA. 40+50.00 TO 41+50.00
33	PROPOSED CROSS SECTIONS STA. 42+00.00 TO 43+50.00
34	PROPOSED CROSS SECTIONS STA. 44+00.00 TO 45+50.00
35	PROPOSED CROSS SECTIONS STA. 46+00.00 TO 47+50.00
36	PROPOSED CROSS SECTIONS STA. 48+00.00 TO 49+00.00

DATE	REVISION	BY

OLNEY-NOBLE AIRPORT
OLNEY, ILLINOIS
RICHLAND COUNTY

IL. PROJ.: OLY-3438 A.I.P. PROJ.: 3-17-0076-B7

HSI Project No. 820-05RWY
Filename R-002FLP.DGN
Scale NO SCALE
Date 02/03/2005

LAYOUT	JAC	02/24/05
DRAWN	JAC	02/24/05
REVIEWED	CAH	05/13/05

HANSON
Hanson Professional Services Inc.
4227 Earth City Expressway, Suite 130
St. Louis, MO 63045-1308
Offices Nationwide

REHABILITATE RUNWAY 3/21

SUMMARY OF QUANTITIES & INDEX TO SHEETS

I:\AIRPORTS\OLNEY\820-05RWY\AIRPORT\SHEETS\R-002FLP.DGN 05\27\2005, 07:43 AM
BAK