


PE084

REVISIONS		
NUMBER	BY	DATE



SUMMARY OF QUANTITIES

ITEM	DESCRIPTION	UNIT	QUANTITY
AR106511	TYPE A AREA LGHT POLE W/ 1 FIXTURE	EA	6
AR106512	TYPE A AREA LGHT POLE W/ 2 FIXTURES	EA	9
AR106905	REMOVE LIGHT POLE AND FIXTURE	EA	3
AR108756	1/C #6 GROUND	LF	4,200
AR801955	1/C #4 600V THWN CABLE	LF	11,980
AR110501	1-WAY CONC. ENCASED DUCT	LF	1,437
AR110946	ADJUST ELECTRICAL HANDHOLE	EA	1
AR801956	1-WAY PVC DUCT, DIRECT BURY	LF	700
AR151420	CLEARING TREES 0-2.5' BUTT. DIA.	EA	1
AR151430	CLEARING TREES 2.5'-5' BUTT DIA.	EA	1
AR152410	UNCLASSIFIED EXCAVATION	CY	4,210
AR156510	SILT FENCE	LF	500
AR156520	INLET PROTECTION	EA	1
AR156544	RIPRAP-GRADATION NO. 4	SY	142
AR201610	BITUMINOUS BASE COURSE	TON	1,400
AR209608	CRUSHED AGG. BASE COURSE - 8"	SY	11,630
AR401610	BITUMINOUS SURFACE COURSE	TON	1,700
AR401655	BUTT JOINT CONSTRUCTION	SY	560
AR401900	REMOVE BITUMINOUS PAVEMENT	SY	4,544
AR501604	4" PCC SIDEWALK	SF	6,620
AR602510	BITUMINOUS PRIME COAT	GAL	2,901
AR603510	BITUMINOUS TACK COAT	GAL	582
AR620530	PAVEMENT MARKING - EPOXY	SF	3,509
AR751940	ADJUST INLET	EA	4
AR751943	ADJUST MANHOLE	EA	1
AR754410	COMB CONCRETE CURB & GUTTER	LF	1,780
AR754904	REMOVE COMB CURB & GUTTER	LF	39
AR801957	LIGHTING CONTROLLER MODIFICATIONS	LS	1
AR904510	SODDING	SY	1,689
AR910210	TEMPORARY SIGN	EA	10
AR910430	TRAFFIC MAINTENANCE (ROADWAY)	LS	1
AR910420	BOLLARD	EA	4

CONSTRUCT, LIGHT & MARK WEST LONG TERM PARKING LOT

CMT
CRAWFORD, MURPHY & TILLY, INC.
CONSULTING ENGINEERS

IL PROJECT NUMBER PIA-3385
FILE:
DESIGN BY: BWS
DRAWN BY: JSP
CHECKED BY: BJS
APPROVED BY: CET
DATE: JUNE 17, 2005
JOB No: 05061-03-00
SUMMARY OF QUANTITIES
SHEET 2 OF 41 SHEETS