

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION CODE	
				STATE FUNDS 100% STATE	STRUCTURE 0040 RURAL
67100100	MOBILIZATION	L SUM	1		1
70100820	TRAFFIC CONTROL AND PROTECTION, STANDARD, 701451	L SUM	1		1
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	20		20
X0325265	REMOVE ELECTRIC SERVICE	EACH	2		2
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	500		500
X8040115	ELECTRICAL CONNECTION TO SIGN STRUCTURE (TRUSS TYPE)	EACH	2		2
X7240195	REMOVE EXISTING SIGN PANEL	EACH	2		2
73600200	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	FOOT	64		64
73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	2		2
73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	12.2		12.2
73302170	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE II-C-A (36" X 5'-6")	FOOT	60		60
73301840	OVERHEAD SIGN STRUCTURE WALKWAY, CANTILEVER, TYPE A	FOOT	28		28
X7330085	FURNISH AND INSTALL SAFETY CHAIN	EACH	4		4
X5090100	FURNISH AND INSTALL HANDRAIL	FOOT	28		28
X7200095	FURNISH AND ERECT SIGN PANEL	SQ FT	168		168
X0321984	SIGN LIGHTING UNIT COMPLETE	EACH	2		2

FILE NAME =	USER NAME = patelj	DESIGNED - YOGESH PATEL	REVISED -
at:\pw_work\p\dot\patelj\08257844\0346	77-Sign Truss-shr-details.DGN	DRAWN - YOGESH PATEL	REVISED -
	PLOT SCALE = 1/8" = 1'-0" / IN.	CHECKED -	REVISED -
	PLOT DATE = Mar 14, 2011 - 01:50:21 PM	DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES

SCALE: _____ SHEET NO. 1 OF 1 SHEETS STA. _____ TO STA. _____

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
I-80	D-3 OVD SIGN STR REPL 12-04	BUREAU	17	3
ILLINOIS			CONTRACT NO. 46177	