* SPECIALTY ITEM

URBAN

	SUMMARY OF QUANTITIES			CONSTRUCTION CODE																								
				0003	0008	0021																		0021	0040		0043
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	21A	23	24	25
* 81400100	HANDHOLE	EACH	92			5	7	5	6	8	4	4	5	4	4	4	3	4		7	5	8	9					
* 81400200	HEAVY-DUTY HANDHOLE	EACH	31			1	4	2	2	4	4	2	4	2	2	3					1							
* 81400300	DOUBLE HANDHOLE	EACH	29			1	3	2	1	4	2	2	3	2	2	2	3			1	1							
* 81603090	UNIT DUCT, 600V, 3-1C NO.4, 1/C NO.6 GROUND, (XLP-TYPE USE), 1 1/4" DIA. POLYETHYLENE	FOOT	18,155																					3,416	14,739			
* 81603115	UNIT DUCT, 600V, 3-1C NO.1, 1/C NO.1 GROUND, (XLP-TYPE USE), 2" DIA. POLYETHYLENE	FOOT	2,373																					2,373				
* 81800290	AERIAL CABLE, 3-1/C NO. 1/0 WITH MESSENGER WIRE	FOOT	2,626																					2,626				
* 81800415	AERIAL CABLE, 4-1/C NO. 6 WITH MESSENGER WIRE	FOOT	2,395																					2,395				
* 81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	39,735			663	804	581	718	1095	573	984	928	670	660	429	371	279		613	563	6574	7226	4842	10,962			
* 82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	4																						4			
* 82102400	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 400 WATT	EACH	141																					76	65			
* 83050810	LIGHT POLE, ALUMINUM, 47.5 FT. M.H., 15 FT. MAST ARM	EACH	89																					24	65			
* 83057350	LIGHT POLE, WOOD, 60 FOOT, CLASS 4	EACH	5																					5				
* 83057355	LIGHT POLE, WOOD, 60 FOOT, CLASS 4, WITH 15FT MAST ARM	EACH	32																					32				
* 83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	930																					240	690			
* 83800105	BREAKAWAY DEVICE, TRANSFORMER BASE, 11.5 INCH BOLT CIRCLE	EACH	4																						4			
* 83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	89																					24	65			
* 84100110	REMOVAL OF TEMPORARY LIGHTING UNIT	EACH	41																					41				
* 84200500	REMOVAL OF LIGHTING UNIT, SALVAGE	EACH	42																					42				
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	4																		4							
* 85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	12			1	1	1	1	1	1	1	1	1	1	1					1							
* 85700305	FULL-ACTUATED CONTROLLER AND TYPE V CABINET, SPECIAL	EACH	2														1			1								
* 86000105	MASTER CONTROLLER (SPECIAL)	EACH	2																			1	1					
* 86400100	TRANSCEIVER-FIBER OPTIC	EACH	14			1	1	1	1	1	1	1	1	1	1	1	1			1	1							
* 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	12,511				2516	1232	427	596		1459	1753	1493	1480	1555												
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	25,573			280	4437	1769	1026	2212	1804	1914	2938	1865	1879	1965	930	306		417	1831							
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	32,932			1561	4335	1049	2001	3768	1333	2211	3161	1290	1788	1488	2015	3225		1624	2083							

Rev. 6-8-11

Rev.

PATRICK ENGINEERING INC.
4970 VARSITY DRIVE
LISLE, IL 60532
patrickengineering.com

USER NAME = Rdwy_Lisle	DESIGNED -	REVISED -
PLOT CONFIG= PDF(Grey_Largel.plt	DRAWN -	REVISED -
PLOT SCALE = 1:50	CHECKED -	REVISED -
PLOT DATE = 12/3/2010	DATE - 12/3/2010	REVISED -

Illinois Department of Transportation

ILLINOIS ROUTE 53
SUMMARY OF QUANTITIES

SCALE: NA | SHEET S00-11 OF 20 | STA. | TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2578	532B	DUPAGE	781	14

CONTRACT NO. 60477

FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT

q:\dot\9356_e0_(i153)\drawings\cadd sheets\D19139797-sht-S00_004-023.dgn