

SUMMARY OF QUANTITIES
INTERSTATE 55 (I-55) AT CENTRAL AVENUE

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	FUNDING BREAKDOWN - 90% FEDERAL, 10% STATE													
				URBAN		L01 ACIM		LIC ACBWT		L01 ACIM		LIC ACBWT		L01 ACIM			
				ROAD 0003	LAND SCAPE 0003	BRIDGE SNO16-0724	BRIDGE SNO16-3240	BRIDGE SNO16-3241	RETAIN WALLS 0040	LIGHT-ING 0021	TRAF. SIGNAL 0021	ROAD 0003	LAND SCAPE 0003	BRIDGE SNO16-0724	BRIDGE SNO16-3240	BRIDGE SNO16-3241	RETAIN WALLS 0040
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	388		388												
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	174		174												
20101000	TEMPORARY FENCE	FOOT	200	200													
20101100	TREE TRUNK PROTECTION	EACH	19		19												
20200100	EARTH EXCAVATION	CU YD	13225	13225													
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	1345	1345													
20800150	TRENCH BACKFILL	CU YD	512	512													
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	46421		46421												
25000210	SEEDING, CLASS 2A	ACRE	10		10												
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	900		900												
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	900		900												
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	900		900												
25000750	MOWING	ACRE	10		10												
25100115	MULCH, METHOD 2	ACRE	10		10												
25100630	EROSION CONTROL BLANKET	SQ YD	46421		46421												
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	1000		1000												
28000305	TEMPORARY DITCH CHECKS	EACH	42		42												
28000510	INLET FILTERS	EACH	149		149												
28100107	STONE RIPRAP, CLASS A4	SQ YD	288	10			278										
28200200	FILTER FABRIC	SQ YD	306				306										
31101200	SUB-BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	2318.0		2318												
31101400	SUBBASE GRANULAR MATERIAL, TYPE B 6"	SQ YD	2872		2872												
31200502	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4 1/2"	SQ YD	37089		37089												
35101500	AGGREGATE BASE COURSE, TYPE B	CU YD	308		308												
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	7.4		7.4												
40600895	CONSTRUCTING TEST STRIP	EACH	3		3												
40603085	HOT-MIX ASPHALT BINDER COURSE, IL 19.0, N70	TON	1924		1924												
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	221		221												

* - INDICATES SPECIALTY ITEM
 ** - SEE BILL OF MATERIALS FOR INDIVIDUAL RETAINING WALL QUANTITIES
 Δ - NON-PARTICIPATING (100% STATE)

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	FUNDING BREAKDOWN - 90% FEDERAL, 10% STATE													
				URBAN		L01 ACIM		LIC ACBWT		L01 ACIM		LIC ACBWT		L01 ACIM			
				ROAD 0003	LAND SCAPE 0003	BRIDGE SNO16-0724	BRIDGE SNO16-3240	BRIDGE SNO16-3241	RETAIN WALLS 0040	LIGHT-ING 0021	TRAF. SIGNAL 0021	ROAD 0003	LAND SCAPE 0003	BRIDGE SNO16-0724	BRIDGE SNO16-3240	BRIDGE SNO16-3241	RETAIN WALLS 0040
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	1928	1928													
42000521	PORTLAND CEMENT CONCRETE PAVEMENT 11" (JOINTED)	SQ YD	24176	24176													
42000570	PORTLAND CEMENT CONCRETE PAVEMENT 15" (JOINTED)	SQ YD	4768	4768													
42001300	PROTECTIVE COAT	SQ YD	38676	38676													
42001420	BRIDGE APPROACH PAVEMENT CONNECTOR (PCC)	SQ YD	3650	3650													
42100390	CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVEMENT, 15"	SQ YD	3181	3181													
42100615	PAVEMENT REINFORCEMENT	SQ YD	6831	6831													
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	2768	2768													
42400800	DETECTABLE WARNINGS	SQ FT	232	232													
44000100	PAVEMENT REMOVAL	SQ YD	21065	21065													
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SQ YD	19443	19443													
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	6586	6586													
44000600	SIDEWALK REMOVAL	SQ FT	2582	2582													
44004250	PAVED SHOULDER REMOVAL	SQ YD	15,267	15,267													
44200614	CLASS A PATCHES, TYPE IV, 13 INCH	SQ YD	54	54													
44213000	PATCHING REINFORCEMENT	SQ YD	54	54													
44213204	TIE BARS 3/4"	EACH	18	18													
48101500	AGGREGATE SHOULDERS, TYPE B 6"	SQ YD	1035	1035													
50101500	REMOVAL OF EXISTING SUPERSTRUCTURES	EACH	1				1										
50102400	CONCRETE REMOVAL	CU YD	2255			1489.5	182.4	469.7	113.4								
50104000	BRIDGE RAIL REMOVAL	FOOT	6531.7			3767.3	1292.4	953.0	319.0								
50157300	PROTECTIVE SHIELD	SQ YD	11209.5			1681.1	3886.3	5642.1									
50200100	STRUCTURE EXCAVATION	CU YD	11,238.3			9135.3	124.6	956.0	1023.0								
50200300	COFFERDAM EXCAVATION	CU YD	927				927										

TYLIN INTERNATIONAL	USER NAME = #USER#	DESIGNED - AZ	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	CENTRAL AVENUE OVER I-55 SUMMARY OF QUANTITIES			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = #SCALE#	DRAWN - AZ	REVISED -		I-55	0711.2R & 1011.1BR	COOK	741	4			
	PLOT DATE = 4/29/2011	CHECKED - DMJ	REVISED -		SCALE: NONE	SHEET NO. OF SHEETS	STA. TO STA.	CONTRACT NO. 60999				
		DATE - 03/25/2011	REVISED -		FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT					