

SUMMARY OF QUANTITIES  
INTERSTATE 55 (I-55) AT CENTRAL AVENUE

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	FUNDING BREAKDOWN - 90% FEDERAL, 10% STATE						
				ROAD 0003	*** 0003	BRIDGE SNO16-0724-0013	BRIDGE SNO16-3240-0013	BRIDGE SNO16-3241-0013	RETAIN WALLS 0040	LIGHT-ING 0021
X2070304	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	1412				342	1070		
X2130010	EXPLORATION TRENCH, SPECIAL	FOOT	300	300						
X4400198	CONCRETE BARRIER REMOVAL (SPECIAL)	FOOT	1801	1801						
X4403300	CONCRETE MEDIAN REMOVAL	SO FT	306	306						
X5080600	MECHANICAL SPLICERS	EACH	675		308	34	96	237		
X5200220	FINGER PLATE EXPANSION JOINT, 6" (ERECT ONLY)	FOOT	116			116				
X6013700	PIPE UNDERDRAIN REMOVAL (SPECIAL)	FOOT	7351	7351						
X6022810	MANHOLES, SANITARY, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2		2					
X6370159	CONCRFTE BARRIER, SINGLE FACE, 32 INCH HEIGHT (SPECIAL)	FOOT	989	989						
X6640300	CHAIN LINK FENCE REMOVAL	FOOT	3046	3046						
X6700410	ENGINEER'S FIELD OFFICE, TYPE A, (SPECIAL)	CAL MO	18	18						
X6700600	ENGINEER'S FIELD LABORATORY (SPECIAL)	CAL MO	18	18						
X7010216	TRAFFIC CONTROL AND PROTECTION (SPECIAL) -	L SUM	1	1						
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1						
X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	548	548						
X7030025	WET REFLECTIVE TEMPORARY TAPE TYPE III - LETTERS AND SYMBOLS	SO FT	2	1680						
X7030030	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 IN	FOOT	126471	126471						
X7030035	WET REFLECTIVE TEMPORARY TAPE TYPE III, 5 IN	FOOT	15330	15330						
X7030040	WET REFLECTIVE TEMPORARY TAPE TYPE III, 6 IN	FOOT	7798	7798						
X7030045	WET REFLECTIVE TEMPORARY TAPE TYPE III, 8 IN	FOOT	14857	14857						
X7030050	WET REFLECTIVE TEMPORARY TAPE TYPE III, 12 IN	FOOT	2205	2205						
X7030055	WET REFLECTIVE TEMPORARY TAPE TYPE III, 24 IN	FOOT	27	27						
X7333100	OVERHEAD SIGN STRUCTURE - MONOTUBE (SPECIAL)	FOOT	165.7						165.7	
X8040310	ELECTRICAL SERVICE DISCONNECT	EACH	2						2	
X8140105	HANDHOLE (SPECIAL)	EACH	7						7	

\* - INDICATES SPECIALTY ITEM  
\*\* - SEE BILL OF MATERIALS FOR INDIVIDUAL RETAINING WALL QUANTITIES  
\*\*\* - 100% CENTRAL STICKNEY SANITARY DISTRICT

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	FUNDING BREAKDOWN - 90% FEDERAL, 10% STATE						
				ROAD 0003	LAND SCAPE 0003	BRIDGE SNO16-0724-0013	BRIDGE SNO16-3240-0013	BRIDGE SNO16-3241-0013	RETAIN WALLS 0040	LIGHT-ING 0021
X8140210	HEAVY-DUTY HANDHOLE (SPECIAL)	EACH	9							9
X8140220	DOUBLE HANDHOLE (SPECIAL)	EACH	5							5
X8140230	HANDHOLE, COMPOSITE CONCRETE (SPECIAL)	EACH	10							10
X8730245	ELECTRIC CABLE IN CONDUIT, NO. 18, 2 PAIR TWISTED, SHIELDED	FOOT	1239							1239
X8808120	OPTICALLY PROGRAMMED SIGNAL HEAD, LED, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	4							4
X8850102	INDUCTION LOOP	FOOT	312							312
X8950130	MODIFY EXISTING LIGHTING CONTROLLER	EACH	1							1
Z0001050	AGGREGATE SUBGRADE 12"	SO YD	38458	38458						
Z0001899	JACK AND REMOVE EXISTING BEARINGS	EACH	63			31	32			
Z0001904	STRUCTURAL STEEL REMOVAL	L SUM	1			0.55	0.45			
Z0001905	STRUCTURAL STEEL REPAIR	POUND	45090				45090			
Z0003802	REMOVAL OF EXISTING BEARINGS	EACH	96			30	66			
Z0004552	APPROACH SLAB REMOVAL	SO YD	1022	1022						
Z0007101	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 1	L SUM	1				1			
Z0007102	CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES NO. 2	L SUM	1				1			
Z0010501	CLEANING AND PAINTING STEEL BRIDGE NO. 1	L SUM	1				1			
Z0010502	CLEANING AND PAINTING STEEL BRIDGE NO. 2	L SUM	1				1			
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SO FT	161				161			
Z0012755	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SO FT	128			40	88			
Z0013797	STABILIZED CONSTRUCTION ENTRANCE	SO YD	900	900						
Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1						
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SO YD	20			20				
Z0016200	DECK SLAB REPAIR (PARTIAL)	SO YD	20			20				

TYLIN INTERNATIONAL	USER NAME = #USERS	DESIGNED - AZ	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	CENTRAL AVENUE OVER I-55 SUMMARY OF QUANTITIES	F.A.T. RTE.	SECTION	COUNTY	TOTAL SHEET NO.
	PLOT SCALE = #SCALE*	DRAWN - AZ	REVISED -			I-55	0711.2R & 1011.1BR	COOK	741 10
	PLOT DATE = 4/29/2011	CHECKED - DMJ	REVISED -	SCALE: NONE	SHEET NO. OF SHEETS STA. TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	CONTRACT NO. 60999	Rev. 4-8-11