

SUMMARY OF QUANTITIES
INTERSTATE 55 (I-55) AT CENTRAL AVENUE

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	FUNDING BREAKDOWN - 90% FEDERAL, 10% STATE															
				ROAD 0003	LAND SCAPE 0003	BRIDGE SNO16-0724 0013	BRIDGE SNO16-3240 0013	BRIDGE SNO16-3241 0013	RETAIN WALLS 0040	LIGHTING 0021	TRAF. SIGNAL 0021								
60201310	CATCH BASINS, TYPE A, 4'- DIAMETER, TYPE 20 FRAME AND GRATE	EACH	6	6															
60218300	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	10	10															
60218400	MANHOLES, TYPE A, 4'- DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	21	21															
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	4	4															
60240328	INLETS, TYPE B, TYPE 24 FRAME AND GRATE	EACH	18	18															
60500040	REMOVING MANHOLES	EACH	11	11															
60500050	REMOVING CATCH BASINS	EACH	4	4															
60500060	REMOVING INLETS	EACH	26	26															
60500105	FILLING MANHOLES	EACH	2	2															
60500305	FILLING INLETS	EACH	10	10															
60603800	COMBINATION CONCRETE CURB AND GUTTER TYPE B-6.12	FOOT	375.0	375															
60605000	COMBINATION CONCRETE CURB AND GUTTER TYPE B-6.24	FOOT	5537.0	5537															
60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQ FT	2059	2059															
60624600	CORRUGATED MEDIAN	SQ FT	152	152															
63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	1563	1563															
63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	4	4															
63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	2	2															
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	1	1															
63100169	TRAFFIC BARRIER TERMINAL, TYPE 1, (SPECIAL) FLARED	EACH	5	5															
63200310	GUARDRAIL REMOVAL	FOOT	1446	1446															
63500105	DELINEATORS	EACH	46	46															

* - INDICATES SPECIALTY ITEM
** - SEE BILL OF MATERIALS FOR INDIVIDUAL RETAINING WALL QUANTITIES

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	FUNDING BREAKDOWN - 90% FEDERAL, 10% STATE															
				ROAD 0003	LAND SCAPE 0003	BRIDGE SNO16-0724 0013	BRIDGE SNO16-3240 0013	BRIDGE SNO16-3241 0013	RETAIN WALLS 0040	LIGHTING 0021	TRAF. SIGNAL 0021								
63801200	MODULAR GLARE SCREEN SYSTEM	FOOT	10890	10890															
64200105	SHOULDER RUMBLE STRIPS	FOOT	16904	16904															
66400305	CHAIN LINK FENCE, 6'	FOOT	1663	1663															
66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	1500	1500															
66900210	HAZARDOUS WASTE DISPOSAL	CU YD	400	400															
66900450	SPECIAL WASTE PLANS AND REPORTS	L SUM	1	1															
66900530	SOIL DISPOSAL ANALYSIS	EACH	6	6															
67100100	MOBILIZATION	L SUM	1	1															
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	548	548															
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	84	84															
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	9645	9645															
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	73337	73337															
70400100	TEMPORARY CONCRETE BARRIER	FOOT	9650	9650															
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	28520	28520															
70400500	TEMPORARY CONCRETE BARRIER, STATE OWNED	FOOT	2515	2515															
70400600	RELOCATE TEMPORARY CONCRETE BARRIER, STATE OWNED	FOOT	7570	7570															
* 72000100	SIGN PANEL - TYPE 1	SO FT	468	468															
* 72000200	SIGN PANEL - TYPE 2	SO FT	192	192															
* 72000300	SIGN PANEL - TYPE 3	SO FT	80	80															
* 72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	11	11															
* 72400200	REMOVE SIGN PANEL ASSEMBLY - TYPE B	EACH	5	5															
* 72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	124	124															
* 72400320	REMOVE SIGN PANEL - TYPE 2	SQ FT	56	56															
* 72400330	REMOVE SIGN PANEL - TYPE 3	SQ FT	40	40															
* 72700200	TUBULAR STEEL SIGN SUPPORT - BREAKAWAY	POUND	322	322															
* 72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	60	60															
* 73000100	WOOD SIGN SUPPORT	FOOT	118	118															

* - INDICATES SPECIALTY ITEM

TYLIN INTERNATIONAL	USER NAME = #USER#	DESIGNED - AZ	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	CENTRAL AVENUE OVER I-55 SUMMARY OF QUANTITIES			F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = #SCALE#	DRAWN - AZ	REVISED -		1-55	0711.2R & 1011.1BR	COOK	741	6			
	PLOT DATE = 4/29/2011	CHECKED - DMJ	REVISED -		SCALE: NONE	SHEET NO. OF SHEETS	STA. TO STA.	CONTRACT NO. 60999				
						FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		Rev.		