

SUMMARY OF QUANTITIES
INTERSTATE 55 (I-55) AT CENTRAL AVENUE

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	FUNDING BREAKDOWN - 90% FEDERAL, 10% STATE								
				ROAD 0003	LAND SCAP 0003	BRIDGE SNO16-0724 0013	BRIDGE SNO16-3240 0013	BRIDGE SNO16-3241 0013	RETAIN WALLS 0040	LIGHT-ING 0021	TRAF. SIGNAL 0021	
* 73100100	BASE FOR TELESCOPING STEEL SIGN SUPPORT	EACH	6	6								
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	40562	40562								
* 78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	11112	11112								
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	601	601								
* 78008200	POLYUREA PAVEMENT MARKING TYPE I -	50 FT	1683	1683								
	LETTERS AND SYMBOLS											
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	81812	81812								
* 78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	7589	7589								
* 78008240	POLYUREA PAVEMENT MARKING TYPE I - LINE 8"	FOOT	16518	16518								
* 78008250	POLYUREA PAVEMENT MARKING TYPE I - LINE 12"	FOOT	9413	9413								
* 78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	417	417								
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	826	826								
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	47	47								
* 78100200	TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER	EACH	194	194								
* 78200100	MONODIRECTIONAL PRISMATIC BARRIER REFLECTOR	EACH	2905	2905								
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	26	26								
* 78200520	BARRIER WALL MARKERS, TYPE B	EACH	107	107								
* 78201000	TERMINAL MARKERS - DIRECT APPLIED	EACH	6	6								
78300100	PAVEMENT MARKING REMOVAL	50 FT	30361	30361								
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	873	873								
* 80500020	SERVICE INSTALLATION - POLE MOUNTED	EACH	1								1	
* 81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	343								343	
* 81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	76								76	
* 81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	355								355	
* 81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	166							71	95	
* 81021370	CONDUIT PUSHED, 4" DIA., PVC	FOOT	71							71		
* 81100320	CONDUIT ATTACHED TO STRUCTURE, 1" DIA.,	FOOT	1358							1358		
	PVC COATED GALVANIZED STEEL											

* - INDICATES SPECIALTY ITEM
** - SEE BILL OF MATERIALS FOR INDIVIDUAL RETAINING WALL QUANTITIES

CODE NUMBER	PAY ITEM	UNIT	TOTAL QUANTITY	FUNDING BREAKDOWN - 90% FEDERAL, 10% STATE								
				ROAD 0003	LAND SCAP 0003	BRIDGE SNO16-0724 0013	BRIDGE SNO16-3240 0013	BRIDGE SNO16-3241 0013	RETAIN WALLS 0040	LIGHT-ING 0021	TRAF. SIGNAL 0021	
* 81100600	CONDUIT ATTACHED TO STRUCTURE, 2" DIA.,	FOOT	1452									1452
	GALVANIZED STEEL											
* 81100605	CONDUIT ATTACHED TO STRUCTURE, 2" DIA.,	FOOT	1507								1155	352
	PVC COATED GALVANIZED STEEL											
* 81100705	CONDUIT ATTACHED TO STRUCTURE, 2 1/2" DIA.,	FOOT	30								30	
	PVC COATED GALVANIZED STEEL											
* 81100805	CONDUIT ATTACHED TO STRUCTURE, 3" DIA.,	FOOT	126									126
	PVC COATED GALVANIZED STEEL											
* 81101005	CONDUIT ATTACHED TO STRUCTURE, 4" DIA.,	FOOT	1305									1305
	PVC COATED GALVANIZED STEEL											
* 81200210	CONDUIT EMBEDDED IN STRUCTURE, 1" DIA., PVC	FOOT	40								40	
* 81200230	CONDUIT EMBEDDED IN STRUCTURE, 2" DIA., PVC	FOOT	1260								30	1230
* 81200240	CONDUIT EMBEDDED IN STRUCTURE 2 1/2" DIA., PVC	FOOT	3743								2380	1363
* 81300220	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO	EACH	22								22	
	STRUCTURE, 6" X 6" X 4"											
* 81300550	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO	EACH	35								33	2
	STRUCTURE, 12" X 12" X 6"											
* 81300710	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO	EACH	6								6	
	STRUCTURE, 16" X 12" X 6"											
* 81300945	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO	EACH	2									2
	STRUCTURE, 24" X 24" X 8"											
* 81400100	HANDHOLE	EACH	1									1
* 81603050	UNIT DUCT, 600V, 3-1C NO.6 1/C NO.8 GROUND,	FOOT	170								170	
	(XLP-TYPE USE), 1" DIA POLYETHYLENE											
* 81603080	UNIT DUCT, 600V, 3-1C NO.2 1/C NO.4 GROUND,	FOOT	170								170	
	(XLP-TYPE USE), 1 1/4" DIA POLYETHYLENE											
* 81702110	ELECTRIC CABLE IN CONDUIT, 600V (XLP-TYPE USE)	FOOT	5605								5605	
	1/C NO. 10											

TYLIN INTERNATIONAL	USER NAME = #USER#	DESIGNED - AZ	REVISED -
	PLOT SCALE = #SCALE#	DRAWN - AZ	REVISED -
	PLOT DATE = 4/29/2011	CHECKED - DMJ	REVISED -
		DATE - 03/25/2011	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

CENTRAL AVENUE OVER I-55 SUMMARY OF QUANTITIES			
SCALE: NONE	SHEET NO. OF SHEETS	STA. TO STA.	

F.A.I. RTE. I-55	SECTION 0711.2R & 1011.1BR	COUNTY COOK	TOTAL SHEETS 741	SHEET NO. 7
FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT			CONTRACT NO. 60999	