

REMOVALS - COMB CONC CURB & GUTTER AND MEDIAN

LOCATION	STATION		OFFSET	COMB CURB GUTTER REM (FOOT)	MEDIAN REMOVAL (SQ FT)
	FROM	TO			
CENTRAL AVE	09+99.8	13+28.9	LT	330	
CENTRAL AVE	09+99.8	13+60.4	RT	361	
RAMP 1	186+80.9	194+71.2	LT	805	
RAMP 1	186+79.9	194+71.2	RT	798	
RAMP 2	368+71.4	394+96.1	LT	833	
RAMP 2	368+73.3	394+96.4	RT	828	
RAMP 3	204+08.9	210+73.7	LT	671	
RAMP 3	204+08.9	210+75.1	RT	666	
RAMP 4	405+28.8	411+69.8	LT	648	
RAMP 4	405+28.8	411+69.0	RT	646	
CENTRAL AVE	11+57.1	13+44.7			189
TOTAL				6586	189

GUARDRAIL REMOVAL

LOCATION	STATION		OFFSET	GUARDRAIL REMOVAL (FOOT)
	FROM	TO		
RAMP 1	179+19.0	181+30.5	LEFT	213
RAMP 1	189+46.8	190+20.8	RIGHT	74
RAMP 3	217+48.2	220+69.7	RIGHT	322
RAMP 4	410+59.2	413+32.6	LEFT	274
RAMP 4	417+61.0	419+60.2	RIGHT	200
TOTAL				1082

REMOVAL SIGNING SCHEDULE

ALIGNMENT	SIGN INFORMATION			SIGN DESCRIPTION
	STATION	OFFSET	SUPPORT	
CENTRAL AVE	10+32	44.0' RT	LIGHT POLE	W8-5 MODIFIED
CENTRAL AVE	11+82	44.0' RT	LIGHT POLE	M2-1
	SAME AS ABOVE			M1-1
CENTRAL AVE	12+87	44.0' LT	LIGHT POLE	W3-3
	SAME AS ABOVE			W16-8
CENTRAL AVE	13+32	44.0' RT	LIGHT POLE	R8-3a
CENTRAL AVE	14+37	44.0' LT	LIGHT POLE	R2-1
CENTRAL AVE	14+81	44.0' RT	LIGHT POLE	M3-3
	SAME AS ABOVE			M1-1
	SAME AS ABOVE			M5-1R
CENTRAL AVE	16+31	44.0' RT	LIGHT POLE	M3-1
	SAME AS ABOVE			M1-1
	SAME AS ABOVE			M5-1L
CENTRAL AVE	17+53	44.0' LT	MAST ARM	R3-8
CENTRAL AVE	18+03	44.0' RT	SIGNAL POST	M3-1
	SAME AS ABOVE			M1-1
	SAME AS ABOVE			M6-1R
	SAME AS ABOVE			M3-1
	SAME AS ABOVE			M1-1
	SAME AS ABOVE			M6-1L
CENTRAL AVE	18+90	44.0' LT	LIGHT POLE	R5-1
CENTRAL AVE	19+01	43.8' LT	SIGNAL POST	R3-1
	SAME AS ABOVE			R3-2
CENTRAL AVE	19+32	43.6' RT	MAST ARM	R3-8
CENTRAL AVE	19+90	42.3' RT	POST	R3-8
	SAME AS ABOVE			R8-3a
CENTRAL AVE	20+71	43.6' RT	SIGNAL POST	R3-1
	SAME AS ABOVE			R3-2
CENTRAL AVE	20+83	44.0' RT	LIGHT POLE	R5-1
CENTRAL AVE	21+33	0.0' RT	SIGNAL POST	R3-2
CENTRAL AVE	21+56	44.5' LT	LIGHT POLE	M3-1
	SAME AS ABOVE			M1-1
	SAME AS ABOVE			M6-1L
CENTRAL AVE	21+59	44.5' LT	SIGNAL POST	M3-1
	SAME AS ABOVE			M1-1
	SAME AS ABOVE			M6-1R
CENTRAL AVE	22+07	44.5' RT	SIGNAL POST	R3-1
CENTRAL AVE	24+42	44.7' LT	LIGHT POLE	R3-8
CENTRAL AVE	25+72	44.5' LT	LIGHT POLE	M1-1
	SAME AS ABOVE			M3-1
	SAME AS ABOVE			M6-1L
CENTRAL AVE	27+02	44.5' LT	LIGHT POLE	M1-1
	SAME AS ABOVE			M3-1
	SAME AS ABOVE			M6-1R
CENTRAL AVE	28+84	44.5' LT	LIGHT POLE	R3-5
CENTRAL AVE	30+63	44.5' LT	LIGHT POLE	RIGHT TURN LANE
RAMP 1	184+92	14.3' RT	POST	W13-3
RAMP 1	186+78	20.8' LT	POST	E5-1a (EXIT 285)
RAMP 1	189+45	14.2' RT	POST	I-5
O.O	SAME AS ABOVE			M6-1R
O.O	SAME AS ABOVE			RACE TRACK
RAMP 1	190+22	16.3' RT	POST	R3-8 MODIFIED
RAMP 1	197+46	23.2' RT	POST	R5-1a
RAMP 1	198+87	26.0' RT	SIGNAL POST	R5-1
RAMP 2	386+71	20.6' RT	POST	W4-1
RAMP 2	399+16	23.5' LT	POST	R5-1100
RAMP 2	399+32	26.1' LT	POST	M3-3
	SAME AS ABOVE			M1-1
	SAME AS ABOVE			M6-1L
RAMP 3	200+68	25.9' RT	SIGNAL POST	R5-1100
RAMP 3	210+76	23.0' LT	POST	W4-1
RAMP 4	401+13	26.1' LT	SIGNAL POST	R5-1
	SAME AS ABOVE			R3-5R
RAMP 4	402+36	23.0' LT	POST	R5-1a
RAMP 4	402+36	20.9' RT	POST	R5-1a
RAMP 4	413+40	8.0' LT	POST	I-5
	SAME AS ABOVE			M6-1R
	SAME AS ABOVE			RACE TRACK
RAMP 4	415+27	4.0' LT	POST	W13-3

SIDEWALK REMOVAL

LOCATION	STATION		OFFSET	SIDEWALK REM (SQ FT)
	FROM	TO		
CENTRAL AVE	09+99.8	13+28.1	LEFT	1205
CENTRAL AVE	09+99.8	13+61.1	RIGHT	1376
TOTAL				2582

SHOULDER REMOVAL

LOCATION	STATION		OFFSET	HMA SHOULDER REM (SQ YD)	PCC SHOULDER REMOVAL (SQ YD)
	FROM	TO			
RAMP 1	178+23.0	186+79.9	RIGHT	769	
RAMP 1	183+23.7	186+90.5	LEFT	427	
RAMP 1	186+80.5	194+71.2	RIGHT		684
RAMP 1	186+80.9	194.71.2	LEFT		314
RAMP 2	367+84.1	386+70.5	LEFT	2111	
RAMP 2	377+29.7	386+84.1	RIGHT	928	
RAMP 2	386+74.3	394+96.1	RIGHT		326
RAMP 2	386+71.0	394+96.1	LEFT		746
I-55	610+44.4	610+57.5	RIGHT	19	
I-55	612+00.1	612+91.9	RIGHT	130	
I-55	613+61.1	619+00.0	RIGHT	765	
I-55	611+51.1	611+64.2	LEFT	10	
I-55	613+03.3	621+05.4	LEFT	415	
RAMP 3	204+08.9	210+73.7	LEFT		269
RAMP 3	204+08.9	210+75.2	RIGHT		613
RAMP 3	210+65.2	221+71.8	LEFT	1244	
RAMP 3	210+75.2	230+16.3	RIGHT	2079	
RAMP 4	405+28.8	411+69.8	LEFT		591
RAMP 4	405+28.8	411+69.0	RIGHT		261
RAMP 4	411+59.4	414+90.3	RIGHT	372	
RAMP 4	411+69.8	420+56.8	LEFT	942	
TOTAL				10211	3805

PIPE UNDERDRAIN REMOVAL SCHEDULE

LOCATION	STATION	OFFSET	STATION	OFFSET	LENGTH
Ramp 1	593+68.0	77.6 RT	181+24.5	2.9 RT	291.7
Ramp 1	181+17.1	8.9 RT	186+60.4	10.2 RT	546.8
Ramp 2	367+43.8	10.2 LT	370+71.9	18.7 LT	330.6
Ramp 2	370+68.7	8.6 LT	371+80.4	14.7 LT	113.5
Ramp 2	371+83.9	14.5 LT	372+69.9	8.6 LT	89.1
Ramp 2	372+73.8	14.7 LT	377+84.7	8.2 LT	511.9
Ramp 2	377+83.1	17.8 LT	382+21.4	9.6 LT	442.0
Ramp 2	382+30.0	14.0 LT	386+47.1	14.5 LT	418.2
Ramp 3	211+14.0	12.8 RT	215+63.8	14.4 RT	451.5
Ramp 3	215+63.8	12.8 RT	228+82.8	10.9 RT	1314.4
Ramp 4	411+62.9	12.3 LT	419+88.0	11.7' LT	828.2
I-55	610+44.4	68.89' RT	610+48.5	68.9' RT	4.1
I-55	610+55.7	77.49' RT	610+62.1	68.1' RT	11.4
I-55	610+35.4	68.13' RT	612+00.0	68.1' RT	222.8
I-55	612+60.6	77.49' RT	613+54.7	68.2' RT	106.4
I-55	613+61.1	68.24' RT	617+52.8	68.5' RT	391.7
I-55	617+55.3	77.46' RT	619+00.0	68.7' RT	148.0
I-55	613+03.3	69.26' LT	613+11.8	69.3' LT	8.5
I-55	611+41.6	73.40' LT	621+00.4	69.2' LT	960.0
I-55	621+00.0	73.49' LT	621+05.4	69.2' LT	7.5
I-55	615+16.1	03.66' RT	615+43.7	28.5' RT	37.1
I-55	615+15.1	00.33' LT	615+40.2	28.9' LT	38.0
I-55	616+46.4	01.94' RT	616+76.9	29.3' RT	40.9
I-55	616+47.9	01.74' LT	616+72.1	29.3' LT	36.7
TOTAL					7351

PAVEMENT REMOVAL

LOCATION	STATION		PAVEMENT REM (SQ YD)
	FROM	TO	
CENTRAL AVE	09+99.2	13+28.9	3018
RAMP 1	181+49.7	194+71.2	3166
RAMP 2	369+46.7	394+96.1	4959
I-55 - NB MED	614+89.5	615+14.7	36
I-55 - SB MED	614+93.4	615+23.6	43
I-55 - NB MED	616+37.3	616+61.2	34
I-55 - SB MED	616+39.5	616+64.4	31
RAMP 3	204+08.9	229+21.9	4551
RAMP 4	405+28.8	417+53.6	2703
I-55 TEMPORARY PAVEMENT (INTERSTATE)	-	-	2318
TOTAL			20860

TYLIN INTERNATIONAL	USER NAME = #USER#	DESIGNED - AZ	REVISED -
	PLOT SCALE = #SCALE#	DRAWN - AZ	REVISED -
	PLOT DATE = 4/28/2011	CHECKED - DMJ	REVISED -
		DATE - 03/25/2011	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

CENTRAL AVENUE OVER I-55 SCHEDULE OF QUANTITIES, REMOVAL ITEMS			
SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1555	CENTRAL AVE & I-55	COOK	741	22
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT			CONTRACT NO. 60999	