

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE						SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE								
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 0004	0021 SIGNAL	0021 LIGHTING				CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 0004	0021 SIGNAL	0021 LIGHTING				
20200100	EARTH EXCAVATION	CU YD	1125	1125						54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	2	2						
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	570	570						542A1053	PIPE CULVERTS, CLASS A, TYPE 2 8"	FOOT	12	12						
20400800	FURNISHED EXCAVATION	CU YD	320	320						542A1057	PIPE CULVERTS, CLASS A, TYPE 2 12"	FOOT	170	170						
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	4620	4620						542A1060	PIPE CULVERTS, CLASS A, TYPE 2 15"	FOOT	100	100						
25000210	SEEDING, CLASS 2A	ACRE	1	1						542A1063	PIPE CULVERTS, CLASS A, TYPE 2 18"	FOOT	20	20						
25000310	SEEDING, CLASS 4	ACRE	0.2	0.2						542A1069	PIPE CULVERTS, CLASS A, TYPE 2 24"	FOOT	30	30						
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	90	90						542A1903	PIPE CULVERTS, CLASS A, TYPE 3 18"	FOOT	120	120						
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	90	90						542A1921	PIPE CULVERTS, CLASS A, TYPE 3 36"	FOOT	10	10						
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	90	90						60100060	CONCRETE HEADWALL FOR PIPE DRAINS	EACH	3	3						
25100630	EROSION CONTROL BLANKET	SO YD	4620	4620						60107600	PIPE UNDERDRAINS 4"	FOOT	1000	1000						
25100900	TURF REINFORCEMENT MAT	SO YD	725	725						60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	50	50						
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	100	100						60200805	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 8 GRATE	EACH	2	2						
28000305	TEMPORARY DITCH CHECKS	FOOT	500	500						60201340	CATCH BASINS, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	6	6						
28000400	PERIMETER EROSION BARRIER	FOOT	3000	3000						60204505	CATCH BASINS, TYPE A, 5'-DIAMETER, TYPE 8 GRATE	EACH	1	1						
28000510	INLET FILTERS	EACH	40	40						60218400	MANHOLES, TYPE A, 4' DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1						
31200502	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4 1/2"	SO YD	500	500						60250200	CATCH BASINS TO BE ADJUSTED	EACH	2	2						
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SO YD	20	20						60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	2	2						
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	3	3						60500050	REMOVING CATCH BASINS	EACH	1	1						
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SO YD	2000	2000						60500060	REMOVING INLETS	EACH	1	1						
42001300	PROTECTIVE COAT	SO YD	8000	8000						60500080	REMOVING CATCH BASINS TO MAINTAIN FLOW	EACH	6	6						
44000100	PAVEMENT REMOVAL	SO YD	330	330						60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	1000	1000						
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1000	1000						60618740	CONCRETE MEDIAN, TYPE M-2.12	SO FT	1800	1800						
44003100	MEDIAN REMOVAL	SO FT	13,275	13,275						60619600	CONCRETE MEDIAN, TYPE SB-6.12	SO FT	2200	2200						
44004250	PAVED SHOULDER REMOVAL	SO YD	60	60						60622800	CONCRETE MEDIAN, TYPE SM-6.12	SO FT	1800	1800						
44200970	CLASS B PATCHES, TYPE II, 10 INCH	SO YD	8	8						67100100	MOBILIZATION	L SUM	1	1						
44201299	DOWEL BARS 1 1/2"	EACH	20	20						70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1						
44213200	SAW CUTS	FOOT	54	54						70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1						
48300300	PORTLAND CEMENT CONCRETE SHOULDERS 8"	SO YD	60	60						70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	30	30						
50104400	CONCRETE HEADWALL REMOVAL	EACH	1	1						70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	750	750						
50105220	PIPE CULVERT REMOVAL	FOOT	70	70						* 72400730	RELOCATE SIGN PANEL - TYPE 3	SO FT	150	150						
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	3	3						* 73400100	CONCRETE FOUNDATIONS	CU YD	10	10						
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1	1						* 73502000	RELOCATE GROUND MOUNTED SIGN SUPPORT	EACH	4	4						
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	1	1																

* SPECIALTY ITEMS

FILE NAME =	USER NAME = kellers	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL ROUTE 59 AT US ROUTE 20 SUMMARY OF QUANTITIES	F.A.P. RTE. 338	SECTION 7 HB-K-N	COUNTY COOK	TOTAL SHEETS 82	SHEET NO. 3
PLOT SCALE = 50:0000' / IN.	CHECKED -	REVISED -	SCALE:			SHEET NO. OF SHEETS STA.	TO STA.	FED. ROAD DIST. NO. 1	ILLINOIS FED. AID PROJECT	CONTRACT NO. 60K62
PLOT DATE = 2/22/2011	DATE -	REVISED -								

Rev