



NOTES:

1. A TEMPORARY DITCH CHECK SHALL BE PLACED FOR EACH ONE FOOT DROP IN THE DITCH LINE ELEVATION. TWO TEMPORARY DITCH CHECKS SHALL BE PLACED IN FLOW LINES APPROACHING INLETS AND PIPES. TWO TEMPORARY DITCH CHECKS SHALL BE PLACED AT OUTFALLS OF EXISTING DITCHES TO COLLECT SILT.
2. TURF REINFORCEMENT MATS SHALL BE APPLIED TO ALL SLOPES 3:1 AND STEEPER.

NOTE: CONTRACTOR SHALL NOT STORE ANY MATERIALS OR EQUIPMENT BEYOND PERIMETER OF SILT FENCE

LEGEND

- SILT FENCE
- INLET & PIPE PROTECTION

FILE NAME =	USER NAME = kellers	DESIGNED -	REVISED - 3/16/11 SK
ci:\pw_work\pwidot\kellers\0156271\142389-1\sh-eros.dgn		DRAWN -	REVISED -
PLOT SCALE = 50.0000' / IN.		CHECKED -	REVISED -
PLOT DATE = 3/16/2011		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

EROSION CONTROL PLAN			
IL. RTE. 59 AT U.S. RTE. 20			
F.A.P. RTE. 338	SECTION 7 HB-K-N	COUNTY COOK	TOTAL SHEETS 82
SCALE: 1"=50'	SHEET NO.	OF SHEETS	STA. TO STA.

TOTAL SHEETS 82	SHEET NO. 26
CONTRACT NO. 60K62	
ILLINOIS FED. AID PROJECT	