



**TEMPORARY EROSION CONTROL SEQUENCE OF CONSTRUCTION**

1. ESTABLISH TEMPORARY EROSION CONTROL MEASURES AND ERECT SILT FILTER FENCE ALONG SITE BOUNDRIES PRIOR TO MASS EARTHWORK.
2. INSTALL DITCH CHECKS IMMEDIATELY AFTER DITCH DISTURBANCE STARTS
3. INSTALL PERMANENT SEEDING BEFORE BEGINNING NEXT CONSTRUCTION STAGE.

**PERMANENT DITCH CHECKS**

197+00 LT.  
198+75 RT.  
201+10 RT.  
201+10 LT.

**TEMPORARY DITCH CHECKS**

(LEFT O/S)	(RIGHT O/S)	(LEFT O/S)	(RIGHT O/S)
191+50	192+00	29+30	29+30
192+43	192+42	38+80	30+30
192+58	192+74	51+73	30+90
192+80	193+30	54+50	38+40
193+19	194+16	60+65	53+00
194+05	195+95		56+00
194+80	196+66		60+65
195+50	197+70		
197+12	198+60		
198+00	201+27		
198+75	201+54		
201+25	202+54		
201+50	203+46		
202+50	203+75		
	204+00		
	205+50		
	206+50		
	207+50		

**NOTE:**

PERMANENT DITCH CHECKS WILL BE PAID FOR AT THE CONTRACT UNIT PRICE PER TON FOR AGGREGATE DITCH CHECKS.

INSTALL PERIMETER EROSION BARRIER ALL ALONG R.O.W. & TEMPORARY EASEMENTS.

**LEGEND**

SYMBOL	DESCRIPTION
◆	PERMANENT DITCH CHECK
—	PERIMETER EROSION BARRIER (SILT FENCE, SEE STANDARD 280001)
~	EXISTING FLOW LINE
—	EXIST. R.O.W.
- - -	PROP. R.O.W.

FILE NAME =	USER NAME = abreuah	DESIGNED -	REVISED -
ct:\pw_work\p\dot\abreuah\d0139641\PI1538-sht-erodgn		DRAWN -	REVISED -
	PLOT SCALE = 50.7684' / IN.	CHECKED -	REVISED -
	PLOT DATE = 3/2/2011	DATE -	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**EROSION CONTROL PLAN  
IL. RTE. 38 AT MEREDITH RD.**

SCALE: 1"=50' SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
567	5 R-N-1	KANE	77	24
			CONTRACT NO. 60K65	
ILLINOIS FED. AID PROJECT				