## SUMMARY OF QUANTITIES

| CODE NO | ITEM | UNIT | URBAN TOTAL QUANTITIES | CONSTRUCTION TYPE CODE 0005 80%FED 20%STATE | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 40600200 | BITUMINOUS MATERIALS (PRIME COAT) | TON | 17 | 17 | | | | | |
| 40600300 | AGGREGATE (PRIME COAT) | TON | 82 | 82 | | | | | |
| 40600400 | MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS | TON | 31 | 31 | | | | | |
| X4060826 | POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50 | TON | 842 | 842 | | | | | |
| 40600895 | CONSTRUCTING TEST STRIP | EACH | 1 | 1 | | | | | |
| 40600982 | HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT | SQ YD | 300 | 300 | | | | | |
| 40601005 | HOT-MIX ASPHALT REPLACEMENT OVER PATCHES | TON | 97 | 97 | | | | | |
| 40603340 | HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70 | TON | 1715 | 1715 | | | | | |
| 42001300 | PROTECTIVE COAT | SQ YD | 70 | 70 | | | | | |
| 42400200 | PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH | SQ FT | 337.5 | 337.5 | | | | | |
| 44000158 | HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4" | SQ YD | 20400 | 20400 | | | | | |
| 44000600 | SIDEWALK REMOVAL | SQ FT | 337.5 | 337.5 | | | | | |
| Z0004562 | COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT | FOOT | 225 | 225 | | | | | |
| 44002212 | HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3" | SQ YD | 575 | 575 | | | | | |
| 44201753 | CLASS D PATCHES, TYPE II, 9 INCH | SQ YD | 78 | 78 | | | | | |
| 44201757 | CLASS D PATCHES, TYPE III, 9 INCH | SQ YD | 70 | 70 | | | | | |
| 44201759 | CLASS D PATCHES, TYPE IV, 9 INCH | SQ YD | 348 | 348 | | | | | |
| △ X5539700 | STORM SEWERS TO BE CLEANED | FOOT | 100 | 100 | | | | | |
| 60300305 | FRAMES AND LIDS TO BE ADJUSTED | EACH | 5 | 5 | | | | | |
| X6030310 | FRAMES AND LIDS TO BE ADJUSTED (SPECIAL) | EACH | 52 | 52 | | | | | |
| 67000400 | ENGINEER'S FIELD OFFICE, TYPE A | CAL MO | 6 | 6 | | | | | |
| 67100100 | MOBILIZATION | L SUM | 1 | 1 | | | | | |
| 70102620 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701501 | L SUM | 1 | 1 | | | | | |
| 70102625 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701606 | L SUM | 1 | 1 | | | | | |
| 70102635 | TRAFFIC CONTROL AND PROTECTION, STANDARD 701701 | L SUM | 1 | 1 | | | | | |
| 70300100 | SHORT TERM PAVEMENT MARKING | FOOT | 1650 | 1650 | | | | | |
| 70300210 | TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS | SQ FT | 363 | 363 | | | | | |
| 70300220 | TEMPORARY PAVEMENT MARKING - LINE 4" | FOOT | 3850 | 3850 | | | | | |

## SUMMARY OF QUANTITIES

| CODE NO | ITEM | UNIT | URBAN TOTAL QUANTITIES | CONSTRUCTION TYPE CODE 0005 80%FED 20%STATE | | | | | |
|---|---|---|---|---|---|---|---|---|---|
| 70300240 | TEMPORARY PAVEMENT MARKING - LINE 6" | FOOT | 3100 | 3100 | | | | | |
| 70300280 | TEMPORARY PAVEMENT MARKING - LINE 24" | FOOT | 520 | 520 | | | | | |
| 70301000 | WORK ZONE PAVEMENT MARKING REMOVAL | SQ FT | 185 | 185 | | | | | |
| * 78000100 | THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS | SQ FT | 363 | 363 | | | | | |
| * 78000200 | THERMOPLASTIC PAVEMENT MARKING - LINE 4" | FOOT | 3850 | 3850 | | | | | |
| * 78000400 | THERMOPLASTIC PAVEMENT MARKING - LINE 6" | FOOT | 3100 | 3100 | | | | | |
| * 78000650 | THERMOPLASTIC PAVEMENT MARKING - LINE 24" | FOOT | 520 | 520 | | | | | |
| * 78006100 | PREFORMED THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS | SQ FT | 12.92 | 12.92 | | | | | |
| Z0030850 | TEMPORARY INFORMATION SIGNING | SQ FT | 51.4 | 51.4 | | | | | |
| △ Z0018500 | DRAINAGE STRUCTURES TO BE CLEANED | EACH | 20 | 20 | | | | | |

* Specialty Items

△ NON-PARTICIPATING (100% STATE)

| | | | |
|---|---|---|---|
| FILE NAME = c:\pw_work\pwidot\guilloumefp\d0206478\D161310-sht-plan.dgn | USER NAME = guilloumefp | DESIGNED - | REVISED - |
| | | DRAWN - | REVISED - |
| | PLOT SCALE = 50.0000 ' / IN. | CHECKED - | REVISED - |
| | PLOT DATE = 4/7/2011 | DATE - | REVISED - |

**STATE OF ILLINOIS**
**DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

| F.A.U RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
|---|---|---|---|---|
| 2812 | 2010-034 RS | COOK | 16 | 3 |
| | | CONTRACT NO. 60K88 | | |
| FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT | | |

D161310-sht-plan.dgn 4/7/2011 11:07:10 AM User=guilloumefp