



**PROJECT ENDS
STA. 520 + 13**

**PROJECT BEGINS
STA. 513 + 36.70**

- TEMPORARY EROSION CONTROL
SEQUENCE OF CONSTRUCTION**
- ① ESTABLISH TEMPORARY EROSION CONTROL MEASURES AND ERECT SILT FENCE ALONG SITE BOUNDARIES PRIOR TO MASS EARTHWORK.
 - ② INSTALL DITCH CHECK IMMEDIATELY AFTER DITCH GRADING IS COMPLETE.
 - ③ INSTALL PERMANENT SEEDING BEFORE BEGINNING NEXT CONSTRUCTION STAGE.

FILE NAME = P141309-sht-eros.dgn	USER NAME = banks1	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	U.S. ROUTE 12/IL. ROUTE 59 @ BONNER ROAD EROSION CONTROL PLAN			F.A.P. RTE. 334	SECTION OR-N	COUNTY LAKE	TOTAL SHEETS 40	SHEET NO. 13
	PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -		SCALE: 1" = 50'	SHEET NO.	OF	SHEETS	STA. 507+00.00 TO STA. 522+00.00	CONTRACT NO. 60L20		
	PLOT DATE = 4/4/2011	DATE -	REVISED -		ILLINOIS FED. AID PROJECT							