



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

June 6, 2011

SUBJECT: Various Routes
Section 2010-069-I
Cook & Will Counties
Contract No. 60L54
Item No. 187, June 17, 2011 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Replaced the Schedule of Prices.
2. Revised page 3 of the Special Provisions.
3. Revised sheets 1 - 7, 17, 20, 25, 27 & 28 of the Plans.
4. Added sheets 4A, 30A & 34C to the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any Schedule of Prices changes in their bidding proposal.

Bidders using computer-generated bids are cautioned to reflect any and all Schedule of Prices changes, if involved, into their computer programs.

Very truly yours,

Scott E. Stitt, P.E.
Acting Engineer of Design and Environment

A handwritten signature in cursive script, reading "Ted B. Walschleger P.E.".

By: Ted B. Walschleger, P. E.
Engineer of Project Management

cc: Diane O'Keefe, Region 1, District 1; Mike Renner; D. Carl Puzey;
Estimates

TBW:MS:jc

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60L54

State Job # - C-91-708-10
 PPS NBR - 0-01617-1026
 County Name - VARIOUS- COOK- WILL
 Code - 0 - 31 - 197
 District - 1 - 1 - 1
 Section Number - 2010-069-I

Project Number

Route

VARIOUS

* REVISED : JUNE 02, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X0323723	CONC BAR WALL R&R L1	L SUM	1.000				
X0323724	CONC BAR WALL R&R L2	L SUM	1.000				
X0323725	CONC BAR WALL R&R L3	L SUM	1.000				
X0323726	CONC BAR WALL R&R L4	L SUM	1.000				
X0323727	CONC BAR WALL R&R L5	L SUM	1.000				
X0323728	CONC BAR WALL R&R L6	L SUM	1.000				
X0323729	CONC BAR WALL R&R L7	L SUM	1.000				
X0323730	CONC BAR WALL R&R L8	L SUM	1.000				
X0323731	CONC BAR WALL R&R L9	L SUM	1.000				
X0323732	CONC BAR WALL R&R L10	L SUM	1.000				
X0323733	CONC BAR WALL R&R L11	L SUM	1.000				
X0323734	CONC BAR WALL R&R L12	L SUM	1.000				
X0323735	CONC BAR WALL R&R L13	L SUM	1.000				
X0323736	CONC BAR WALL R&R L14	L SUM	1.000				
X0323737	CONC BAR WALL R&R L15	L SUM	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60L54

State Job # - C-91-708-10
 PPS NBR - 0-01617-1026
 County Name - VARIOUS- COOK- WILL
 Code - 0 - 31 - 197
 District - 1 - 1 - 1
 Section Number - 2010-069-I

Project Number

Route

VARIOUS

* REVISED : JUNE 02, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
X0323738	CONC BAR WALL R&R L16	L SUM	1.000				
X0323739	CONC BAR WALL R&R L17	L SUM	1.000				
X0323740	CONC BAR WALL R&R L18	L SUM	1.000				
X0323741	CONC BAR WALL R&R L19	L SUM	1.000				
X7011015	TR C-PROT EXPRESSWAYS	L SUM	1.000				
Z0026346	NIGHT WORK ZONE LIGHT	L SUM	1.000				
* Z0030850	TEMP INFO SIGNING	SQ FT	154.200				
Z0048665	RR PROT LIABILITY INS	L SUM	1.000				
42001300	PROTECTIVE COAT	SQ YD	155.000				
* 44201007	CL B PATCH T2 13	SQ YD	8.000				
* 44201299	DOWEL BARS 1 1/2	EACH	24.000				
* 44213200	SAW CUTS	FOOT	60.000				
* 60406100	FR & LIDS T1 CL	EACH	1.000				
67000400	ENGR FIELD OFFICE A	CAL MO	3.000				
67100100	MOBILIZATION	L SUM	1.000				

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF PRICES
 CONTRACT
 NUMBER - 60L54

State Job # - C-91-708-10
 PPS NBR - 0-01617-1026
 County Name - VARIOUS- COOK- WILL
 Code - 0 - 31 - 197
 District - 1 - 1 - 1
 Section Number - 2010-069-I

Project Number

Route

VARIOUS

* REVISED : JUNE 02, 2011

Item Number	Pay Item Description	Unit of Measure	Quantity	x	Unit Price	=	Total Price
70102630	TR CONT & PROT 701601	L SUM	1.000				
70300530	PAVT MARK TAPE T3 5	FOOT	500.000				
70301000	WORK ZONE PAVT MK REM	SQ FT	210.000				

DETAILS:

- Freeway Entrance and Exit Ramp Closure Details (TC-8)
- Traffic Control Details for Freeway Single and Multi-Lane Weave (TC-9)
- Traffic Control and Protection for Side Roads, Intersections and Driveways (TC-10)
- Traffic Control and Protection of Turn bays (To Remain Open to Traffic) (TC-14)
- Traffic Control Details for Freeway Shoulder Closures and Partial Ramp Closures (TC-17)
- Arterial Road Information Sign (TC-22)
- Traffic Control and Protection for Freeway Center Lane Closure Shoulder Lane (TC 25)**

SPECIAL PROVISIONS:

- Keeping the Expressway Open to Traffic
- Failure to Open Traffic Lanes to Traffic
- Keeping Arterial Roadways Open to Traffic
- Traffic Control and Protection (Expressways)
- Temporary Information Signing
- Nighttime Work Zone Lighting (BDE)
- Truck Mounted / Trailer Mounted Attenuators (BDE)
- Post Mounting of Signs (BDE)

EPOXY COATING ON REINFORCEMENT (DISTRICT ONE)

Effective: January 1, 2007

Revised: July 20, 2010

For work outside the limits of bridge approach pavement, all references in the Highway Standards and Standard Specifications for reinforcement, dowel bars and tie bars in pavement, shoulders, curb, gutter, combination curb and gutter and median, and chair supports for CRC pavement, shall be epoxy coated, unless noted on the plan.

TEMPERATURE CONTROL FOR CONCRETE PLACEMENT (DISTRICT ONE)

Effective: May 1, 2007

Delete the second and third sentences of the second paragraph of Article 1020.14(a) of the Standard Specifications.

KEEPING ARTERIAL ROADWAYS OPEN TO TRAFFIC

Effective: January 22, 2003

Revised: January 1, 2007

The Contractor shall provide the necessary traffic control devices to warn the public and to delineate the work zone as required in these Special Provisions, the Standard Specifications, and the State Standards.

Daily arterial lane closures shall be in accordance with the Standard Specifications, Highway Standards and the direction of the Engineer. The Contractor shall request and gain approval from the Illinois Department of Transportation's Arterial Traffic Control Supervisor at (847-705-4470) seventy-two (72) hours in advance of all long term (24 hrs. or longer) lane closures.

Arterial lane closures **for Vollmer Road** will only be permitted during the **off-peak** traffic volume hours. **Peak traffic volume hours are defined as weekdays (Monday through Friday) from 7:00 AM to 9:00 AM and 4:00 PM to 6:00 PM.**

Revised 06/06/2011