

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE										
				URBAN		KANE CO.		COOK CO.		KANE CO.		KANE CO.		
				KANE CO. ROADWAY	COOK CO. ROADWAY	US RTE 20 OVER FOX RIVER	US RTE 20 OVER RAYMOND ST	US RTE 20 OVER ST CHARLES ST	US RTE 20 OVER IL RTE 25	US RTE 20 OVER POPLAR CREEK	US RTE 20 OVER US BUS US 20	IL RTE 31 OVER US RTE 20	FA 426 OVER WB US RTE 20	
		045-0004	045-0005	045-0006	045-0007	016-0217	016-0218	045-0017	045-0008					
70400100	TEMPORARY CONCRETE BARRIER	FOOT	4857	3643	594	-	-	-	-	-	-	-	-	620
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	4237	3643	594	-	-	-	-	-	-	-	-	-
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	110	110	-	-	-	-	-	-	-	-	-	-
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	155138	127298	27840	-	-	-	-	-	-	-	-	-
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	600	600	-	-	-	-	-	-	-	-	-	-
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	25710	23862	1848	-	-	-	-	-	-	-	-	-
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	6360	6150	210	-	-	-	-	-	-	-	-	-
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	240	240	-	-	-	-	-	-	-	-	-	-
78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	7189	5603	1116	-	-	-	-	-	-	-	-	470
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	1657	1312	345	-	-	-	-	-	-	-	-	-
78100105	RAISED REFLECTIVE PAVEMENT MARKER(BRIDGE)	EACH	107	80	22	-	-	-	-	-	-	-	-	5
78200530	BARRIER WALL MARKERS, TYPE C	EACH	743	508	137	-	-	-	-	-	-	-	-	98
78300100	PAVEMENT MARKING REMOVAL	SQ FT	2290	2290	△	-	-	-	-	-	-	-	-	-
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1713	1352	356	-	-	-	-	-	-	-	-	5
88600600	DETECTOR LOOP REPLACEMENT	FOOT	2218	2218	-	-	-	-	-	-	-	-	-	-
X2020110	GRADING AND SHAPING SHOULDERS	UNIT	966	751	215	-	-	-	-	-	-	-	-	-
70012102	CONCRETE BRIDGE DECK SCARIFICATION (3/8 INCH)	SO YD	530	-	-	-	-	-	-	-	-	-	-	530
X0320882	GUTTERS TO BE CLEANED	FOOT	70	-	-	70	-	-	-	-	-	-	-	-
X0322215	CLEANING BRIDGE SCUPPERS AND DOWNSPOUTS	EACH	4	-	-	-	-	-	-	4	-	-	-	-
X0322944	BRIDGE DECK THIN POLYMER OVERLAY 3/8"	SO YD	530	-	-	-	-	-	-	-	-	-	-	530
40600895	CONSTRUCT ^{ING} TEST STRIP	EACH	1	0.8	0.2	-	-	-	-	-	-	-	-	-
X0325490	FURNISH AND INSTALL ACCESS DOOR	EACH	1	-	-	1	-	-	-	-	-	-	-	-
X0325983	BRIDGE DECK FLY ASH OR GGBF SLAG CONCRETE OVERLAY, 2 1/4"	SO YD	362	-	-	-	-	-	-	-	-	-	-	362
X0326331	CLEANING AND PAINTING BEARINGS	SO YD	15	-	-	-	-	-	-	-	-	-	-	15
X0326394	FLOOR DRAINS TO BE CLEANED	EACH	30	-	-	-	8	8	8	-	6	-	-	-
X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL VARIABLE DEPTH	SO YD	2809	2809	-	-	-	-	-	-	-	-	-	-
X40603500	PRELIMINARY TEST STRIP	EACH	1	0.75	0.25	-	-	-	-	-	-	-	-	-
X4060826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	15954	11335	4619	-	-	-	-	-	-	-	-	-
X55039700	STORM SEWERS TO BE CLEANED	FOOT	1152	1008	144	-	-	-	-	-	-	-	-	-
X60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	10	10	-	-	-	-	-	-	-	-	-	-
X0640200	TRAFFIC BARRIER TERMINAL, SPECIAL	EACH	1	-	-	-	-	-	-	-	1	-	-	-
X7030030	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	5200	-	-	-	-	-	-	-	-	-	-	5200
Z0001495	BRIDGE APPROACH SHOULDER REMOVAL	SO YD	20	-	-	-	-	-	-	-	-	-	-	20
Z0001899	JACK AND REMOVE EXISTING BEARINGS	EACH	15	-	-	-	-	-	-	-	-	-	-	15

• SPECIALTY ITEM

Rev. 6-6-11

Rev.

FILE NAME = P:\2009\ME09086_Ver\Ver_Plan\CADD\W021_US20_Shts\03-500sht-ht-US20.dgn
 PLOT SCALE = 1:1000 / IN.
 USER NAME = Millennium Professional Services



200 22ND Street, Suite 216, Lombard, IL 60148
 630.785.8110 voice, 630.839.2566 fax
 WWW.MPS-IL.COM
MILLENNIA PROFESSIONAL SERVICES

DESIGNED - TVN	REVISED -
DRAWN - TVN	REVISED -
CHECKED - RPD	REVISED -
DATE - 4/5/2011	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

U.S. ROUTE 20
EAST OF PLANK ROAD TO WELD ROAD

SUMMARY OF QUANTITIES

F.A.P. RTE. 345	SECTION BWRS-2	COUNTY KANE	TOTAL SHEETS 124	SHEET NO. 5
CONTRACT NO. 600746				

FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT
 P:\2009\ME09086_Ver\Ver_Plan\CADD\W021_US20_Shts\03-500sht-ht-US20.dgn