

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE										
				URBAN		KANE CO.		COOK CO.		KANE CO.		KANE CO.		
				KANE CO. ROADWAY	COOK CO. ROADWAY	US RTE 20 OVER FOX RIVER 045-0004	US RTE 20 OVER RAYMOND ST 045-0005	US RTE 20 OVER ST CHARLES ST 045-0006	US RTE 20 OVER IL RTE 25 045-0007	US RTE 20 OVER POPLAR CREEK 016-0217	US RTE 20 OVER US BUS US 20 016-0218	IL RTE 31 OVER US RTE 20 045-0017	FA 426 OVER WB US RTE 20 045-0008	
0005	0005	0014	0014	0014	0014	0014	0014	0014	0014	0014				
Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	310	250	60	-	-	-	-	-	-	-	-	-
Z0012754	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 IN.)	SQ. FT.	499	-	-	10	27	-	-	6	55	-	-	401
Z0012755	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 IN.)	SQ. FT.	172	-	-	73	-	-	-	-	-	-	-	99
Z0016001	DECK SLAB REPAIR (FULL DEPTH, TYPE I)	SQ. YD.	0.7	-	-	-	-	0.7	-	-	-	-	-	-
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ. YD.	132.5	-	-	25.1	-	79.1	-	13.3	-	-	-	15
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ. YD.	491.5	-	-	246.9	21.7	100.4	39.7	50.8	9.1	22.9	-	-
Z0018002	DRAINAGE SCUPPERS, DS-11	EACH	1	-	-	1	-	-	-	-	-	-	-	-
Z0018400	DRAINAGE STRUCTURES TO BE ADJUSTED	EACH	35	35	-	-	-	-	-	-	-	-	-	-
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	94	82	12	-	-	-	-	-	-	-	-	-
Z0021904	SILICONE JOINT SEALER, 1"	FOOT	307	-	-	-	-	155	152	-	-	-	-	-
Z0021907	SILICONE JOINT SEALER, 1 3/4"	FOOT	382	-	-	-	87	76	77	-	-	142	-	-
Z0021908	SILICONE JOINT SEALER, 2"	FOOT	167	-	-	-	-	-	-	167	-	-	-	-
Z0021914	SILICONE JOINT SEALER, 2 3/4"	FOOT	231	-	-	-	78	79	74	-	-	-	-	-
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	-	-	-	-	-	-	-	-	-	-	2
Z0030255	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 2	EACH	6	4	2	-	-	-	-	-	-	-	-	-
Z0030320	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 2	EACH	6	4	2	-	-	-	-	-	-	-	-	-
Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	363.7	286	52	-	-	-	-	-	-	-	-	25.7
Z0041895	POLYMER CONCRETE	CU. FT.	11.4	-	-	-	-	-	-	11.4	-	-	-	-
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1	-	-	-	-	-	-	-	-	-	-
04200105	SHOULDER RUMBLE STRIPS	FOOT	68255	54394	13861	-	-	-	-	-	-	-	-	-
Z0073200	TEMPORARY SHORING AND CRIBBING	EACH	6	-	-	-	1	-	-	-	-	-	-	5
X0327303	REMOVAL OF EXISTING SIGN LIGHTING UNIT WITH NO SALVAGE	EACH	17	17	-	-	-	-	-	-	-	-	-	-
Z001214-2	BRIDGE DECK SCARIFICATION (2 1/4 INCH)	SO YD	362	-	-	-	-	-	-	-	-	-	-	362
Z0034105	MATERIAL TRANSFER DEVICE	TON	21,984	15,855	6,129	-	-	-	-	-	-	-	-	-

• SPECIALTY ITEM

Rev. 6-9-11

Rev.

FILE NAME : P:\2009\ME\09086_Ver_Ver_Phil\CADD\W02LUS20\Shets\03-500sh-t-ht-US20.dgn
 PLOT SCALE : 1:1000 / IN.
 USER : Phil
 MILLENIA PROFESSIONAL SERVICES



200 22ND Street, Suite 216, Lombard, IL 60148
 630.705.0110 voice, 630.839.2566 fax
 WWW.MPS-IL.COM
MILLENNIA PROFESSIONAL SERVICES

DESIGNED	TVN	REVISED	-
DRAWN	TVN	REVISED	-
CHECKED	RPD	REVISED	-
DATE	4/4/2011	REVISED	-

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

U.S. ROUTE 20
EAST OF PLANK ROAD TO WELD ROAD

SUMMARY OF QUANTITIES

SCALE: NTS SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
345	BWRS-2	KANE	124	6
CONTRACT NO.			000446	

FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT
 P:\2009\ME\09086_Ver_Ver_Phil\CADD\W02LUS20\Shets\03-500sh-t-ht-US20.dgn