

90% FED.
10% STATE

SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE	
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	0021 QUANTITY	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5	5	
67100100	MOBILIZATION	L SUM	1	1	
72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	103	103	
72400310	REMOVE SIGN PANEL - TYPE 1	SQ FT	82	82	△
72400320	REMOVE SIGN PANEL - TYPE 2	SQ FT	229	229	
72400330	REMOVE SIGN PANEL - TYPE 3	SQ FT	12,496	12,496	
72400710	RELOCATE SIGN PANEL - TYPE 1	SQ FT	144	144	
72400720	RELOCATE SIGN PANEL - TYPE 2	SQ FT	633	633	△
72600100	MILE POST MARKER ASSEMBLY	EACH	56	56	△
72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	3,447	3,447	
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	1260	1260	
72900100	METAL POST - TYPE A	FOOT	658	658	△
73000100	WOOD SIGN SUPPORT	FOOT	3870	3870	
73301810	OVERHEAD SIGN STRUCTURE WALKWAY, TYPE A	FOOT	116	116	
73400100	CONCRETE FOUNDATIONS	CU YD	10	10	
73700100	REMOVE GROUND MOUNTED SIGN SUPPORT	EACH	2	2	
73700200	REMOVE CONCRETE FOUNDATION - GROUND MOUNT	EACH	2	2	
73800100	STRUCTURAL STEEL SUPPORT FOR OVERHEAD SIGN STRUCTURE - SPAN	EACH	2	2	
73801100	REMOVE AND REERECT OVERHEAD SIGN STRUCTURE-SPAN	EACH	1	1	
73801200	REMOVE AND REERECT OVERHEAD SIGN STRUCTURE-CANTILEVER	EACH	1	1	
84200600	REMOVAL OF LIGHTING UNIT, NO SALVAGE	EACH	38	38	
Z0025620	FURNISH AND INSTALL TRUSS DAMPER	EACH	2	2	
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1	
X7200105	SIGN PANEL - TYPE 1 (SPECIAL)	SQ FT	1340	1340	
X7200205	SIGN PANEL - TYPE 2 (SPECIAL)	SQ FT	2661	2661	△
X7200305	SIGN PANEL - TYPE 3 (SPECIAL)	SQ FT	13,512	13,512	
X7240200	REMOVE SIGN PANEL ASSEMBLY - TYPE B (SPECIAL)	EACH	161	161	
Z0026346	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1	
Z0025680	FURNISH AND INSTALL SADDLE SHIM BLOCK	EACH	4	4	
X7340105	REBUILD FOUNDATION FOR OVERHEAD SIGN STRUCTURE CONCRETE	EACH	2	2	
X7330070	OVERHEAD SIGN SUPPORT GROUT REPAIR	EACH	1	1	

* INDICATES SPECIALTY ITEM

DESIGNED BY: BAXTER & WOODMAN, INC.
 STATE OF ILLINOIS - PROFESSIONAL DESIGN FIRM
 LICENSE NO. 084-00081 - EXPRESS 4/30/2011
 4/5/2011 9:46:00 AM
 \\p01s10003-10-10-BK\101
 C:\CrystalLake\LDOT\00853-1-00-Design\10-10-CADD-SURVEY\DRAWINGS\00853-1-00-000-001-000000-001-000000.dgn



USER NAME = 231ukb	DESIGNED - DJS	REVISED -
	DRAWN - LKB	REVISED -
PLOT SCALE = 50.0000' / 1" IN.	CHECKED - RWL	REVISED -
PLOT DATE = 4/5/2011	DATE - 11-8-10	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES	
SCALE:	SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	2010-114-SG	WILL	115	3
CONTRACT NO. 60M48				
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

Rev. 6-7-11