SIGNING SCHEDULE

SIGN NAME	STATION	SIGN DESCRIPTION	EXISTING PANEL DIMENSIONS WIDTH (FT)	EXISTING PANEL DIMENSIONS HEIGHT (FT)	PROPOSED PANEL DIMENSIONS WIDTH (FT)	PROPOSED PANEL DIMENSIONS HEIGHT (FT)	REMOVE SIGN PANEL - TYPE 1 (SQ FT)	REMOVE SIGN PANEL - TYPE 2 (SQ FT)	REMOVE SIGN PANEL - TYPE 3 (SQ FT)	REMOVE SIGN PANEL ASSEMBLY - TYPE A (EACH)	REMOVE SIGN PANEL ASSEMBLY - TYPE B (SPECIAL) (EACH)	RELOCATE SIGN PANEL - TYPE 1 (SQ FT)	RELOCATE SIGN PANEL - TYPE 2 (SQ FT)	SIGN PANEL - TYPE 1 (SPECIAL) (SQ FT)	SIGN PANEL - TYPE 2 (SPECIAL) (SQ FT)	SIGN PANEL - TYPE 3 (SPECIAL) (SQ FT)	WOOD SIGN SUPPORT (FT)	TELESCOPING STEEL SIGN SUPPORT (FT)	MILE POST MARKER ASSEMBLY (FT)	REMOVAL OF LIGHTING UNIT, NO SALVAGE (EACH)
RO-TS-488B	14+05	M6-1	1.8	1.3	1.8	1.3								2.2						
RO-WP-489A	14+83	R1-1	4.0	4.0	4.0	4.0					1				13.2		18			
RO-WP-489B	14+83	R5-1	2.5	2.5	2.5	2.5								6.3						
RO-WP-490A	14+99	R1-1	4.0	4.0	4.0	4.0					1				13.2		18			
RO-WP-490B	14+99	R5-1	2.5	2.5	2.5	2.5								6.3						
RP-WP-491	1+29	R5-I100	4.0	5.0	4.0	5.0					1				20.0		18			
RP-WP-845	6+70	W1-8R			3.0	4.0									12.0		18			
RP-WP-846	7+50	W1-8R			3.0	4.0									12.0		18			
RP-WP-847	8+30	W1-8R			3.0	4.0									12.0		18			
RP-WP-848	9+10	W1-8R			3.0	4.0									12.0		18			
RP-WP-849	9+90	W1-8R			3.0	4.0									12.0		18			
RP-WP-850	10+70	W1-8R			3.0	4.0									12.0		18			
RQ-TS-493	0+82	R4-7	2.0	2.5	2.0	2.5				1				5.0				18		
RQ-WP-494	1+38	R5-I100	4.0	5.0	4.0	5.0					1				20.0		18			
RR-WP-495	4+47	W13-3	4.0	5.0	4.0	5.0					1				20.0		18			
RR-WP-496	10+15	W3-1	4.0	4.0	4.0	4.0					1				16.0		18			
RR-GM-497	13+07	WILMINGTON	8.5	2.0	8.5	2.0		17.0							17.0					
RR-WP-498	13+28	R5-1A	3.5	2.5	3.5	2.5				1				8.8			18			
RR-WP-499	13+31	R5-1A	3.5	2.5	3.5	2.5				1				8.8			18			
RR-TS-500A	15+09	WEIGHT LIMIT 5 TONS	2.0	2.5	2.0	2.5				1				5.0				18		
RR-TS-500B	15+09	M6-1	1.8	1.3	1.8	1.3								2.2						
RR-WP-501A	17+00	R1-1	4.0	4.0	4.0	4.0					1				13.2		18			
RR-WP-501B	17+00	R5-1	2.5	2.5	2.5	2.5								6.3						
RR-WP-502A	17+05	R1-1	4.0	4.0	4.0	4.0					1				13.2		18			
RR-WP-502B	17+05	R5-1	2.5	2.5	2.5	2.5								6.3						
RR-WP-502C	17+05	R4-7	2.0	2.5	2.0	2.5								5.0						
RW-WP-521	4+79	W13-3	4.0	5.0	4.0	5.0					1				20.0		18			
RW-WP-522A	10+00	W3-1	4.0	4.0	4.0	4.0					1				16.0		18			
RW-WP-522B	10+00	R5-1A	3.5	2.5	3.5	2.5								8.8						
RW-WP-523	10+06	R5-1A	3.5	2.5	3.5	2.5				1				8.8			18			
RW-TS-524	14+35	R5-1	2.5	2.5	2.5	2.5				1				6.3				18		
RW-TS-525	14+42	R5-1	2.5	2.5	2.5	2.5				1				6.3				18		
RW-WP-526A	14+99	R1-1	3.0	3.0	3.0	3.0					1			7.4			18			
RW-WP-526B	14+99	R6-2L	2.0	2.5	2.0	2.5								5.0						
RW-WP-526C	14+99	R6-2R	2.0	2.5	2.0	2.5								5.0						
RW-WP-527	15+02	R1-1	3.0	3.0	3.0	3.0				1				7.4			18			
RX-WP-528	1+71	R5-I100	4.0	5.0	4.0	5.0					1				20.0		18			
RY-WP-529	1+66	R5-I100	4.0	5.0	4.0	5.0					1				20.0		18			
RZ-WP-530	4+84	W13-3	4.0	5.0	4.0	5.0					1				20.0		18			
RZ-WP-531A	9+06	W3-1	4.0	4.0	4.0	4.0					1				16.0		18			
RZ-WP-531B	9+06	R5-1a	3.5	2.5	3.5	2.5								8.8						
RZ-WP-532	9+10	R5-1a	3.5	2.5	3.5	2.5				1				8.8			18			
RZ-WP-533A	13+50	R1-1	4.0	4.0	4.0	4.0					1				13.2		18			
RZ-WP-533B	13+50	R5-1	2.5	2.5	2.5	2.5								6.3						
RZ-WP-533C	13+50	R6-2L	2.0	2.5	2.0	2.5								5.0						
RZ-WP-533D	13+50	R6-2R	2.0	2.5	2.0	2.5								5.0						
RZ-WP-534A	13+57	R1-1	4.0	4.0	4.0	4.0					1				13.2		18			
RZ-WP-534B	13+57	R5-1	2.5	2.5	2.5	2.5								6.3						
RAA-WP-535	8+00	W13-3	4.0	5.0	4.0	5.0					1				20.0		18			
RAA-GM-536	11+42	FOOD	9.5	8.0	9.5	8.0			76.0			19.0				76.0				
RAA-GM-537	13+09	MORRIS JOLIET	6.5	4.0	6.5	4.0			26.0							26.0				
RAA-WP-538A	13+30	R5-1A	3.5	2.5	3.5	2.5					1			8.8			18			
RAA-WP-538B	13+30	RIVERBOAT	2.0	2.0	2.0	2.0								4.0						
RAA-WP-538C	13+30	M6-1	1.8	1.3	1.8	1.3								2.2						
RAA-WP-539	13+31	R5-1A	3.5	2.5	3.5	2.5				1				8.8			18			
RAA-GM-540A	14+82	GAS	9.5	6.0	9.5	6.0			57.0			9.0				57.0				
RAA-GM-540B	14+82	BIODIESEL	2.0	2.0	2.0	2.0	4.0							4.0						
RAA-GM-540C	14+82	M6-1	1.8	1.3	1.8	1.3	2.2							2.2						
RAA-TS-541	15+79	D4-2	2.5	3.0	2.5	3.0				1				7.5				18		
RAA-TS-542	16+06	R5-1	2.5	2.5	2.5	2.5				1				6.3				18		
RAA-WP-543A	16+12	R5-1	2.5	2.5	2.5	2.5					1			6.3			18			
RAA-WP-543B	16+12	STATE PARK	3.0	3.0	3.0	3.0								9.0						
RAB-WP-544	1+20	R5-I100	4.0	5.0	4.0	5.0					1				20.0		18			

Rev. 6-7-11

BAXTER & WOODMAN Consulting Engineers

USER NAME = 231ukb	DESIGNED - DJS	REVISED -5-27-11 ADD.1	
	DRAWN - UKB	REVISED -	
PLOT SCALE = 1.0000 ' / IN.	CHECKED - RWL	REVISED -	
PLOT DATE = 6/1/2011	DATE - 11-8-10	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SIGNAGE SCHEDULE

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.I RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	2010-114-SG	WILL	115	11

CONTRACT NO.60M48

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT

COPYRIGHT 2009, BY BAXTER & WOODMAN, INC.
STATE OF ILLINOIS - PROFESSIONAL DESIGN FIRM
LICENSE NO. 184-001007 EXPIRES 4/30/2011
231UKB 10/26/54 AM/231ukb\cyg\dl.dwg\LIDOT\0D153\MD-Design\WD-ID\CADD-SURVEY\DRAWINGS\0D153-WD-ID-SIGN-SCHEDULE.dgn