SIGNING SCHEDULE

SIGN NAME	STATION	SIGN DESCRIPTION	EXISTING PANEL DIMENSIONS WIDTH (FT)	EXISTING PANEL DIMENSIONS HEIGHT (FT)	PROPOSED PANEL DIMENSIONS WIDTH (FT)	PROPOSED PANEL DIMENSIONS HEIGHT (FT)	REMOVE SIGN PANEL - TYPE 1 (SQ FT)	REMOVE SIGN PANEL - TYPE 2 (SQ FT)	REMOVE SIGN PANEL - TYPE 3 (SQ FT)	REMOVE SIGN PANEL ASSEMBLY - TYPE A (EACH)	REMOVE SIGN PANEL ASSEMBLY - TYPE B (SPECIAL) (EACH)	RELOCATE SIGN PANEL - TYPE 1 (SQ FT)	RELOCATE SIGN PANEL - TYPE 2 (SQ FT)	SIGN PANEL - TYPE 1 (SPECIAL) (SQ FT)	SIGN PANEL - TYPE 2 (SPECIAL) (SQ FT)	SIGN PANEL - TYPE 3 (SPECIAL) (SQ FT)	WOOD SIGN SUPPORT (FT)	TELESCOPING STEEL SIGN SUPPORT (FT)	MILE POST MARKER ASSEMBLY (FT)	REMOVAL OF LIGHTING UNIT, NO SALVAGE (EACH)
LOR-TS-620B	11+33	M1-1	2.0	2.0	2.0	2.0								3.1						
LOR-TS-620C	11+33	M6-3	1.8	1.3	1.8	1.3								2.2						
LOR-TS-621A	11+33	M3-3	2.0	1.0	2.0	1.0				1				2.0				18		
LOR-TS-621B	11+33	M1-1	2.0	2.0	2.0	2.0								3.1						
LOR-TS-621C	11+33	M5-1R	1.8	1.3	1.8	1.3								2.2						
LOR-GM-622	14+97	SOUTH TO BLOOMINGTON	11.0	7.0	11.0	7.0			77.0							77.0				
LOR-GM-623	17+86	SOUTH TO BLOOMINGTON	11.0	7.0	11.0	7.0			77.0							77.0				
LOR-TS-624A	18+36	M3-1	2.0	1.0	2.0	1.0				1				2.0				18		
LOR-TS-624B	18+36	M1-1	2.0	2.0	2.0	2.0								3.1						
LOR-TS-624C	18+36	M5-1L	1.8	1.3	1.8	1.3								2.2						
LOR-TS-625A	22+75	M3-3	2.0	1.0	2.0	1.0				1				2.0				18		
LOR-TS-625B	22+75	M1-1	2.0	2.0	2.0	2.0								3.1						
LOR-TS-625C	22+75	M5-1L	1.8	1.3	1.8	1.3								2.2						
LOR-GM-626	23+56	NORTH JOLIET	11.0	6.5	11.0	6.5			71.5							71.5				
LOR-TS-627A	25+65	M3-3	2.0	1.0	2.0	1.0				1				2.0				18		
LOR-TS-627B	25+65	M1-1	2.0	2.0	2.0	2.0								3.1						
LOR-TS-627C	25+65	M5-1R	1.8	1.3	1.8	1.3								2.2						
LOR-TS-628A	25+66	M3-3	2.0	1.0	2.0	1.0				1				2.0				18		
LOR-TS-628B	25+66	M1-1	2.0	2.0	2.0	2.0								3.1						
LOR-TS-628C	25+66	M6-3	1.8	1.3	1.8	1.3								2.2						
LOR-TS-629A	29+65	M4-5	2.0	1.0	2.0	1.0				1				2.0				18		
LOR-TS-629B	29+65	M1-1	2.0	2.0	2.0	2.0								3.1						
LOR-TS-629C	29+65	M6-1	1.8	1.3	1.8	1.3								2.2						
NRR-TS-630A	1+03	M2-1	1.8	1.3	1.8	1.3				1				2.2				18		
NRR-TS-630B	1+03	M1-1	2.0	2.0	2.0	2.0								3.1						
NRR-TS-631A	3+87	M3-3	2.0	1.0	2.0	1.0					1			2.0				18		
NRR-TS-631B	3+87	M1-1	2.0	2.0	2.0	2.0								3.1						
NRR-TS-631C	3+87	M6-1	1.8	1.3	1.8	1.3								2.2						
NRR-TS-631D	3+87	M3-1	2.0	1.0	2.0	1.0								2.0						
NRR-TS-631E	3+87	M1-1	2.0	2.0	2.0	2.0								3.1						
NRR-TS-631F	3+87	M6-3	1.8	1.3	1.8	1.3								2.2						
NRR-TS-632A	7+76	M3-3	2.0	1.0	2.0	1.0				1				2.0				18		
NRR-TS-632B	7+76	M1-1	2.0	2.0	2.0	2.0								3.1						
NRR-TS-632C	7+76	M6-3	1.8	1.3	1.8	1.3								2.2						
NRR-WP-633	8+60	BLOOMINGTON	9.5	2.0	9.5	2.0					1				19.0		54			
NRR-TS-634A	15+84	M3-1	2.0	1.0	2.0	1.0				1				2.0				18		
NRR-TS-634B	15+84	M1-1	2.0	2.0	2.0	2.0								3.1						
NRR-TS-634C	15+84	M6-1	1.8	1.3	1.8	1.3								2.2						
NRR-TS-635A	17+15	M3-3	2.0	1.0	2.0	1.0					1			2.0				18		
NRR-TS-635B	17+15	M1-1	2.0	2.0	2.0	2.0								3.1						
NRR-TS-635C	17+15	M6-3	1.8	1.3	1.8	1.3								2.2						
NRR-TS-635D	17+15	M3-1	2.0	1.0	2.0	1.0								2.0						
NRR-TS-635E	17+15	M1-1	2.0	2.0	2.0	2.0								3.1						
NRR-TS-635F	17+15	M6-1	1.8	1.3	1.8	1.3								2.2						
NRR-TS-636A	25+30	M2-1	1.8	1.3	1.8	1.3				1				2.2				18		
NRR-TS-636B	25+30	M1-1	2.0	2.0	2.0	2.0								3.1						
BLF-TS-647A	1+26	M2-1			1.8	1.3								2.2				18		
BLF-TS-647B	1+26	M1-1			2.0	2.0								3.1						
BLF-WP-648	10+26	CHICAGO BLOOMINGTON	9.5	3.0	9.5	3.0					1					28.5	54			
BLF-TS-649A	10+85	M3-1	2.0	1.0	2.0	1.0					1			2.0				18		
BLF-TS-649B	10+85	M1-1	2.0	2.0	2.0	2.0								3.1						
BLF-TS-649C	10+85	M6-3	1.8	1.3	1.8	1.3								2.2						
BLF-TS-649D	10+85	M3-3	2.0	1.0	2.0	1.0								2.0						
BLF-TS-649E	10+85	M1-1	2.0	2.0	2.0	2.0								3.1						
BLF-TS-649F	10+85	M6-1	1.8	1.3	1.8	1.3								2.2						
BLF-TS-650A	12+19	R5-1	2.5	2.5	2.5	2.5					1			6.3				18		
BLF-TS-650B	12+19	R3-1	2.0	2.0	2.0	2.0								4.0						
BLF-TS-651A	12+89	M3-3	2.0	1.0	2.0	1.0				1				2.0				18		
BLF-TS-651B	12+89	M1-1	2.0	2.0	2.0	2.0								3.1						
BLF-TS-651C	12+89	M6-1	1.8	1.3	1.8	1.3								2.2						
BLF-WP-652	19+63	CHICAGO	7.0	2.0	7.0	2.0					1				14.0		36			
BLF-TS-653A	22+04	M3-1	2.0	1.0	2.0	1.0				1				2.0				18		
BLF-TS-653B	22+04	M1-1	2.0	2.0	2.0	2.0								3.1						

COPYRIGHT 2006 BY BAXTER & WOODMAN, INC.
STATE OF ILLINOIS - PROFESSIONAL DESIGN FIRM ...\ILLINOIS\WILL\2010-114-SG\SIGN SCHEDULE.dgn
LICENSE NO. 184-001002 EXPIRES 4/30/2011 ...\DGNS\00053 WO 10 SIGN SCHEDULE.dgn
2SUBS NO. 184-001002 EXPIRES 4/30/2011 ...\DGNS\00053 WO 10 SIGN SCHEDULE.dgn
6/07/03 ADV/2011\Crystal Lake\LDXT\00053\CAD Design\WO 10\CADD SUrv\Y\DRAWINGS\DGNS\00053 WO 10 SIGN SCHEDULE.dgn

BAXTER & WOODMAN Consulting Engineers

USER NAME = 231ukb	DESIGNED - DJS	REVISED -5-27-11 ADD.1	
	DRAWN - UKB	REVISED -	
PLOT SCALE = 1.0000 ' / IN.	CHECKED - RWL	REVISED -	
PLOT DATE = 6/1/2011	DATE - 11-8-10	REVISED -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SIGNAGE SCHEDULE

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

Rev. 6-7-11

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	2010-114-SG	WILL	115	13
		CONTRACT NO.60M48		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		