

**SIGNING SCHEDULE**

SIGN NAME	STATION	SIGN DESCRIPTION	EXISTING PANEL DIMENSIONS		PROPOSED PANEL DIMENSIONS		REMOVE SIGN PANEL TYPE 1	REMOVE SIGN PANEL TYPE 2	REMOVE SIGN PANEL TYPE 3	REMOVE SIGN PANEL ASSEMBLY - TYPE A	REMOVE SIGN PANEL ASSEMBLY - TYPE B (SPECIAL)	RELOCATE SIGN PANEL - TYPE 1	RELOCATE SIGN PANEL - TYPE 2	SIGN PANEL - TYPE 1 (SPECIAL)	SIGN PANEL - TYPE 2 (SPECIAL)	SIGN PANEL - TYPE 3 (SPECIAL)	WOOD SIGN SUPPORT (FT)	TELESCOPING STEEL SIGN SUPPORT (FT)	METAL POST - TYPE A (FT)	REMOVAL OF LIGHTING UNIT, NO SALVAGE (EACH)
			WIDTH (FT)	HEIGHT (FT)	WIDTH (FT)	HEIGHT (FT)	(SQ FT)	(SQ FT)	(SQ FT)	(EACH)	(EACH)	(SQ FT)	(SQ FT)	(SQ FT)	(SQ FT)	(SQ FT)	(SQ FT)	(FT)	(FT)	(FT)
RB-GM-421B	9+93	FOOD	9.5	5.0	9.5	5.0			47.5							47.5				
RB-GM-422	13+48	BRAIDWOOD	9.0	2.5	9.0	2.5		22.5							22.5					
RB-WP-423	16+00	R5-1a	3.5	2.5	3.5	2.5	8.8							8.8						
RB-WP-424	16+00	R5-1a	3.5	2.5	3.5	2.5	8.8							8.8						
RB-WP-425	16+79	R5-1	2.5	2.5	2.5	2.5	6.3							6.3						
RB-WP-426	16+81	R5-1	2.5	2.5	2.5	2.5	6.3							6.3						
RB-WP-427A	17+70	R6-1R	3.0	1.0	3.0	1.0	3.0							3.0						
RB-WP-427B	17+70	R6-1L	3.0	1.0	3.0	1.0	3.0							3.0						
RB-WP-427C	17+70	R1-1	3.0	3.0	3.0	3.0	9.0							7.4						
RB-WP-427D	17+70	R6-3	3.0	2.5	3.0	2.5	7.5							7.5						
RB-WP-428	17+95	R1-1	3.0	3.0	3.0	3.0	9.0							7.4						
RC-WP-429	0+18	W13-3	4.0	5.0	4.0	5.0		20.0							20.0					
RC-GM-430A	3+87	BLANK SERVICE SIGN	9.5	5.0	9.5	5.0			47.5							47.5				
RC-GM-430B	3+87	CAMPING	9.5	5.0	9.5	5.0			47.5		3.0					47.5				
RC-GM-431	5+94	FOOD	9.5	8.0	9.5	8.0			76.0		21.0					76.0				
RC-GM-432	7+97	GAS	9.5	8.0	9.5	8.0			76.0		7.0					76.0				
RC-PM-433	10+43	W3-1	4.0	4.0	4.0	4.0		16.0							16.0					
RC-GM-434	10+92	DIAMOND, COAL CITY, KANKAKEE	8.0	5.0	8.0	5.0			40.0							40.0				
RC-WP-435	11+43	R5-1a	3.5	2.5	3.5	2.5	8.8							8.8						
RC-WP-436	11+47	R5-1a	3.5	2.5	3.5	2.5	8.8							8.8						
RC-WP-437	13+33	R5-1	2.5	2.5	2.5	2.5	6.3							6.3						
RC-WP-438	13+39	R5-1	2.5	2.5	2.5	2.5	6.3							6.3						
RC-TS-439	13+68	R1-1	3.0	3.0	3.0	3.0	9.0							7.4						
RC-TS-440	14+13	R1-1	3.0	3.0	3.0	3.0	9.0							7.4						
RD-PM-441	2+40	R5-1100	4.0	5.0	4.0	5.0		20.0							20.0					
RE-WP-442	2+00	R5-1100			4.0	5.0									20.0		20			
RF-WP-443	0+30	W13-3	4.0	5.0	4.0	5.0		20.0							20.0					
RF-GM-444A	5+59	BLANK SERVICE SIGN	9.5	5.0	9.5	5.0			47.5							47.5				
RF-GM-444B	5+59	CAMPING	9.5	5.0	9.5	5.0			47.5		3.0					47.5				
RF-GM-445	7+73	FOOD	9.5	8.0	9.5	8.0			76.0		21.0					76.0				
RF-GM-446	9+87	GAS	9.5	8.0	9.5	8.0			76.0		7.0					76.0				
RF-PM-447	12+17	W3-1	4.0	4.0	4.0	4.0		16.0							16.0					
RF-WP-448	12+47	R5-1A	3.5	2.5	3.5	2.5	8.8							8.8						
RF-WP-449	12+48	R5-1A	3.5	2.5	3.5	2.5				1				8.8			16			
RF-GM-450	12+96	KANKAKEE, DIAMOND, COAL CITY	8.0	5.0	8.0	5.0			40.0							40.0				
RF-TS-451	14+51	R5-1	2.5	2.5	2.5	2.5	6.3							6.3						
RF-TS-452	14+56	R5-1	2.5	2.5	2.5	2.5				1				6.3			16			
RF-TS-453	15+37	R1-1	3.0	3.0	3.0	3.0	9.0							7.4						
RF-TS-454	15+76	R1-1	3.0	3.0	3.0	3.0	9.0							7.4						
RG-WP-455	2+76	W13-3	4.0	5.0	4.0	5.0		20.0							20.0					
RG-WP-810	3+50	W1-8R			3.0	4.0									12.0		16			
RG-WP-811	4+70	W1-8R			3.0	4.0									12.0		16			
RG-WP-812	5+90	W1-8R			3.0	4.0									12.0		16			
RG-WP-813	7+10	W1-8R			3.0	4.0									12.0		16			
RG-WP-814	8+30	W1-8R			3.0	4.0									12.0		16			
RG-TS-456A	9+20	W4-1R	4.0	4.0	4.0	4.0		16.0							16.0					
RG-TS-456B	9+20	R5-1A	3.5	2.5	3.5	2.5	8.8							8.8						
RG-PM-457	9+80	R5-1A	3.5	2.5	3.5	2.5	8.8							8.8						
RG-TS-458A	16+94	R3-4	2.0	2.0	2.0	2.0	4.0							4.0						
RG-TS-458B	16+94	R4-7	2.0	2.5	2.0	2.5	5.0							5.0						
RG-TS-458C	16+94	OM1-3	1.5	1.5	1.5	1.5	2.3							2.3						
RG-TS-459A	17+00	R5-1	2.5	2.5	2.5	2.5	6.3							6.3						
RG-TS-459B	17+00	W6-3	3.0	3.0	3.0	3.0	9.0							9.0						
RG-TS-460A	24+20	M4-5	2.0	1.0	2.0	1.0	2.0							2.0						
RG-TS-460B	24+20	M3-1	2.0	1.0	2.0	1.0	2.0							2.0						
RG-TS-460C	24+20	M1-1	2.0	2.0	2.0	2.0	4.0							3.1						
RG-TS-460D	24+20	M6-1	1.8	1.3	1.8	1.3	2.2							2.2						
RG-WP-461A	24+81	M2-1	1.8	1.3	1.8	1.3	2.2							2.2						
RG-WP-461B	24+81	M3-1	2.0	1.0	2.0	1.0	2.0							2.0						
RG-WP-461C	24+81	M1-1	2.0	2.0	2.0	2.0	4.0							3.1						
RH-PM-462	1+91	R5-1100	4.0	5.0	4.0	5.0		20.0							20.0					
RH-PM-463A	12+03	M4-6	2.0	1.0	2.0	1.0	2.0							2.0						
RH-PM-463B	12+03	M1-1100	2.0	2.0	2.0	2.0	4.0							4.0						

DRAWN BY: BAXTER, WOODMAN, INC. PROJECT: ILLINOIS DEPARTMENT OF TRANSPORTATION, SIGNAGE SCHEDULE, SHEET NO. 9  
 DATE: 4/14/2011  
 USER: 231ukb  
 CHECKED: RWL  
 DATE: 11-8-10  
 REVISIONS: NONE



USER NAME = 231ukb  
 PLOT SCALE = 1/8" = 1'-0"  
 PLOT DATE = 4/14/2011

DESIGNED - DJJ  
 DRAWN - UKB  
 CHECKED - RWL  
 DATE - 11-8-10

**STATE OF ILLINOIS  
 DEPARTMENT OF TRANSPORTATION**

**SIGNAGE SCHEDULE**  
 SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	2010-114-SG	WILL	115	9
CONTRACT NO. 60M48				
FED. ROAD DIST. NO. 1   ILLINOIS   FED. AID PROJECT				