

SCHEDULE OF QUANTITIES- SIGNS

STATION	OFFSET		REMOVE SIGN PANEL - TYPE 1 (SQ.FT.)	SIGN PANEL ASSEMBLY REMOVAL (EACH)	Sign	SIGN ID #	SIZE (inches)	SIGN PANEL TYPE 1 (SQ.FT.)	TELESCOPING STEEL SIGN SUPPORT (FT.)
105+42	38.9	LT	3	0	Black and Yellow Striped Object Marker	OM-3L	12x36	3	0
105+80	27.7	RT	0	1	Black and Yellow Striped Object Marker	OM-3R	12x36	3	13
104+25	38.8	RT	0	1	Equestrain	W11-7	36x36	9	15.25
103+15	39.5	RT	0	1	SPEED LIMIT 40	R2-1	30x36	7.5	13
108+45	26.1	RT	0	1	Black and Yellow Striped Object Marker	OM-3L	12x36	3	13
108+63	27.3	RT	0	1	Equestrain	W11-7	36x36	9	15.25
108+09	36.2	LT	0	1	Black and Yellow Striped Object Marker	OM-3R	12x36	3	13
108+71	32.6	LT	0	1	Equestrain	W11-7	36x36	9	15.25
110+93	32.9	RT	0	1	SPEED LIMIT 45	R2-1	30x36	7.5	13
110+91	35.1	LT	0	1	SPEED LIMIT 40	R2-1	30x36	7.5	13
114+81	35.6	LT	0	1	Equestrain	W11-7	36x36	9	15.25
117+99	30.3	RT	0	1	Black and Yellow Striped Object Marker	OM-3L	12x36	0	0
127+92	29.7	LT	0	1	SPEED LIMIT 45	R2-1	30x36	7.5	13
131+23	34.7	RT	0	1	SPEED LIMIT 45	R2-1	30x36	7.5	13
151+44	35.1	RT	7.5	0	SPEED LIMIT 35	R2-1	30x36	7.5	0
152+08	33.9	LT	7.5	0	SPEED LIMIT 45	R2-1	30x36	7.5	0
		TOTALS	18	13				101	165

SCHEDULE OF QUANTITIES - ROADWAY

From	To	Side	Measured Length	Total SY	X2020110 GRADING AND SHAPING SHOULDERS	48102100 AGGREGATE WEDGE SHOULDER, TYPE B	48203029 HOT-MIX ASPHALT SHOULDERS, 8"	64200105 SHOULDER RUMBLE STRIP	X0325866 CENTERLINE RUMBLE STRIPS	78000200 THERMOPLASTIC PAVEMENT MARKING - LINE 4" YELLOW C/L	78000200 THERMOPLASTIC PAVEMENT MARKING - LINE 4" WHITE EDGE	78300100 PAVEMENT MARKING REMOVAL	78100100 RAISED REFLECTIVE PAVEMENT MARKER
106+00	112+00	LT	0	0.0	0	0	0	0	295	396	0	132	10
		RT	4	1.9	0	0	2	4			4	1	
112+00	118+00	LT	211	103.5	2	4	104	211	600	1,054	211	422	26
		RT	600	288.7	6	11	289	600			600	200	
118+00	124+00	LT	600	288.7	6	11	289	600	600	1,200	600	600	30
		RT	600	288.7	6	11	289	600			600	200	
124+00	130+00	LT	528	254.0	5	10	254	528	600	1,044	528	524	26
		RT	586	281.9	6	11	282	586			586	195	
130+00	136+00	LT	600	288.7	6	11	289	600	600	1,000	600	533	25
		RT	262	126.1	3	5	126	262			262	87	
136+00	142+00	LT	454	218.4	5	8	218	454	600	1,044	454	499	26
		RT	535	257.4	5	10	257	535			535	178	
142+00	148+00	LT	0	0.0	0	0	0	0	299	486	0	162	12
		RT	31	14.9	0	1	15	31			31	10	
148+00	152+08	LT	0	0.0	0	0	0	0		0	0	0	0
		RT	0	0.0	0	0	0	0			0	0	
		TOTAL	5,011	2,413	50	94	2,413	5,011	3,594	6,224	5,011	3,745	155