

**SUMMARY OF QUANTITIES**

| ITEM NO. | SPECIALTY ITEM | SP | CODE NUMBER | ITEM  | UNIT   | TOTAL QUANTITY<br><i>URBAN</i><br><i>100% STATE</i> | CONSTRUCTION TYPE CODE   |  |
|----------|----------------|----|-------------|---|--------|---|--------------------------|--|
|          |                |    |             |   |        |   | BRIDGE, NEW CONSTRUCTION |  |
|          |                |    |             |   |        |   | 0008                     |  |
|          |                |    |             |   |        |   | 80% FED - 20% STATE      |  |
| 1        |                |    | 20100500    | TREE REMOVAL, ACRES                         | ACRE   | 0.25  | 0.25                     |  |
| 2        |                |    | 20200100    | EARTH EXCAVATION                            | CU YD  | 448   | 448                      |  |
| 3        |                |    | 20201200    | REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL | CU YD  | 4,843   | 4,843                    |  |
| 4        |                |    | 20400800    | FURNISHED EXCAVATION                        | CU YD  | 31,374  | 31,374                   |  |
| 5        |                |    | 21301052    | EXPLORATION TRENCH 52" DEPTH                | FOOT   | 1,000   | 1,000                    |  |
| 6        |                |    | 25000350    | SEEDING, CLASS 7                            | ACRE   | 3.25  | 3.25                     |  |
| 7        |                |    | 25000400    | NITROGEN FERTILIZER NUTRIENT                | POUND  | 293   | 293                      |  |
| 8        |                |    | 25000500    | PHOSPHORUS FERTILIZER NUTRIENT              | POUND  | 293   | 293                      |  |
| 9        |                |    | 25000600    | POTASSIUM FERTILIZER NUTRIENT               | POUND  | 293   | 293                      |  |
| 10       |                |    | 25100135    | MULCH, METHOD 4                             | ACRE   | 3.25  | 3.25                     |  |
| 11       |                |    | 28000200    | EARTH EXCAVATION FOR EROSION CONTROL        | CU YD  | 734   | 734                      |  |
| 12       |                |    | 28000250    | TEMPORARY EROSION CONTROL SEEDING           | POUND  | 9,295   | 9,295                    |  |
| 13       |                |    | 28000305    | TEMPORARY DITCH CHECKS                      | FOOT   | 364   | 364                      |  |
| 14       |                |    | 28000400    | PERIMETER EROSION BARRIER                   | FOOT   | 2,358   | 2,358                    |  |
| 15       |                |    | 28000500    | INLET AND PIPE PROTECTION                   | EACH   | 6   | 6                        |  |
| 16       |                |    | 28001000    | AGGREGATE (EROSION CONTROL)                 | TON    | 108   | 108                      |  |
| 17       |                |    | 28100105    | STONE RIPRAP, CLASS A3                      | SQ YD  | 47  | 47                       |  |
| 18       |                |    | 542A3367    | PIPE CULVERTS, CLASS A, TYPE 5 12"          | FOOT   | 372   | 372                      |  |
| 19       |                |    | 66400105    | CHAIN LINK FENCE, 4'                        | FOOT   | 675   | 675                      |  |
| 20       |                | *  | 66900200    | NON-SPECIAL WASTE DISPOSAL                  | CU YD  | 6000  | 6000                     |  |
| 21       |                | *  | 66900450    | SPECIAL WASTE PLANS AND REPORTS             | L SUM  | 1   | 1                        |  |
| 21       |                | *  | 66900205    | SPECIAL WASTE DISPOSAL                      | CU YD  | 80  | 80                       |  |
| 22       |                | *  | 66900530    | SOIL DISPOSAL ANALYSIS                      | EACH   | 1   | 1                        |  |
| 22       |                |    | 67000400    | ENGINEER'S FIELD OFFICE, TYPE A             | CAL MO | 6   | 6                        |  |
| 23       |                |    | 67100100    | MOBILIZATION                                | L SUM  | 1   | 1                        |  |
| 24       |                |    | 70106800    | CHANGEABLE MESSAGE SIGN                     | CAL MO | 20  | 20                       |  |
| 25       |                |    | X7010216    | TRAFFIC CONTROL AND PROTECTION, (SPECIAL)   | L SUM  | 1   | 1                        |  |
| 26       |                |    | Z0013797    | STABILIZED CONSTRUCTION ENTRANCE            | SQ YD  | 630   | 630                      |  |
| 27       |                |    | Z0013798    | CONSTRUCTION LAYOUT                         | L SUM  | 1   | 1                        |  |
| 28       |                |    | Z0019600    | DUST CONTROL WATERING                       | UNIT   | 304   | 304                      |  |
| 29       |                |    | Z0022800    | FENCE REMOVAL                               | FOOT   | 2,457   | 2,457                    |  |
| 30       |                |    | Z0030850    | TEMPORARY INFORMATION SIGNING               | SQ FT  | 103   | 103                      |  |
| 31       |                |    | Z0048665    | RAILROAD PROTECTIVE LIABILITY INSURANCE     | L SUM  | 1   | 1                        |  |
| 32       |                |    | Z0055905    | TEMPORARY CONSTRUCTION FENCE                | FOOT   | 160   | 160                      |  |
| 33       |                |    | Z0073002    | TEMPORARY SOIL RETENTION SYSTEM             | SQ FT  | 3,477   | 3,477                    |  |

*\*Specialty Items*

*Rev. 6-6-11*

|  |                             |                   |           |   |   |                         |                     |                       |        |                    |                |  |
|--|-----------------------------|-------------------|-----------|---|---|-------------------------|---------------------|-----------------------|--------|--------------------|----------------|--|
| FILE NAME =<br>...D168N06-SHT-S00-01.DGN | USER NAME = nrtterm         | DESIGNED - NMR    | REVISED - | <b>STATE OF ILLINOIS<br/>DEPARTMENT OF TRANSPORTATION</b> | <b>SUMMARY OF QUANTITIES<br/>CANADIAN PACIFIC RAILWAY</b> |                         | F.A.U. RTE.<br>1321 | SECTION<br>2010-134-T | COUNTY | TOTAL SHEETS<br>40 | SHEET NO.<br>4 |  |
|  | PLOT SCALE = 78.0000' / IN. | CHECKED - LGP     | REVISED - |   | SCALE:  | SHEET NO. 1 OF 1 SHEETS | STA.                | TO STA.               |        | CONTRACT NO. 60N06 |                |  |
|  | PLOT DATE = 3/25/2011       | DATE - 03/17/2011 | REVISED - |   | ILLINOIS FED. AID PROJECT                                 |                         |                     |                       |        |                    |                |  |
|  |                             |                   |           |   |   |                         |                     |                       |        |                    |                |  |