

SUMMARY OF QUANTITIES			URBAN		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 100 % STATE					
				0005					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	50	50					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	17	17					
75200110	SODDING, SALT TOLERANT	SQ YD	50	50					
40600300	AGGREGATE (PRIME COAT)	TON	74	74					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	12	12					
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	432	432					
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	148	148					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3068	3068					
42001300	PROTECTIVE COAT	SQ YD	4314	4314					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK	SQ FT	400	400					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2 INCH 1/4"	SQ YD	36518	36518					
44002222	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 5 1/2"	SQ YD	479	479					
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	217	217					
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	144	144					
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	75	75					
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	10	10					
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	20	20					
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4					
67100100	MOBILIZATION	L SUM	1	1					
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
70300100	SHORT TERM PAVEMENT MARKING	FOOT	10031	10031					
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SQ FT	312	312					
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	9965	9965					
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2339	2339					
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1123	1123					
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	675	675					
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3344	3344					
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	312	312					
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	9965	9965					
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2339	2339					
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1123	1123					

SUMMARY OF QUANTITIES			URBAN		CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 100 % STATE					
				0005					
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	675	675					
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	628	628					
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	377	377					
88600600	DETECTOR LOOP REPLACEMENT	FOOT	768	768					
X2020110	GRADING AND SHAPING SHOULDERS	UNIT	4	4					
X4060826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1581	1581					
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	50	50					
Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	500	500					
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4					
Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1					
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1					
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					

Rev. 6-13-11
*Specially Items

FILE NAME =	USER NAME = qureshya	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL ROUTE 25 SUMMARY OF QUANTITIES	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pw_wor\k\pw\of\qureshya\0252940\DI30511-stl-plan.dgn	PLOT SCALE = 500001' / IN.	DRAWN -	REVISED -			2503	2010-151-RS	KANE	20	3	
	PLOT DATE = 4/16/2011	CHECKED -	REVISED -			CONTRACT NO. 60N35					
		DATE -	REVISED -			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT					