

SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			URBAN	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 100 % STATE 0005					CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 100 % STATE 0005				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	17	17					*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	675	675				
40600300	AGGREGATE (PRIME COAT)	TON	74	74					*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	628	628				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	12	12					78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	377	377				
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					88600600	DETECTOR LOOP REPLACEMENT	FOOT	768	768				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	432	432					X2020110	GRADING AND SHAPING SHOULDERS	UNIT	4	4				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	148	148					X4060826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1581	1581				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3068	3068					X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	50	50				
42001300	PROTECTIVE COAT	SO YD	4314	4314					Z0004562	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	12940	12940				
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	36518	36518					Z0030850	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4				
44002222	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 5 1/2"	SO YD	479	479					Z0048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1				
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SO YD	217	217					70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1				
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SO YD	144	144					70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1				
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SO YD	75	75													
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	10	10													
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	20	20													
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4													
67100100	MOBILIZATION	L SUM	1	1													
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1													
70300100	SHORT TERM PAVEMENT MARKING	FOOT	10031	10031													
70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	312	312													
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	9965	9965													
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	2339	2339													
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1123	1123													
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	675	675													
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	3344	3344													
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	312	312													
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	9965	9965													
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2339	2339													
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1123	1123													

\*Separately Items

Rev.

FILE NAME =	USER NAME = qureshtya	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>IL ROUTE 25 SUMMARY OF QUANTITIES</b>	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pwr_work\pwr\qureshtya\0252940\030511-sh-pln.dgn	DRAWN -	REVISED -	2503			2010-151-RS	KANE	20	3	
PLOT SCALE = 50.0001' / IN.	CHECKED -	REVISED -	CONTRACT NO. 60N35							
PLOT DATE = 4/16/2011	DATE -	REVISED -	SCALE:			SHEET NO. OF SHEETS	STA. TO STA.	FED. ROAD DIST. NO. 1	ILLINOIS FED. AID PROJECT	