

SUMMARY OF QUANTITIES				URBAN 100% STATE				CONSTRUCTION TYPE CODE: 0005				SUMMARY OF QUANTITIES				URBAN 100% STATE				CONSTRUCTION TYPE CODE: 0005				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES					CODE NO	ITEM	UNIT	TOTAL QUANTITIES					CODE NO	ITEM	UNIT	TOTAL QUANTITIES					
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	149	149				58700300	CONCRETE SEALER	SO FT	11248	11248												
20400800	FURNISHED EXCAVATION	CU YD	480	480				* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	8	8												
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	848	848				63200310	GUARDRAIL REMOVAL	FOOT	400	400												
25000210	SEEDING, CLASS 2A	ACRE	0.18	0.18				67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6												
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	16	16				67100100	MOBILIZATION	L SUM	1	1												
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	16	16				70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1												
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	16	16				70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1												
25100630	EROSION CONTROL BLANKET	SO YD	848	848				70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1												
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	141	141				70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1												
40600300	AGGREGATE (PRIME COAT)	TON	706	706				70300100	SHORT TERM PAVEMENT MARKING	FOOT	27123	27123												
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	265	265				70300210	TEMPORARY PAVEMENT MARKING LETTERS AND SYMBOLS	SO FT	763.2	763.2												
40600895	CONSTRUCTING TEST STRIP	EACH	2	2				70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	92616	92616												
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	1201	1201				70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	6146	6146												
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	190	190				70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	740	740												
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	14820	14820				70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1555	1555												
42001300	PROTECTIVE COAT	SO YD	556	556				70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	1020	1020												
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SO YD	1255	1255				70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	9041	9041												
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	176430	176430				* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	763.2	763.2												
44002213	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3 1/4"	SO YD	1043	1043				* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	92616	92616												
44201749	CLASS D PATCHES, TYPE I, 9 INCH	SO YD	17	17				* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	6146	6146												
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SO YD	422	422				* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	740	740												
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SO YD	293	293				* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1555	1555												
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SO YD	261	261				* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	1020	1020												
44201785	CLASS D PATCHES, TYPE I, 12 INCH	SO YD	54	54				* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	764	764												
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SO YD	471	471				* 78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	46	46												
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SO YD	335	335				* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	2775	2775												
44201796	CLASS D PATCHES, TYPE IV, 12 INCH	SO YD	626	626				* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	8	8												
44201803	CLASS D PATCHES, TYPE II, 13 INCH	SO YD	52	52				78300100	PAVEMENT MARKING REMOVAL	SO FT	161	161												
44201807	CLASS D PATCHES, TYPE III, 13 INCH	SO YD	40	40																				
44201809	CLASS D PATCHES, TYPE IV, 13 INCH	SO YD	1451	1451																				
48101620	AGGREGATE SHOULDERS, TYPE B 10"	SO YD	120	120																				
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	325	325																				

FILE NAME =	USER NAME = mdy/ja	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION				ILL 171 SUMMARY OF QUANTITIES				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2:\work\p\rd\mdy\ja\0248692\01330H-stt-plandp	DRAWN -	REVISED -	577									D-RS-7	WILL	38	3	
PLOT SCALE = 507684' / IN.	CHECKED -	REVISED -	CONTRACT NO. 60N60													
PLOT DATE = 3/29/2011	DATE -	REVISED -	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT													

* SPECIALTY ITEMS