ROUTE: IL 120 (1 mi e/o US 12 to US 12) - Jointed Pavement | PATCHING = CLASS B

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
		EB	1	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
			1	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
			LT	10	6	60	7
			LT	12	6	72	8
			LT	12	6	72	8
			2	12	6	72	8
			RT	19	6	114	13
			RT	19	6	111	12
			1	12	6	72	8
			2	12	6	72	8
			1	12	6	72	8
			RT	17	6	102	11
			RT	8	9	68	8
			2	12	9	102	11
			1	12	9	102	11
			RT	12	6	72	8
			2	12	6	72	8
			1	12	6	72	8
		WB	2	12	10	120	13
			1	12	10	120	13
			LT	10	6	60	7
			LT	12	6	72	8
			LT	12	6	72	8
			2	12	6	72	8
			1	12	6	72	8
			LT	16	6	96	11
			2	12	6	72	8
			2	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
			1	12	6	72	8
			LT	12	6	72	8
			LT	12	6	72	8
			LT	12	6	72	8
			1	12	6	72	8
			1	12	6	72	8
			2	12	6	72	8
			1	12	6	72	8
			2	12	8	90	10
			1	12	8	90	10
			RT	12	8	90	10
			2	12	9	102	11
			1	12	9	102	11
			RT	12	9	102	11
			RT	16	6	96	11
			2	12	6	72	8
			LT	12	6	72	8
		TOTALS:			346 FT		472 SY

ROUTE: US 12 at IL 120 Intersection - Jointed Pavement | PATCHING = CLASS B

CROSS STREETS FROM	CROSS STREETS TO	DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
US 12		EB	LT	12	6	72	8
West to East		EB	2	12	6	72	8
		EB	1	12	6	72	8
		EB	2	12	6	72	8
		EB	1	12	6	72	8
		EB	2	12	8	96	11
		EB	1	12	6	72	8
		EB	2	12	6	72	8
		EB	1	12	6	72	8
		EB	2	12	6	72	8
East to West		WB	1	12	6	72	8
		WB	2	12	6	72	8
		WB	1	12	6	72	8
		WB	LT	10	6	60	7
		WB	RT	9	6	54	6
		WB	RT	10	6	60	7
		WB	LT	12	6	72	8
		WB	RT	11	6	66	7
		WB	RT	12	6	72	8
		WB	RT	12	6	72	8
		WB	RT	12	15	180	20
		WB	LT	12	8	96	11
		WB	LT	16	14	224	25
		WB	RT	12	6	72	8
		WB	RT	15	14	203	23
		WB	RT	12	6	72	8
		WB	RT	12	6	72	8
		WB	RT	8	6	48	5
IL120		WB	1	12	6	72	8
East to West		WB	2	12	6	72	8
		WB	1	12	6	72	8
		WB	2	12	6	72	8
West to East		EB	1	12	8	90	10
		EB	2	12	8	90	10
		EB	1	12	6	72	8
		EB	2	12	6	72	8
		EB	1	12	6	72	8
Radii	WB 12 to EB 120			22	10	209	23
				13	6	78	9
				11	6	66	7
	EB 120 to EB 12			16	6	98	11
				13	6	78	9
				18	6	108	12
				9	5	45	5
				9	5	45	5
	EB 12 to WB 120			9	5	45	5
				7	7	49	5
				15	6	90	10
				9	5	45	5
	WB 120 to WB 12			23	4	92	10
				13	6	78	9
				9	5	45	5
				8	6	48	5
				12	6	69	8
		TOTALS:			354 FT		484 SY

FILE NAME = c:\pw_work\pwidot\velichkovvv\d0259997\Design.dgn	USER NAME = VelichkovVV	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 4/13/2011	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
IL 120 & US 12

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2011-006-PP	LK. & MCH.	23	12

CONTRACT NO. 60N94

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT