ROUTE: IL 72 (IL 47 to I-90)

CROSS STREETS		DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR
FROM	TO	(EB/WB) (NB/SB)	NO. (1, 2, 3)	PATCH WIDTH	PATCH LENGTH	AREA (SQ FT)	AREA (SQ YD)
		E	1	12	6	72	8
		W	1	12	6	72	8
		E	1	12	6	72	8
		W	1	12	6	72	8
		W	1	12	6	72	8
		E	1	12	120	1440	160
		W	1	12	6	72	8
		E	1	12	6	72	8
		W	1	12	6	72	8
		W	1	12	6	72	8
		E	1	12	6	72	8
		E	1	12	6	72	8
		E	1	12	6	72	8
		W	1	12	6	72	8
		W	1	12	6	72	8
		W	1	12	30	360	40
		E	1	12	6	72	8
		W	1	12	6	72	8
		W	1	12	6	72	8
		E	1	12	6	72	8
		W	1	12	6	72	8
		E	1	12	6	72	8
		W	1	12	6	72	8
		E	1	12	6	72	8
		W	1	12	6	72	8
		E	1	12	6	72	8
		W	1	12	6	72	8
	IL 90	W	1	12	6	72	8
				TOTALS:	3811 FT		5079 SY

ROUTE: IL 68 (IL 72 to IL 62)

CROSS STREETS		DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR
FROM	TO	(EB/WB) (NB/SB)	NO. (1, 2, 3)	PATCH WIDTH	PATCH LENGTH	AREA (SQ FT)	AREA (SQ YD)
IL 72 TO:		EB	1	12	10	120	13
		EB	2	12	10	120	13
		WB	1	12	10	120	13
		WB	2	12	20	240	27
		EB	1	12	10	120	13
		EB	1	12	6	72	8
		EB	2	12	6	72	8
		EB	1	12	6	72	8
		EB	1	12	20	240	27
		EB	2	12	75	900	100
		EB	1	12	15	180	20
		EB	2	12	30	360	40
		EB	1	12	25	300	33
		EB	2	12	6	72	8
		EB	1	12	6	72	8
		EB	2	12	6	72	8

ROUTE: IL 68 (IL 72 to IL 62)

CROSS STREETS		DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR
FROM	TO	(EB/WB) (NB/SB)	NO. (1, 2, 3)	PATCH WIDTH	PATCH LENGTH	AREA (SQ FT)	AREA (SQ YD)
LORIEN CT.		WB	1	18	20	360	40
		WB	1	18	6	108	12
		WB	1	18	6	108	12
		WB	1	18	6	108	12
		WB	1	18	6	108	12
		WB	1	18	6	108	12
		WB	1	12	6	72	8
		WB	1	12	6	72	8
		WB	1	12	6	72	8
		EB	1	12	6	72	8
		EB	1	12	6	72	8
		EB	1	12	20	240	27
		WB	1	12	6	72	8
		EB	1	12	6	72	8
		EB	1	12	10	120	13
		EB	1	12	10	120	13
		WB	LTL	12	10	120	13
		WB	1	12	10	120	13
		EB	1	12	6	72	8
		WB	1	12	10	120	13
		WB	1	12	6	72	8
		EB	LTL	12	6	72	8
		EB	LTL	12	10	120	13
		EB	1	12	10	120	13
		WB	LLJT.	4	100	400	44
		WB	CL	4	75	300	33
		EB	LLJT	4	100	400	44
		EB	1	18	20	360	40
		EB	1	12	6	72	8
		WB	1	12	20	240	27
		WB	LTL	15	60	900	100
		EB	LL JT	12	50	600	67
		WB	1	12	8	96	11
		EB	1	15	8	120	13
	ALDIAS DRIVE	EB	1	12	8	96	11
		WB	1	12	100	1200	133
		EB	1	12	6	72	8
		EB	1	12	6	72	8
		EB	1	12	6	72	8
		EB	LL JT	4	100	400	44
		WB	1	12	6	72	8
		WB	1	12	6	72	8
		WB	1	12	6	72	8
		EB	1	12	6	72	8
		WB	1	12	6	72	8
		EB	1	12	6	72	8
		EB	1	12	75	900	100
		WB	1	12	6	72	8
		WB	1	12	6	72	8
		EB	1	12	75	900	100
		EB	1	18	6	108	12
		WB	1	15	75	1125	125
		EB	LL JT	4	100	400	44
		WB	1	18	75	1350	150
		EB	2	12	6	72	8
		EB	2	12	6	72	8

CONTINUED ON NEXT SHEET

FILE NAME = c:\pw_work\pwidot\velichkovvv\d0260186\Design.dgn

USER NAME = VelichkovVV | PLOT SCALE = 100.0000 ' / IN. | PLOT DATE = 4/13/2011

DESIGNED - | DRAWN - | CHECKED - | DATE -

REVISED - | REVISED - | REVISED - | REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
IL 72 & IL 68

SCALE: | SHEET NO. OF SHEETS | STA. | TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2011-011-RS	KANE	36	19
		CONTRACT NO. 60N99		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		