ROUTE: IL 62 (IL 31 to Sandbloom)

CROSS STREETS		DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
FROM	TO						
		EB	2	12	6	72	8
		EB	1	12	6	72	8
		EB	2	12	6	72	8
		EB	1	12	6	72	8
		EB	2	12	25	300	33
		EB	1	12	12	144	16
		EB	2	12	12	144	16
		EB	1	12	6	72	8
		EB	2	12	6	72	8
		EB	1	12	6	72	8
		EB	2	12	6	72	8
		EB	1	12	6	72	8
		EB	2	12	6	72	8
		EB	LTL	12	6	72	8
		EB	1	12	6	72	8
		EB	LTL	12	6	72	8
		EB	1	12	6	72	8
		EB	2	12	6	72	8
		EB	LTL	12	6	72	8
		EB	1	12	6	72	8
		EB	2	12	6	72	8
		EB	LTL	12	6	72	8
		EB	1	12	6	72	8
	SANDBLOOM RD	EB	2	12	6	72	8
		WB	1	12	6	72	8
		WB	2	12	6	72	8
		WB	1	12	6	72	8
		WB	2	12	6	72	8
		WB	1	12	6	72	8
		WB	2	12	6	72	8
		WB	1	12	6	72	8
		WB	2	12	6	72	8
		WB	1	12	12	144	16
		WB	MED	12	6	72	8
		WB	1	12	25	300	33
		WB	2	12	6	72	8
		WB	2	12	45	540	60
		WB	1	12	6	72	8
		WB	2	12	6	72	8
		WB	1	12	40	480	53
		WB	1	12	6	72	8
		WB	2	12	6	72	8
		WB	1	12	6	72	8
		WB	2	12	6	72	8
		WB	1	12	6	72	8
		WB	2	12	6	72	8
		WB	1	12	6	72	8
		WB	1	12	6	72	8
		WB	2	12	6	72	8
		WB	1	12	6	72	8
		WB	1	12	6	72	8
		WB	1	12	10	120	13
		WB	2	12	6	72	8
		WB	1	12	6	72	8
		WB	2	12	8	96	11
		WB	1	12	6	72	8
		WB	2	12	6	72	8
		WB	1	12	6	72	8

ROUTE: IL 62 (IL 31 to Sandbloom)

CROSS STREETS		DIRECTION (EB/WB) (NB/SB)	LANE NO. (1, 2, 3)	PAVEMENT PATCH WIDTH	PAVEMENT PATCH LENGTH	REPAIR AREA (SQ FT)	REPAIR AREA (SQ YD)
FROM	TO						
		WB	2	12	6	72	8
		WB	1	12	30	360	40
		WB	2	12	6	72	8
	FOUNTAIN SQUARE	WB	2	12	6	72	8
		WB	1	12	25	300	33
		WB	2	12	6	72	8
		WB	2	12	6	72	8
		WB	2	12	6	72	8
		WB	2	12	6	72	8
		WB	1	12	6	72	8
		WB	1	12	6	72	8
		WB	2	12	6	72	8
		WB	1	12	6	72	8
		WB	2	12	6	72	8
		WB	1	12	6	72	8
		WB	2	12	6	72	8
		WB	1	12	6	72	8
		WB	2	12	6	72	8
		WB	2	12	6	72	8
		WB	2	12	6	72	8
		WB	1	12	6	72	8
		WB	1	12	35	420	47
		WB	2	12	6	72	8
		WB	2	12	6	72	8
		WB	2	12	6	72	8
		WB	2	12	6	72	8
		WB	1	12	6	72	8
		WB	2	12	6	72	8
		WB	1	12	6	72	8
		WB	2	12	6	72	8
		WB	1	12	30	360	40
		WB	2	12	6	72	8
		WB	2	12	6	72	8
		WB	1	12	20	240	27
		WB	2	12	6	72	8
		WB	2	12	6	72	8
		WB	1	12	6	72	8
		WB	2	12	6	72	8
		WB	1	12	6	72	8
		WB	2	12	6	72	8
		WB	1	12	6	72	8
		WB	2	12	6	72	8
		WB	LTL+1	18	6	108	12
		WB	2	12	6	72	8
		WB	LTL	12	6	72	8
		WB	LTL	12	6	72	8
		WB	1	12	6	72	8
		WB	2	12	6	72	8
		WB	1	12	6	72	8
		WB	2	12	6	72	8

CONTINUED ON NEXT SHEET

FILE NAME = c:\pw_work\pwidot\velichkovvv\d0260186\Design.dgn	USER NAME = VelichkovVV	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 4/13/2011	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
IL 62

SCALE: | SHEET NO. OF SHEETS | STA. | TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2011-011-RS	KANE	36	25
		CONTRACT NO. 60N99		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		