ROUTE: Oakton St. (Busse Rd to IL 72) or (Oakton/IL 72 S-Curve)

CROSS STREETS		DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR
FROM	TO	(EB/WB) (NB/SB)	NO. (1, 2, 3)	PATCH WIDTH	PATCH LENGTH	AREA (SQ FT)	AREA (SQ YD)
Oakton/IL 72	Busee Rd	Intersection	Int	2	60	120	13
		Intersectio	Int	15	4	60	7
		E/B	2	12	4	48	5
		E/B	3	12	4	48	5
		E/B	2	12	4	48	5
		E/B	3	12	4	48	5
		E/B	2	12	4	48	5
		E/B	3	12	4	48	5
		E/B	2	12	4	48	5
		E/B	3	12	4	48	5
		E/B	1	12	4	48	5
		E/B	2	12	4	48	5
		E/B	3	12	4	48	5
		E/B	LT	12	4	48	5
		E/B	3	12	7	84	9
		E/B	1	12	4	48	5
		E/B	2	12	4	48	5
		W/B	1	12	4	48	5
		W/B	2	12	4	48	5
		W/B	2	12	4	48	5
		W/B	3	12	4	48	5
		W/B	3,RT	2	150	300	33
		W/B	1	12	4	48	5
		W/B	2	12	4	48	5
		W/B	3	12	4	48	5
		W/B	RT	12	4	48	5
		W/B	RT	12	4	48	5
		W/B	RT	12	4	48	5
		W/B	RT	12	4	48	5
		W/B	1,2	2	30	60	7
		W/B	1	12	4	48	5
		W/B	2	12	4	48	5
		W/B	RT	12	4	48	5
		W/B	RT	12	4	48	5
		W/B	RT	12	4	48	5
		W/B	RT	12	4	48	5
		W/B	RT	12	4	48	5
		W/B	R+1,RT2	2	120	240	27
		W/B	INT	12	4	48	5
		W/B	INT	12	4	48	5
		W/B	INT	12	4	48	5
		W/B	Ramp,L1	12	100	1200	133
		W/B	Ramp1,2	4	100	400	44
Busee Rd	IL 72	E/B	RT	12	4	48	5
		E/B	RT	12	4	48	5
		E/B	RT	12	4	48	5
		E/B	RT	12	4	48	5
		E/B	RT	12	4	48	5
		E/B	RT	12	4	48	5
		W/B	1	12	4	48	5
		W/B	2	12	4	48	5
		W/B	3	12	4	48	5
		W/B	2,3	2	30	60	7
		W/B	3,RT	2	70	140	16
		W/B	RT	15	4	60	7
		TOTALS:			847 FT		532 SY

ROUTE: Skokie Rd. (Old Orchard to Golf Rd.)

CROSS STREETS		DIRECTION	LANE	PAVEMENT	PAVEMENT	REPAIR	REPAIR
FROM	TO	(EB/WB) (NB/SB)	NO. (1, 2, 3)	PATCH WIDTH	PATCH LENGTH	AREA (SQ FT)	AREA (SQ YD)
Old Orchard	Golf Rd.	SB	3	5	12	60	7
			3	5	12	60	7
			3	5	12	60	7
			3	5	12	60	7
			3	5	12	60	7
			3	5	12	60	7
			3	5	8	40	4
			3	2	150	300	33
		NB	3	5	12	60	7
			3	2	200	400	44
			3	2	200	400	44
			3	2	200	400	44
		SB	2	5	12	60	7
			2	5	12	60	7
			2	5	12	60	7
			2	5	12	60	7
			2	15	12	180	20
			2	2	300	600	67
		NB	2	5	12	60	7
			2	5	12	60	7
			2	5	12	60	7
			2	5	12	60	7
			2	5	12	60	7
			2	5	12	60	7
			2	5	12	60	7
			2	12	15	180	20
			2	2	20	40	4
			2	2	200	400	44
		SB	1	5	12	60	7
			1	5	12	60	7
			1	5	12	60	7
			1	5	12	60	7
			1	5	12	60	7
			1	12	15	180	20
			1	12	15	180	20
			1	12	15	180	20
			1	2	300	600	67
			1	2	200	400	44
			1	2	200	400	44
		NB	1	5	12	60	7
			1	5	12	60	7
			1	5	12	60	7
			1	5	12	60	7
			1	5	12	60	7
			1	5	12	60	7
		TOTALS:			2446 FT		762 SY

FILE NAME = c:\pw_work\pwidot\velichkovvv\d0260192\Design.dgn	USER NAME = VelichkovVV	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 100.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 4/14/2011	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

PATCHING SCHEDULE
OAKTON ST. & SKOKIE RD.

SCALE: | SHEET NO. OF SHEETS | STA. | TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
VAR.	2011-013-RS	COOK	70	50
		CONTRACT NO. 60P02		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		