

INDEX OF SHEETS

- 1 COVER SHEET
- 2 INDEX OF SHEETS, STANDARDS, COMMITMENTS, AND GENERAL NOTES
- * 3 SUMMARY OF QUANTITIES
- 4 GENERAL DATA
- 5-6 HIGH MAST LIGHT TOWER FOUNDATION REPAIRS
- 7 ANCHOR ROD DETAILS
- 8-10 ROADWAY LIGHTING LOCATION
- 11-12 CONCRETE RUSTICATION DETAILS
- 13-15 TOWER DETAILS
- * 16-17 ELECTRICAL DETAILS
- * 18-19E DISTRICT STANDARDS

* 3A.-3D. MAINTENANCE OF TRAFFIC AND DETOUR PLAN

* 17A-17C. LIGHTING DETAILS

* 19A-19E ADDED

STATE STANDARDS

000001-06	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
001001-02	AREA OF REINFORCEMENT BARS
001006	DECIMAL OF AN INCH AND OF A FOOT
701427	LANE CLOSURE, MULTILANE, INTERMITTENT OR MOVING OPER., FOR SPEEDS ≤ 40 MPH
701901-01	TRAFFIC CONTROL DEVICES
720001-01	SIGN PANEL MOUNTING DETAILS
720011-01	METAL POSTS FOR SIGNS, MARKERS & DELINEATORS
728001-01	TELESCOPING STEEL SIGN SUPPORT
729001-01	APPLICATIONS OF TYPES A & B METAL POSTS
835001	LIGHT TOWER
837001	LIGHT TOWER FOUNDATION
701601-07	
704001-06	

DISTRICT STANDARDS *(included as plan sheets)*

TC08	FREEWAY ENTRANCE AND EXIT RAMP CLOSURE DETAILS
TC22	ARTERIAL ROAD INFORMATION SIGN
TC10	
TC17	
TC-21	
TC-24	

COMMITMENTS

NO COMMITMENTS HAVE BEEN MADE FOR THIS PROJECT.

GENERAL NOTES

1. PLAN DIMENSIONS AND DETAILS RELATIVE TO EXISTING PLANS ARE SUBJECT TO NOMINAL CONSTRUCTION VARIATIONS. THE CONTRACTOR SHALL FIELD VERIFY EXISTING DIMENSIONS AND DETAILS AFFECTING NEW CONSTRUCTION AND MAKE NECESSARY APPROVED ADJUSTMENTS PRIOR TO CONSTRUCTION OR ORDERING OF MATERIALS. SUCH VARIATIONS SHALL NOT BE CAUSE FOR ADDITIONAL COMPENSATION FOR A CHANGE IN SCOPE OF THE WORK, HOWEVER, THE CONTRACTOR WILL BE PAID FOR THE QUANTITY ACTUALLY FURNISHED AT THE UNIT PRICE BID FOR THE WORK.
2. THE FENCE ON THE RETAINING WALLS SHALL BE CAREFULLY REMOVED TO ALLOW ROOM FOR REPAIRS. THE CONTRACTOR SHALL REINSTALL THE FENCE UPON COMPLETION OF CONSTRUCTION, AND IS RESPONSIBLE FOR THE FENCE DURING CONSTRUCTION. EXISTING HARDWARE MAY BE REUSED WITH THE APPROVAL OF THE ENGINEER. COST IS INCLUDED WITH CONCRETE REMOVAL.
3. WHEN ARTIFICIAL LIGHTING IS USED DURING NIGHT OPERATIONS, THE CONTRACTOR SHALL EXERCISE THE UTMOST PRECAUTIONS IN PREVENTING ADVERSE VISIBILITY TO THE MOTORING PUBLIC AND ADJOINING RESIDENTIAL AREAS.
4. THE CONTRACTOR SHALL CONTACT THE TRAFFIC CONTROL SUPERVISOR AT (847) 705-4470 A MINIMUM OF 72 HOURS PRIOR TO THE PLACEMENT OF ANY TEMPORARY TRAFFIC CONTROL DEVICES.
5. THE CONTRACTOR SHALL CONTACT <<PATRICE HARRIS>>, THE AREA TRAFFIC FIELD TECHNICIAN, AT 708-597-9800 TWO (2) WEEKS PRIOR TO THE PLACEMENT OF PERMANENT PAVEMENT MARKINGS.
6. THE CONTRACTOR SHALL REFER TO THE SPECIAL PROVISIONS FOR MAINTENANCE OF TRAFFIC PLANS. ANY MODIFICATION TO THESE PLANS SHALL BE APPROVED BY THE ENGINEER.
7. THE CONTRACTOR SHALL REQUEST AND GAIN APPROVAL FROM THE ILLINOIS DEPARTMENT OF TRANSPORTATION'S EXPRESSWAY TRAFFIC OPERATIONS ENGINEER (847-705-4151) TWENTY-FOUR (24) HOURS IN ADVANCE OF ALL DAILY LANE, RAMP AND SHOULDER CLOSURES AND SEVENTY-TWO (72) HOURS IN ADVANCE OF ALL PERMANENT AND WEEKEND CLOSURES ON ALL FREEWAYS AND/OR EXPRESSWAYS IN DISTRICT ONE.
8. BEFORE STARTING ANY WORK, THE CONTRACTOR SHALL CALL "C.U.A.N." (CHICAGO UTILITY ALERT NETWORK) AT (312) 744-7000, OR "J.U.L.I.E." (JOINT UTILITY LOCATION INFORMATION FOR EXCAVATION) AT (800) 892-0123 FOR FIELD LOCATIONS OF BURIED UTILITIES. 48-HOUR ADVANCED NOTIFICATION IS REQUIRED.



USER NAME = #USER#
 PLOT SCALE = #SCALE#
 PLOT DATE = #DATE#

DESIGNED - SEW
 DRAWN - SEW
 CHECKED - FML
 DATE - 04/2011

REVISED -
 REVISED -
 REVISED -
 REVISED -

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

INDEX OF SHEETS, STANDARDS, COMMITMENTS, AND GENERAL NOTES
 FAI 9094 HIGH MAST LIGHT TOWER FOUNDATION REPAIRS

SCALE: N/A SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
90/94	2011-021-L	COOK	19	2
CONTRACT NO. 60P16				
ILLINOIS FED. AID PROJECT				