

SUMMARY OF QUANTITIES

URBAN
100% STATE

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	0021 STRUCTURE
31101000	SUBBASE GRANULAR MATERIAL, TYPE B	TON	3.5	3.5
44003100	MEDIAN REMOVAL	SQ FT	76	76
50102400	CONCRETE REMOVAL	CU YD	16.9	16.9
50300225	CONCRETE STRUCTURES	CU YD	16.9	16.9
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1710	1710
60618324	CONCRETE MEDIAN SURFACE, 6 INCH (SPECIAL)	SQ FT	36	36
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2	2
67100100	MOBILIZATION	L SUM	1	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	2	2
X0324534	REMOVE AND REINSTALL LIGHT POLES	L SUM	1	1
X6065740	CONCRETE MEDIAN SURFACE, 5" (MODIFIED)	SQ FT	36	36
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1
X7015005	CHANGEABLE MESSAGE SIGN	CAL DA	40	40
Z0026346	NIGHTTIME WORK ZONE LIGHTING	L SUM	1	1
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	80	80
Z0033028	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	1	1
70301000	WORKZONE PAVEMENT MARKING REMOVAL	SQ FT	899	899
70400100	TEMPORARY CONCRETE BARRIER	FOOT	1762.5	1762.5
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	400	400
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	282	282
78300100	PAVEMENT MARKING REMOVAL	SQ FT	134	134
* 81800300	AERIAL CABLE, 3-1/C NO. 2 WITH MESSENGER WIRE	FOOT	1520	1520
* 83057175	LIGHT POLE, WOOD, 35 FT. CLASS 3 WITH 15 FT. MAST ARM	EACH	6	6
* 84100110	REMOVAL OF TEMPORARY LIGHTING UNIT	EACH	6	6
* 84400205	RELOCATE EXISTING LIGHT TOWER	EACH	3	3
X7010216	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1
X7030030	WET REFLECTIVE TEMPORARY TAPE TYPE III, 4 INCH	FOOT	2696	2696
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY RE-DIRECTIVE, NARROW), TEST LEVEL 3	EACH	2	2
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-RE-DIRECTIVE), TEST LEVEL 3	EACH	2	2

*Specialty Items



USER NAME = #USER#
DESIGNED
DRAWN - SEW
CHECKED - FML
DATE - 04/2011

REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
FAI 9094 HIGH MAST LIGHT TOWER FOUNDATION REPAIRS
SCALE: N/A SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.I. RTE. 90/94	SECTION 2011-021-L	COUNTY COOK	TOTAL SHEETS 19	SHEET NO. 3
CONTRACT NO. 60P16			ILLINOIS FED. AID PROJECT	

Rev.