

INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	TITLE SHEET
2	INDEX OF SHEETS, STATE STANDARDS AND GENERAL NOTES
3	SUMMARY OF QUANTITIES
4 - 15	PROPOSED PLANS AND PAVEMENT MARKING PLANS
16	CRACK & JOINT SEALING DETAIL
17	TRAFFIC CONTROL DETAILS FOR FREEWAY SINGLE & MULTI-LANE WEAVE (TC-09)
18 - 19	MULTI-LANE FREEWAY PAVEMENT MARKING DETAILS (TC-12)
20	TRAFFIC CONTROL DETAILS FOR FREEWAY SHOULDER CLOSURES AND PARTIAL RAMP CLOSURES (TC-17)

20A. TC-8 

STANDARDS

- 701400-05 APPROACH TO LANE CLOSURE, FREEWAY/EXPRESSWAY
- 701401-06 LANE CLOSURE, FREEWAY/EXPRESSWAY
- 701411-07 LANE CLOSURE, MULTILANE, AT ENTRANCE OR EXIT RAMP, FOR SPEEDS \geq 45 MPH
- 701426-04 LANE CLOSURE, MULTILANE, INTERMITTENT OR MOVING OPER., FOR SPEEDS \geq 45 MPH
- 701446-02 TWO LANE CLOSURE FREEWAY/EXPRESSWAY
- 701901-01 TRAFFIC CONTROL DEVICES

GENERAL NOTES

BEFORE STARTING ANY EXCAVATION, THE CONTRACTOR SHALL CALL "C.U.A.N." (CHICAGO UTILITY ALERT NETWORK) AT (312)744-7000 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS UTILITIES. (48 HOUR NOTIFICATION IS REQUIRED).

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.

THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON TOLLWAY PROPERTY WITHOUT WRITTEN PERMISSION FROM THE ISTHA.

IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND CONDITIONS EXISTING IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.


THE CONTRACTOR SHALL CONTACT THE DISTRICT ONE TRAFFIC CONTROL SUPERVISOR AT (847) 705-4151 A MINIMUM OF 72 HOURS IN ADVANCE OF BEGINNING WORK.

THE ILLINOIS STATE TOLL HIGHWAY AUTHORITY SHALL BE NOTIFIED AT LEAST 48 HOURS IN ADVANCE FOR ANY LANE CLOSURE DURING THE AM AND PM PEAK HOURS FOR WORK ADJACENT TO THE NORTHWEST TOLLWAY SECTION. ISTHA DAILY TRAFFIC CONTROL AUTHORIZATION AT (630) 241-6800 EXT 3822

THE ENGINEER SHALL CONTACT THE DISTRICT ONE TRAFFIC CONTROL SUPERVISOR, AT (847) 705-4151 A MINIMUM OF TWO (2) WEEKS PRIOR TO THE PLACEMENT OF PERMANENT PAVEMENT MARKINGS.

ALL CRACK ROUTING & CRACK SEALING LOCATIONS WILL BE DETERMINED IN THE FIELD BY THE ENGINEER. CRACK ROUTING SHALL BE OMITTED WHERE VEHICLE DETECTOR LOOPS & RAISED REFLECTIVE PAVEMENT MARKERS ARE PRESENT IN THE PAVEMENT.

DO NOT SCALE PLANS FOR CONSTRUCTION DIMENSIONS.

 Rev. 6-2-11

FILE NAME = D151111-sh-t-plan.dgn	USER NAME = nathanbc	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	I-90 (KENNEDY EXPRESSWAY) INDEX OF SHEETS, LIST OF STATE STANDARDS & PLAN NOTES	F.A.I. RTE. 90	SECTION 2011-029-1	COUNTY COOK	TOTAL SHEETS 20	SHEET NO. 2	
	PLOT SCALE = 100.0000' / IN.	DRAWN -	REVISED -			SCALE: 1"= 50'	SHEET NO. OF SHEETS	STA. TO STA.	CONTRACT NO. 60P32		
	PLOT DATE = 4/8/2011	CHECKED -	REVISED -			ILLINOIS FED. AID PROJECT					
		DATE -	REVISED -								