

				CONSTRUCTION CODE	
				100% LAKE CD.	
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY 0003 URBAN	
28100203	STONE RIPRAP, CLASS A2	TON	13	13	
28200200	FILTER FABRIC	SQ YD	40	40	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	1808	1808	
40600300	AGGREGATE (PRIME COAT)	TON	27.1	27.1	
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES,	TON	60	60	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	887	887	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1043	1043	
44002216	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 4"	SQ YD	268	268	
44004250	PAVED SHOULDER REMOVAL	SQ YD	2687	2687	
44201749	CLASS D PATCHES, TYPE I, 9 INCH	SQ YD	5	5	
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	221	221	
50104400	CONCRETE HEADWALL REMOVAL	EACH	1	1	
50105220	PIPE CULVERT REMOVAL	FOOT	105	105	
5421A012	PIPE CULVERTS, CLASS A, TYPE 1 12" (TEMPORARY)	FOOT	66	66	
5421A024	PIPE CULVERTS, CLASS A, TYPE 1 24" (TEMPORARY)	FOOT	16	16	
5421A030	PIPE CULVERTS, CLASS A, TYPE 1 30" (TEMPORARY)	FOOT	12	12	
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	145	145	
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	71	71	
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	84	84	
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	59	59	
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	265	265	
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	321	321	
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	362	362	
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	2	2	
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	2	2	
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	1	1	
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	2	2	
54247110	GRATING FOR CONCRETE FLARED END SECTION, 18"	EACH	1	1	
54247130	GRATING FOR CONCRETE FLARED END SECTION, 24"	EACH	2	2	

\* SPECIALITY ITEM

FILE NAME =  
sh1-soq802.dgn

USER NAME = IDOT

DESIGNED - EJM

REVISED -

PLOT SCALE = 50.0000' / IN.

DRAWN - BK

REVISED -

PLOT DATE = 4/1/2011

CHECKED - GFL

REVISED -

DATE - 12/17/10

REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
330	128-I-3	LAKE	128	6
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				

Rev.

CONTRACT NO. 60P33