

SUMMARY OF QUANTITIES

FAU RTEs.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1547, 2757	01-00024-00-SW	COOK	24	3
STA. 09+99		TO STA. 112+83		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 63441				

ITEM No.	ITEMS	UNITS	CONSTRUCTION TYPE CODE 0021 QTY.
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER))	UNIT	39
20200100	EARTH EXCAVATION	CU YD	25
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	4,136
21400100	GRADING AND SHAPING DITCHES	FOOT	900
25000210	SEEDING, CLASS 2A	ACRE	0.75
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	52
25000500	PHOSPHOROUS FERTILIZER NUTRIENT	POUND	52
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	52
25100630	EROSION CONTROL BLANKET	SQ YD	1,500
25200110	SODDING, SALT TOLERANT	SQ YD	1,500
X2500200	TEMPORARY DITCH CHECKS, SPECIAL	EACH	6
28000400	PERIMETER EROSION BARRIER	FOOT	3,520
28000500	INLET AND PIPE PROTECTION	EACH	1
Z000510	INLET FILTERS	EACH	9
31101200	SUB BASE GRANULAR MATERIAL, TYPE B 4"	SQ YD	72
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SQ YD	42
35102200	AGGREGATE BASE COURSE, TYPE B 10"	SQ YD	1,053
35501287	HOT-MIX ASPHALT BASE COURSE, 2 1/4"	SQ YD	1,095
35600700	HOT-MIX ASPHALT BASE COURSE WIDENING, 6"	SQ YD	72
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	92
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	44
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	26,857
42400410	PORTLAND CEMENT CONCRETE SIDEWALK 8 INCH	SQ FT	390
42400800	DETECTABLE WARNINGS	SQ FT	830
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1,379
44000300	CURB REMOVAL	FOOT	288
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	378

*

ITEM No.	ITEMS	UNITS	CONSTRUCTION TYPE CODE 0021 QTY.
44000600	SIDEWALK REMOVAL	SQ FT	150
50105220	PIPE CULVERT REMOVAL	FOOT	30
50901760	PIPE HANDRAIL	FOOT	136
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	20
56500600	DOMESTIC WATER SERVICE BOXES TO BE ADJUSTED	EACH	7
60107600	PIPE UNDERDRAINS 4"	FOOT	282
60255500	MANHOLES TO BE ADJUSTED	EACH	7
60265700	VALVE VAULTS TO BE ADJUSTED	EACH	3
60266600	VALVE BOXES TO BE ADJUSTED	EACH	1
60402210	GRATES, TYPE 8	EACH	2
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	1,872
63200310	GUARDRAIL REMOVAL	FOOT	5
67100100	MOBILIZATION	L SUM	1
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1
Z0013302	SEGMENTAL CONCRETE BLOCK WALL	SQ FT	1,343
XZ127900	RETAINING WALL REMOVAL	FOOT	5
X0323569	STEEL POST REMOVAL	EACH	2
X0326681	REMOVE AND RE-ERECT BOULDERS	L SUM	1
X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	4
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	22
XX003505	PORTLAND CEMENT CONCRETE SIDEWALK 10 INCH (SPECIAL)	SQ FT	1,626
XX007747	PARK BENCH REMOVAL AND REPLACEMENT	EACH	5

* DENOTES SPECIALTY ITEM

the Hoefler-Butler Engineering, Inc.
 Consulting Civil Engineers - Land Surveyors
 PROFESSIONAL DESIGN FIRM LICENSE NO. 084-00889
 874 S. ROBERTS ROAD, HICKORY HILLS, ILLINOIS 60437
 (708) 599-6980 FAX (708) 599-6796

REVISIONS		DATE
NO.	DESCRIPTION	
1	JMH PER REVIEW	02.26.10
2	KCC PER REVIEW	05.11.10
3	JMH PER REVIEW	07.01.10
4	JMH PER REVIEW	10.14.10
5	JMH PER REVIEW	12.01.10
6	JMH PER REVIEW	03.24.11
7	JMH PER REVIEW	04.13.11

ILLINOIS DEPARTMENT OF TRANSPORTATION
 VILLAGE OF JUSTICE
 79th STREET & ROBERTS ROAD
 SIDEWALK CONSTRUCTION
 SUMMARY OF QUANTITIES &
 HMA MIXTURE CHART
 DRAWN BY: JMH
 CHECKED BY: SAL
 DATE: 12/03/09