

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE 0011		
				ROADWAY	BOX CULVERT	UTILITIES
20101400	NITROGEN FERTILIZER NUTRIENT	POUND	16	16		
20101500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	16	16		
20101600	POTASSIUM FERTILIZER NUTRIENT	POUND	16	16		
20200100	EARTH EXCAVATION	CU YD	229	229		
20300100	CHANNEL EXCAVATION	CU YD	160		160	
20700220*	POROUS GRANULAR EMBANKMENT	CU YD	168		168	
20800150	TRENCH BACKFILL	CU YD	12	9		3
25100630	EROSION CONTROL BLANKET	SQ YD	1,239	1,239		
25200110	SODDING, SALT TOLERANT	SQ YD	852	852		
25200200	SUPPLEMENTAL WATERING	UNIT	26	26		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	100	100		
28000400	PERIMETER EROSION BARRIER	FOOT	370	370		
28000500	INLET AND PIPE PROTECTION	EACH	2	2		
28500100	FABRIC FORMED CONCRETE REVETMENT MAT	SQ YD	64		64	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	393	393		
40600300	AGGREGATE (PRIME COAT)	TON	2	2		
40701866	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 9 1/4"	SQ YD	656	656		
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1,843	1,843		
42400800	DETECTABLE WARNINGS	SQ FT	24	24		
44000100	PAVEMENT REMOVAL	SQ YD	656	656		
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	350	350		
44000600	SIDEWALK REMOVAL	SQ FT	1,819	1,819		
50100100*	REMOVAL OF EXISTING STRUCTURES	EACH	1		1	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	33,480		33,480	
50800515	BAR SPLICERS	EACH	140		140	
50900105+	ALUMINUM RAILING, TYPE L	FOOT	50		50	
50901760+	PIPE HANDRAIL	FOOT	95		95	
51500100	NAME PLATES	EACH	1		1	

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE 0011		
				ROADWAY	BOX CULVERT	UTILITIES
54003000*	CONCRETE BOX CULVERTS	CU YD	200.8		200.8	
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	38	38		
55100500	STORM SEWER REMOVAL 12"	FOOT	40	40		
55100700	STORM SEWER REMOVAL 15"	FOOT	40	40		
55100900	STORM SEWER REMOVAL 18"	FOOT	19	19		
56103900**	DUCTILE IRON WATER MAIN, MECHANICAL JOINT 8"	FOOT	133			133
56105000**	WATER VALVES 8"	EACH	1			1
56400820**	FIRE HYDRANT WITH AUXILIARY VALVE AND VALVE BOX	EACH	1			1
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3		
60248700**	VALVE VAULTS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1			1
60500040	REMOVING MANHOLES	EACH	1	1		
60500060	REMOVING INLETS	EACH	2	2		
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	350	350		
67100100	MOBILIZATION	L SUM	1	1		
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	6	6		
72000100	SIGN PANEL - TYPE 1	SQ FT	8.25	8.25		
72900100	METAL POST - TYPE A	FOOT	12	12		
78001110+	PAINT PAVEMENT MARKING - LINE 4"	FOOT	328	328		
78001130+	PAINT PAVEMENT MARKING - LINE 6"	FOOT	68	68		
K1005421*	SEEDING (SPECIAL)	ACRE	0.08	0.08		
X6024240*	INLETS, SPECIAL	EACH	2	2		
X7010216*	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1		
Z0001050*	AGGREGATE SUBGRADE 12"	SQ YD	736	736		
Z0056610*	STORM SEWER (WATER MAIN REQUIREMENTS) 15 INCH	FOOT	53	53		
Z0056612*	STORM SEWER (WATER MAIN REQUIREMENTS) 18 INCH	FOOT	18	18		
Z0067500**	STEEL CASINGS 16"	FOOT	70			70

* Special Provision
+ Specialty Item

FILE NAME = S:\PROJECTS\2010\1201010\BarneyDrivePHI\Design\Trans\CoverE.dgn

USER NAME =	DESIGNED - L.G.N.	REVISED -
	CHECKED - G.F.S.	REVISED -
PLOT SCALE =	DRAWN - L.G.N.	REVISED -
PLOT DATE =	CHECKED - G.F.S.	REVISED -

**ILLINOIS DEPARTMENT OF TRANSPORTATION
BARNEY DRIVE OVER TRIBUTARY OF ROCK RUN
STATION 20+00**

**SUMMARY OF QUANTITIES
STRUCTURE NO. 099-6474**

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0330	08-00413-00-BR	WILL	33	3
WHA* 1201010		CONTRACT NO. 63571		
ILLINOIS FED. AID PROJECT BRM-90031062				