

SCHEDULE OF QUANTITIES

DETECTABLE WARNINGS		
STATION	SQ FT	REMARKS
BARNEY DRIVE		
19+26 RT 24'	8	2' X 4'
RT 20+93	8	2' X 4'
LT 20+93	8	2' X 4'
PROJECT TOTAL	24	
42400800		

STORM SEWER REMOVAL 12"		
STATION	FOOT	REMARKS
BARNEY DRIVE		
RT TO LT 20+34	34	
LT 20+34	6	
PROJECT TOTAL	40	
55100300		

MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID		
STATION	EACH	REMARKS
BARNEY DRIVE		
19+44 LT 27'	1	
20+10 LT 25'	1	
20+38 LT 25'	1	
PROJECT TOTAL	3	
60218400		

PAVEMENT REMOVAL		
STATION	SQ YD	REMARKS
BARNEY DRIVE		
19+25 TO 21+00	656	
PROJECT TOTAL	656	
44000100		

STORM SEWER REMOVAL 15"		
STATION	FOOT	REMARKS
BARNEY DRIVE		
LT 19+97 TO 20+36	40	
PROJECT TOTAL	40	
55100700		

VALVE VAULTS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID		
STATION	EACH	REMARKS
BARNEY DRIVE		
20+57 LT 28'	1	
PROJECT TOTAL	1	
60248700*		

COMBINATION CURB AND GUTTER REMOVAL		
STATION	FOOT	REMARKS
BARNEY DRIVE		
RT 19+25 TO 21+00	175	
LT 19+25 TO 21+00	175	
PROJECT TOTAL	350	
44000500		

STORM SEWER REMOVAL 18"		
STATION	FOOT	REMARKS
BARNEY DRIVE		
LT 19+42 TO 19+60	19	
PROJECT TOTAL	19	
55100300		

REMOVING MANHOLES		
STATION	EACH	REMARKS
BARNEY DRIVE		
LT 20+37	1	
PROJECT TOTAL	1	
60500040		

SIDEWALK REMOVAL		
STATION	SQ FT	REMARKS
BARNEY DRIVE		
RT 19+25 TO 21+00	890	
LT 19+25 TO 21+00	930	
PROJECT TOTAL	1,819	
44000600		

DUCTILE IRON WATER MAIN, MECHANICAL JOINT 8"		
STATION	FOOT	REMARKS
BARNEY DRIVE		
LT 19+26 TO 20+57	133	
PROJECT TOTAL	133	
56103300*		

REMOVING INLETS		
STATION	EACH	REMARKS
BARNEY DRIVE		
RT 20+33	1	
LT 20+35	1	
PROJECT TOTAL	2	
60500060		

STORM SEWERS, CLASS A, TYPE 1 12"		
STATION	FOOT	REMARKS
BARNEY DRIVE		
RT TO LT 20+38	33	PIPE-1
LT 20+38	5	PIPE-2
PROJECT TOTAL	38	
550A0050		

WATER VALVES 8"		
STATION	EACH	REMARKS
BARNEY DRIVE		
19+26 LT 28'	1	
PROJECT TOTAL	1	
56105300*		

COMBINATION CONCRETE CURB & GUTTER, TYPE B - 6.12		
STATION	FOOT	REMARKS
BARNEY DRIVE		
RT 19+25 TO 21+00	175	
LT 19+25 TO 21+00	175	
PROJECT TOTAL	350	
606038090		

FIRE HYDRANT WITH AUXILIARY VALVE AND VALVE BOX		
STATION	EACH	REMARKS
BARNEY DRIVE		
20+53 LT 28'	1	
PROJECT TOTAL	1	
56400820*		

FILE NAME = S:\PROJECTS\2010\12010100_B Barney Drive\ph1\Design-Trans\Cover-Exc.dgn

USER NAME =	DESIGNED - L.G.N.	REVISED -
PLOT SCALE =	CHECKED - G.F.S.	REVISED -
PLOT DATE =	DRAWN - L.G.N.	REVISED -
	CHECKED - G.F.S.	REVISED -

**ILLINOIS DEPARTMENT OF TRANSPORTATION
BARNEY DRIVE OVER TRIBUTARY OF ROCK RUN
STATION 20 + 00**

**SCHEDULE OF QUANTITIES
STRUCTURE NO. 099-6474**

SHEET NO. 2 OF 3 SHEETS

F.A.J. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0330	08-00413-00-BR	WILL	33	6
WHA# 1201010		CONTRACT NO. 63571		
ILLINOIS FED. AID PROJECT BRM-90031621				