INDEX OF SHEETS


1	COVER SHEET
2	GENERAL NOTES
3	SUMMARY OF QUANTITIES
4	TYPICAL SECTIONS
5-7	SCHEDULE OF QUANTITIES
8	PLAN AND PROFILE
9	DETOUR SIGNING
10-11	STAGING PEDESTRIAN CONTROL
12-13	EROSION CONTROL PLAN
14	WATERMAIN PLAN AND PROFILE
15-25	STRUCTURAL DETAILS
26	DISTRICT ONE DETAIL TC-21
27-28	INLETS, SPECIAL DETAILS
29	WATERMAIN DETAILS
30-32	CROSS SECTIONS - BARNEY DRIVE
33	CROSS SECTIONS - TRIBUTARY OF ROCK RUN

STANDARDS

Ì	000001-06	STANDARD SYMBOLS, ABBREVIATIONS, AND PATTERNS
Ì	001001-02	AREAS OF REINFORCEMENT BARS
ı	280001-05	TEMPORARY EROSION CONTROL SYSTEMS
	285001-02	FABRIC FORMED CONCRETE REVETMENT MATS
	424001-05	CURB RAMPS FOR SIDEWALKS
	515001-03	NAME PLATE FOR BRIDGES
ĺ	602401-03	MANHOLE TYPE A
ĺ	602701-02	MANHOLE STEPS
-	604001-03	FRAME AND LIDS TYPE 1
	606001-04	CONCRETE CURB TYPE B AND COMBINATION CONCRETE CURB AND GUTTER
	664001-02	CHAIN LINK FENCE
	701006-03	OFF-ROAD OPERATIONS, 2L, 2W, 15' TO 24" FROM PAVEMENT EDGE
	701801-04	LANE CLOSURE MULTILANE 1W OR 2W Crosswalk or sidewalk closure
	701901-01	TRAFFIC CONTROL DEVICES
	720011-01	METAL POSTS FOR SIGNS, MARKERS & DELINEATORS.
-	728001-01	TELESCOPING STEEL SIGN SUPPORT
		APPLICATIONS OF TYPES A & B METAL POSTS (FOR SIGNS & MARKERS)
	780001-02	TYPICAL PAVEMENT MARKINGS

DESIGN DESIGNATION

	DESIGN SPEED:	40 MPH	
	POSTED SPEED:	30 MPH	
FUNCTIONAL CLASSIFICATION	ROUTE	ADT (2031)	% TRUCKS
COLLECTOR	BARNEY DRIVE	5440	8



FULL SIZE PLANS HAVE BEEN PREPARED USING STANDARD ENGINEERING SCALES. REDUCED SIZED PLANS WILL NOT CONFORM TO STANDARD SCALES. IN MAKING MEASUREMENTS ON REDUCED PLANS, THE ABOVE SCALES MAY BE USED.

J.U.L.I.E.
JOINT UTILITY LOCATION INFORMATION FOR EXCAVATION
1-800-892-0123
OR 811

CONTRACT NO. 63571

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION
DIVISION OF HIGHWAYS

PLANS FOR PROPOSED FEDERAL AID HIGHWAY

F.A.U. ROUTE 0330 (BARNEY DRIVE)

OVER ROCK RUN TRIBUTARY NO. 3

BRIDGE REPLACEMENT

SECTION 08-00413-00-BR


PROJECT NO. BRS-9003(162)

COUNTY OF WILL

CITY OF JOLIET


C-91-174-09

LOCATION MAP



GROSS LENGTH = 175 FT. = 0.03 MILE NET LENGTH = 175 FT. = 0.03 MILE





PRINTED BY THE AUTHORITY OF THE STATE OF ILLINOIS



Brian & Comen DATE: March 24, 2011 EXPIRES 11/30/11



809 East Second Street Dixon, Illinois 61021 Phone 815,284,3381 Fax 815,284,3385 Design Firm #184-000918 www.willetthofmann.com

GENERAL NOTES

GENERAL NOTES

THE CONTRACTOR SHALL CAREFULLY PRESERVE ALL PROPERTY MARKS, SECT ON OR SUBSECTION MONUMENTS ENCOUNTERED, UNTIL AN OWNER OR AUTHORIZED SURVEYOR OR AGENT HAS WITNESSED OR OTHERWISE REFERENCED THEIR LOCATION. ANY PROPERTY MARKS, SECTION OR SUBSECTION MONUMENTS UNLESS REFERENCED, DAMAGED BY THE CONTRACTOR SHALL BE REPLACED AT THE EXPENSE OF THE CONTRACTOR.

THE CONTRACTOR SHALL REMOVE ALL STRUCTURES OTHER THAN THE EXISTING TRIPLE BARREL CMP CULVERT WITHIN THE EXISTING RIGHT OF WAY AS DIRECTED BY THE ENGINEER AND AS SHOWN ON THE PLANS. COST SHALL BE INCLUDED IN THE UNIT BID PRICES OF THE CONTRACT.

THE CONTRACTOR SHALL NOTIFY THE RESPECTIVE UTILITIES TO MAKE THE NECESSARY ADUSTMENTS PRIOR TO THIS CONSTRUTION.

THE LOCATION AND ELEVATION OF THE UNDERGROUND UTILILITIES AS SHOWN ON THE PLANS ARE NOT TO BE TAKEN AS EXACT. THE CONTRACTOR SHALL USE SPECIAL CARE WHEN CONDUCTING CONSTRUCTION OPERATIONS NEAR THEM TO PREVENT DAMAGE.

BITUMINOUS MATERIALS (PRIME COAT) SHALL BE RC-70 OR SS-1 ON BITUMINOUS AND MC-30 OR P.E.P. ON AGGREGATE AND SHALL BE APPLIED AT THE RATE OF 0.10-0.40 GALLONS PER SQUARE YARD, OR AS DIRECTED BY THE ENGINEER.

ALL PAVEMENT SHALL BE CLEANED AND "FRESH OIL" SIGNS SHALL BE PLACED AT ALL INTERSECTIONS OF THE STREETS PRIOR TO APPLYING BITUMINOUS MATERIALS (PRIME COAT).

AGGREGATE (PRIME COAT) SHALL BE APPLIED AT THE RATE OF 3 POUNDS SQUARE YARD OR AS DIRECTED BY THE ENGINEER.

THE FINAL TOP 4" OF SOIL IN ANY AREA DISTURBED BY THE CONTRACTOR MUST BE ABLE TO SUPPORT VEGETATION.

EXISTING STREET SIGNS AND TRAFFIC SIGNS THAT ARE WITHIN THE CONSTRUCTION LIMITS SHALL BE REMOVED AND RESET BY THE CONTRACTOR IN ACCORDANCE WITH ARTICLE 107.25.

WHERE THE PROPOSED CONSTRUCTION MEETS AN EXISTING BITUMINOUS OR CONCRETE SURFACE, OR WHERE SAWING IS STATED ON THE PLANS, THE EXISTING SURFACE SHALL BE SAWED IN A NEAT, STRAIGHT LINE. COST OF SAWING IS TO BE INCLUDED IN THE UNIT BID PRICES OF THE CONTRACT.

ANY TEMPORARY SEEDING THAT IS DIRECTED BY THE ENGINEER SHALL BE PAID AS TEMPORARY EROSION CONTROL SEEDING.

USER NAME =	DESIGNED	- L.G.N.	. REVISED -	ILLINOIS DEPARTMENT OF TRANSPORTATION	GENERAL NOTES	F.A.U.	SECTION	COUNTY	TOTAL	SHEET
	CHECKED	- G.F.S.	REVISED -			0370	08 00417 00 BB	WILL	311113	110.
PLOT SCALE ≈	DRAWN	- L.G.N.	. REVISED -	BARNEY DRIVE OVER TRIBUTARY OF ROCK RUN	STRUCTURE NO. 099-6474	0330	WHA# 1201D10	CONTRAC	T NO 6	3571
PLOT DATE =	CHECKED	- G.F.S.	. REVISED -	STATION 20+00			ILLINOIS FED.	AID PROJECT BR	M-9003(162)	3311

SUMMARY OF QUANTITIES


				CON	STRUCTION TYPE (0011	CODE
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	BOX CULVERT	UTILITIES
20101400	NITROGEN FERTILIZER NUTRIENT	POUND	16	16		
20101500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	16	16		
20101600	POTASSIUM FERTILIZER NUTRIENT	POUND	16	16		
20200100	EARTH EXCAVATION	CU YD	229	229		
20300100	CHANNEL EXCAVATION	CU YD	160		160	
20700220*	POROUS GRANULAR EMBANKMENT	CU YD	168		168	
20800150	TRENCH BACKFILL	CU YD	12	9		3
25100630	EROSION CONTROL BLANKET	SQ YD	1,239	1,239		
25200110	SODDING, SALT TOLERANT	SQ YD	852	852		
25200200	SUPPLEMENTAL WATERING	UNIT	26	26		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	100	100		
28000400	PERIMETER EROSION BARRIER	FOOT	370	370		
28000500	INLET AND PIPE PROTECTION	EACH	2	2		
28500100	FABRIC FORMED CONCRETE REVETMENT MAT	SQ YD	64		64	
40600100-	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	393	393		
40600300	AGGREGATE (PRIME COAT)	TON	2	2		
40701866	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 9 1/4"	SQ YD	656	656		
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1,843	1,843		
42400800	DETECTABLE WARNINGS	SQ FT	24	24		
44000100	PAVEMENT REMOVAL	SQ YD	656	656	-	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	350	350		
44000600	SIDEWALK REMOVAL	SQ FT	1,819	1,819		
50100100*	REMOVAL OF EXISTING STRCTURES	EACH	1		1	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	33,480		33,480	
50800515	BAR SPLICERS	EACH	140		140	
50900105+	ALUMINUM RAILING, TYPE L	FOOT	50		50	
50901760-+	PIPE HANDRAIL	FOOT	95		95	
51500100	NAME PLATES	EACH	1		1	

		or .		CON	STRUCTION TYPE (0011	CODE
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	ROADWAY	BOX CULVERT	UTILITIES
4003000*	CONCRETE BOX CULVERTS	CU YD	200.8		200.8	
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	38	38		
55100500	STORM SEWER REMOVAL 12"	FOOT	40	40		
55100700	STORM SEWER REMOVAL 15"	FOOT	40	40		
55100900	STORM SEWER REMOVAL 18"	FOOT	19	19		
6103900*+	DUCTILE IRON WATER MAIN, MECHANICAL JOINT 8"	FOOT	133			133
6105000*+	WATER VALVES 8"	EACH	1			1
6400820*+	FIRE HYDRANT WITH AUXILIARY VALVE AND VALVE BOX	EACH	1			1
60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	3	3		
0248700*+	VALVE VAULTS, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1			1
60500040	REMOVING MANHOLES	EACH	1	1		
60500060	REMOVING INLETS	EACH	2	2		
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	350	350		
67100100	MOBILIZATION	L SUM	1	1		
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	6	6		
72000100	SIGN PANEL - TYPE 1	SQ FT	8.25	8.25		***************************************
72900100	METAL POST - TYPE A	FOOT	12	12		
78001110+	PAINT PAVEMENT MARKING - LINE 4"	FOOT	328	328		
8001130+	PAINT PAVEMENT MARKING - LINE 6"	FOOT	68	68		
K1005421*	SEEDING (SPECIAL)	ACRE	0.08	0.08		
(6024240*	INLETS, SPECIAL	EACH	2	2		
K7010216*	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1		
0001050*	AGGREGATE SUBGRADE 12"	SQ YD	736	736		
0056610*	STORM SEWER (WATER MAIN REQUIREMENTS) 15 INCH	FOOT	53	53		
20056612*	STORM SEWER (WATER MAIN REQUIREMENTS) 18 INCH	FOOT	18	18		
0067500*+	STEEL CASINGS 16"	FOOT	70			70


	USER NAME =	DESIGNED -	L.G.N.	REVISED -	ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.U. RTE.	SECTION	COUNTY	TOTAL
		CHECKED -	G.F.S.	REVISED -	BARNEY DRIVE OVER TRIBUTARY OF ROCK RUN		0330	08-00413-00-BR	WILL	33
L	PLOT SCALE =	DRAWN -	L.G.N.	REVISED -		STRUCTURE NO. 099-6474		WHA# 1201D10	CONTRACT	T NO. 6
	PLOT DATE =	CHECKED -	G.F.S.	REVISED -	STATION 20+00			ILLINOIS FED.	AID PROJECT BRM	A-9003(162

^{*} Special Provision + Specialty Item

TYPICAL SECTIONS



PROPOSED TYPICAL SECTION 19+25.00 TO 21+00.00, BARNEY DRIVE



EXISTING TYPICAL SECTION 19+25.00 TO 21+00.00, BARNEY DRIVE

PAVEMENT STRUCTURAL DESIGN BARNEY DRIVE

P.V. 4,106 S.U. 268 M.U. 89

STRUCTURAL DESIGN TRAFFIC (S.D.T.) = YEAR 2021

CLASS II STREET

80,000# TRUCK DESIGN

ERI : (ASSUMED) 2 ksi TF = 0.65 HMA MIX TEMP. 78°F HMA EAC = 600 ksi HMA DESIGN STRAIN 120 microstrain

USE 2" HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50 7 1/4" HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50 12" AGGREGATE BASE

HOT-MIX ASPHALT MIXTURE REQUIREMENTS		
MIXTURE TYPE	AIR VOIDS @ Ndes	
HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50 (IL 9.5mm); 2"	4% @ 50 Gyr.	
HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50 7 1/4" (IN 3 LIFTS)	4% @ 50 Gyr.	

NOTE: THE UNIT WEIGHT USED TO CALCULATE ALL HMA SURFACE MIXTURE QUANTITIES IS 112 LBS/SQ YD/IN.

THE "AC TYPE" FOR POLYMERIZED HMA MIXES SHALL BE "SBS/SBR PG-70-22" AND FOR NON-POLYMERIZED HMA THE "AC TYPE SHALL BE "PG 64-22" UNLESS MODIFIED BY DISTRICT ONE SPECIAL PROVISIONS. FOR "PERCENT OF RAP" SEE DISTRICT ONE SPECIAL PROVISIONS.

	JOLIET - BARNEY DRIVE - HORIZONTAL CONTROL POINTS													
POINT #	STATION	0/S	NORTH	EAST	DESCRIPTION									
1	1 18+44.25 24.04′ 1,769,872.77 1,036,314.96′ 5/8″ IRON PIN													
2	19+53.76	-23.39'	1,769,980.70	1,036,264.01	CHIS. "X"									
3	21+97.01	23.54'	1,770,225.33	1,036,303.05	5 5/8" IRON PIN									
		JOLIET -	- BARNEY DR	IVE - VERTIC	CAL BENCH MARKS									
STATION	0/S	ROAD	ELEV.		DESCRIPTION									
17+86.76	-54.21'	BARNEY	NEY 634.68 "O" IN OPEN ON FH @ NW COR. OF BARNEY DR. & CAMPBELL ST.											
21+18.97	-61.43′	BARNEY	633.10	"O" IN OPEN	I ON FH & SW COR. OF BARNEY DR. & FAIRWAY DF	₹.								

DATUM: NAD83 1997, ILLINOIS STATE PLANE EAST 1201

USER NAME =	DESIGNED -	L.G.N.	REVISED -	ILLINOIS DEPARTMENT OF TRANSPORTATION	
	CHECKED -	G.F.S.	REVISED -	BARNEY DRIVE OVER TRIBUTARY OF ROCK RUN	
PLOT SCALE =	DRAWN -	L.G.N.	REVISED -		
PLOT DATE =	CHECKED -	G.F.S.	REVISED -	STATION 20+00	

YPICAL SECTIONS & GENERAL NOTES	F.A.U. RTE.	SECTION	COUNTY	TOTAL	SHEE
STRUCTURE NO. 099-6474	0330	08-00413-00-BR	WILL	33	4
SINUCIONE NO. 033-0474		WHA# 1201D10	CONTRACT	NO. 63	3571
		ILLINOIS FED. AI	D PROJECT BRM-	9003(162)	

SCHEDULE OF QUANTITIES

EARTHWORK SCHEDULE

LOCATION	EARTH EXCAVATION 20200100	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE 25%	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
BARNEY DRIVE STA. 19+25.00 TO 21+00.00	229	172	44	128

NITTOOL	_	ER NUTRIENT
STATION	POUND	REMARKS
RNEY DRIVE		
LT 19+25 TO 19+44	1	0.01 ACRE @ 90 LB / ACRE
LT 19+25 TO 21+00	6	0.06 ACRE @ 90 LB / ACRE
RT 19+25 TO 21+00	1	O.O1 ACRE @ 90 LB / ACRE
RT 20+00	6	0.07 ACRE @ 90 LB / ACRE
RT 20+50	2	0.02 ACRE @ 90 LB / ACRE
PROJECT TOTAL	16	

PHOSPHOR	RUS FERTILIZ	ZER NUTRIENT
STATION	POUND	REMARKS
RNEY DRIVE		
LT 19+25 TO 19+44	1	O.O1 ACRE @ 90 LB / ACRE
LT 19+25 TO 21+00	6	0.06 ACRE @ 90 LB / ACRE
RT 19+25 TO 21+00	1	0.01 ACRE @ 90 LB / ACRE
RT 20+00	6	0.07 ACRE @ 90 LB / ACRE
RT 20+50	2	0.02 ACRE @ 90 LB / ACRE
PROJECT TOTAL	16	

POTASS	IUM FERTILIZ	ER NUTRIENT
STATION	POUND	REMARKS
BARNEY DRIVE		
LT 19+25 TO 19+44	1	0.01 ACRE @ 90 LB / ACRE
LT 19+25 TO 21+00	6	0.06 ACRE @ 90 LB / ACRE
RT 19+25 TO 21+00	1	0.01 ACRE @ 90 LB / ACRE
RT 20+00	6	0.07 ACRE @ 90 LB / ACRE
RT 20+50	2	0.02 ACRE @ 90 LB / ACRE
PROJECT TOTAL	16	

٦	FRENCH BACKF	ILL
STATION	CU YD	REMARKS
RNEY DRIVE		
RT TO LT 20+34	5	PIPE REMOVAL
RT TO LT 20+38	4	PIPE-4
LT 19+60 TO 19+97	3	WATERMAIN
PROJECT TOTAL	12	
800150		

EROS	ION CONTROL B	LANKET
STATION	SQ YD	REMARKS
ARNEY DRIVE		
LT 19+25 TO 19+44	40	
LT 19+25 TO 21+00	310	
RT 19+25 TO 21+00	50	A Control of the Cont
RT 20+00	341	
RT 20+25	387	
RT 20+50	111	
PROJECT TOTAL	1,239	

	SODDING, SALT TO	LERANT
STATION	SQ YD	REMARKS
BARNEY DRIVE		
LT 19+25 TO 19+4	4 40	
LT 19+25 TO 21+0	0 310	
RT 19+25 TO 21+0	0 50	
RT 20+00	341	
RT 20+50	111	
PROJECT TOTAL	852	
25200110		

SUPPLEMENTAL WATERING		
STATION	UNIT	REMARKS
RNE Y DRIVE		
CONTIGENCY ITEM	26	10 APPLICATIONS @ 3 GAL/SQ YD
PROJECT TOTAL	26	

	TEMPORARY	EROSION CON	TROL SEEDING	
	STATION	POUND	REMARKS	
BARNE Y	DRIVE			
	LT 19+25 TO 21+00	50		
	RT 19+25 TO 21+00	50		
	PROJECT TOTAL	100		
28000 2	50			

PERIN	METER EROSION	BARRIER
STATION	FOOT	REMARKS
BARNE Y DRIVE		
LT 19+40	45	
LT 20+00	60	
RT 20+13	145	
RT 20+38	120	
PROJECT TOTAL	370	
28000 400		

INLET A	AND PIPE PR	ROTECTION
STATION	EACH	REMARKS
BARNEY DRIVE		
RT & LT 20+38	2	S-1 AND S-2
PROJECT TOTAL	.2	
28000500		

BITUMINOU	S MATERIAL	S (PRIME COAT)
STATION	GALLON	REMARKS
BARNEY DRIVE		
19+25 TO 21+00	262	1 APPL @ .4 GAL/SY ON AGG
19+25 TO 21+00	131	2 APPL @ .1 GAL/SY ON BIT
PROJECT TOTAL	393	**************************************
40600100*		

AGGF	REGATE (PRIN	ME COAT)
STATION	TON	REMARKS
BARNEY DRIVE		
19+25 TO 21+00	2	2 APPL @ 3 LBS/SY
PROJECT TOTAL	2	
40600300*		

HOT-MIX ASPHALT	PAVEMENT	Γ (FULL-DEPTH), 9 1/4"
STATION	SQ YD	REMARKS
BARNEY DRIVE		
19+25 TO 21+00	656	7 1/4" BINDER & 2" SURFACE
PROJECT TOTAL	656	
40701866		

PORTLAND CEMENT CONCRETE				
SIDEWALK, 5 INCH				
STATION	SQ FT	REMARKS		
BARNEY DRIVE				
RT 19+25 TO 21+00	875			
LT 19+25 TO 21+00	875			
RT 20+93	13	CROSSWALK RAMP		
LT 20+93	80	CROSSWALK RAMP		
PROJECT TOTAL	1,843			
2400100				

USER NAME =	DESIGNED	-	L.G.N.	REVISED	-
	CHECKED	~	G.F.S.	REVISED	-
PLOT SCALE =	DRAWN	-	L.G.N.	REVISED	-
PLOT DATE =	CHECKED	_	G.F.S.	REVISED	-

SCHEDULE OF QUANTITIES

DE ⁻	TECTABLE WAR	NINGS
STATION	SQ FT	REMARKS
BARNEY DRIVE		
19+26 RT 24'	8	2' X 4'
RT 20+93	8	2' X 4'
LT 20+93	8	2′ X 4′
PROJECT TOTAL	24	
12400800		

AVEMENT REMO	VAL
SQ YD	REMARKS
	-
656	
656	The second secon
	656

CURB AND	GUTTER REMOVAL
FOOT	REMARKS
` .	
175	
175	
350	
	175 175

IDEWALK REMO	VAL
SQ FT	REMARKS
890	
930	
1,819	
	890 930

STORM SEV	VERS, CLASS	S A, TYPE 1 12"
STATION	FOOT	REMARKS
BARNEY DRIVE		
RT TO LT 20+38	33	PIPE-1
LT 20+38	5	PIPE-2
PROJECT TOTAL	38	
550A0050		

		VAL 12''
STATION	FOOT	REMARKS
		WARRANT WARRANT CONTRACTOR OF THE CONTRACTOR OF
TO LT 20+34	34	
T 20+34	6	
JECT TOTAL	40	
	TO LT 20+34 T 20+34	TO LT 20+34 34 .T 20+34 6

STORM	SEWER RI	EMOVAL 15"
STATION	FOOT	REMARKS
BARNEY DRIVE		
LT 19+97 TO 20+36	40	
PROJECT TOTAL	40	
55100 700		

STORM	SEWER R	EMOVAL 18"
STATION	FOOT	REMARKS
BARNE Y DRIVE		
LT 19+42 TO 19+60	19	
PROJECT TOTAL	19	
55100 300		

DUCTILE IRON	WATER MAIN,	MECHANICAL JOINT 8"
STATION	FOOT	REMARKS
BARNEY DRIVE		
LT 19+26 TO 20+57	133	
PROJECT TOTAL	133	
56103 100*		

1	WATER VALVES	8 8"
STATION	EACH	REMARKS
BARNE Y DRIVE		
19+26 LT 28'	1	
PROJECT TOTAL	1	
56105)00•		

FERE HYDRANT WITH	AUXILIARY	VALVE AND VALVE BOX
STATION	EACH	REMARKS
BARNE Y DRIVE 20+53 LT 28'	1	
PROJECT TOTAL	1	
5640C 820*		

		4'-DIAMETER,		
1175	I FRANC,	PLOSED LID		
STATION EACH REMARKS				
BARNEY DRIVE				
19+44 LT 27'	1			
20+10 LT 25' 1				
20+38 LT 25'	1			
PROJECT TOTAL 3				
60218400				

VALVE VAU	LTS, TYPE /	4, 4'-DIAMETER,		
TYPE 1 FRAME, CLOSED LID				
STATION	EACH	REMARKS		
BARNEY DRIVE				
20+57 LT 28'	1			
PROJECT TOTAL 1				
60248700*				

REMOVING MANHOLES				
STATION	STATION EACH REMARKS			
BARNEY DRIVE				
LT 20+37	1			
PROJECT TOTAL	1			
60500040				

REMOVING INLETS		
STATION	EACH	REMARKS
BARNEY DRIVE		
RT 20+33	1	
LT 20+35	1	
PROJECT TOTAL	2	
60500060		

COMBINATION	I CONCRET	E CURB & GUTTER,		
	TYPE B -	6.12		
STATION	STATION FOOT REMARKS			
BARNEY DRIVE				
RT 19+25 TO 21+00	175			
LT 19+25 TO 21+00	175			
PROJECT TOTAL	350			
506038090				

I	USER NAME =	DESIGNED	-	L.G.N.	REVISED -
-		CHECKED	~	G.F.S.	REVISED -
	PLOT SCALE =	DRAWN	-	L.G.N.	REVISED -
	PLOT DATE =	CHECKED	-	G.F.S.	REVISED ~

SCHEDULE OF QUANTITIES

S:	GN PANEL -	- TYPE 1
STATION	SQ FT	REMARKS
BARNEY DRIVE		
20+10 LT 22'	6.25	W11-2 PEDESTRIAN SIGN 30" X 30"
20+10 LT 22'	2.00	W16-9P AHEAD PLAQUE 24" X 12"
PROJECT TOTAL	8.25	
72000100		

METAL POST - TYPE A				
STATION	STATION FOOT REMARKS			
BARNEY DRIVE				
20+10 LT 22'	12	PEDESTRIAN SIGN		
PROJECT TOTAL	12			
72900100	······································			

PAINT	PAVEMENT N	MARKING -	
	LINE 4"		
STATION FOOT REMARKS			
BARNEY DRIVE			
19+25 TO 20+89	328	CENTERLINE (DBL YLW)	
PROJECT TOTAL	328		
78001110			

PAIN	T PAVMENT MA	ARKING -	
	LINE 6"		
STATION FOOT REMARKS			
BARNEY DRIVE			
RT TO LT 20+92	68	CROSSWALK (WHT)	
PROJECT TOTAL	- 68		
78001130			

S	SEEDING (SPEC	IAL)
STATION	ACRE	REMARKS
BARNEY DRIVE RT 20+25	0.08	CHANNEL AREA
PROJECT TOTAL	0.08	

	INLETS, SPECI	AL
STATION	EACH	REMARKS
ARNEY DRIVE		
RT 20+38	1	S-1
LT 20+38	1	S-2
PROJECT TOTAL	2	


AGGR	EGATE SUBGRA	DE 12"	
STATION	SQ YD	REMARKS	
BARNE Y DRIVE			
19+25 TO 21+00	736		
PROJECT TOTAL	736		
Z000:050*			


	STORM SE	EWER
(WATER MA	IN REQUIRI	EMENTS) 15 INCH
STATION	FOOT	REMARKS
BARNEY DRIVE		
LT 19+85 TO 20+10	24	PIPE-3
LT 20+10 TO 20+36	29	PIPE-4
PROJECT TOTAL	53	
Z005€ 610 +		


	STORM SE	EWER
(WATER MAI	N REQUIRI	EMENTS) 18 INCH
STATION	FOOT	REMARKS
BARNEY DRIVE		
LT 19+45 TO 19+54	18	PIPE-5
PROJECT TOTAL	18	
Z0056 612*		


S	TEEL CASINGS	16''	
STATION	FOOT	REMARKS	
BARNEY DRIVE			
LT 19+42 TO 20+12	70		
PROJECT TOTAL	70		
Z006 ⁻ 500•			


USER NAME =	DESIGNED	-	L.G.N.	REVISED	-
	CHECKED	-	G.F.S.	REVISED	
PLOT SCALE =	DRAWN	-	L.G.N.	REVISED	-
PLOT DATE =		-	G.F.S.	REVISED	-











EROSION CONTROL PLAN

THE FOLLOWING PLAN WAS ESTABLISHED AND INCLUDED IN THESE PLANS TO DIRECT THE CONTRACTOR IN THE PLACEMENT OF TEMPORARY EROSION CONTROL SYSTEMS AND TO PROVIDE A STORM WATER POLLUTION PREVENTION PLAN FOR COMPLIANCE UNDER NPDES.

THE PURPOSE OF THIS PLAN IS TO MINIMIZE SILTATION WITHIN THE CONSTRUCTION ZONE AND TO ELIMINATE SEDIMENTS FROM ENTERING AND LEAVING THE CONSTRUCTION ZONE BY UTILIZING PROPER TEMPORARY EROSION CONTROL SYSTEMS AND PROVIDING GROUND COVER WITHIN A REASONABLE AMOUNT OF TIME.

CERTAIN ITEMS, AS SHOWN IN THIS PLAN AND REFERENCED BY THE LEGEND, SHALL BE PLACED BY THE CONTRACTOR AT THE BEGINNING OF CONSTRUCTION. OTHER ITEMS SHALL BE PLACED BY THE CONTRACTOR AS DIRECTED BY THE ENGINEER ON A CASE BY CASE SITUATION RESULTING FROM THE CONTRACTOR'S SEQUENCE OF ACTIVITIES, TIME OF YEAR, AND EXPECTED WEATHER CONDITIONS.

THE CONTRACTOR SHALL PLACE PERMANENT EROSION CONTROL SYSTEMS AND SEEDING WITHIN A REASONABLE AMOUNT OF TIME: THEREFORE, REDUCING THE AMOUNT OF AREA BEING OPEN TO THE POSSIBILITY OF EROSION AND REDUCING THE AMOUNT OF TEMPORARY SEEDING. THE RESIDENT ENGINEER WILL DETERMINE IF TEMPORARY EROSION CONTROL SYSTEMS SHOWN IN THE PLAN CAN BE DELETED, THE PROPER METHOD OF INSTALLATION, AND IF ANY ADDITIONAL TEMPORARY EROSION CONTROL SYSTEMS SHALL BE ADDED WHICH ARE NOT INCLUDED IN THE PLANS. THE CONTRACTOR SHALL PERFORM ALL WORK AS DIRECTED BY THE ENGINEER AND AS SHOWN IN STANDARD 280001 OF THE PLANS.

SITE DESCRIPTION:

DESCRIPTION OF CONSTRUCTION ACTIVITY: THIS PROJECT CONSITSTS OF REMOVAL OF EXISTING CULVERT, CONSTRUCTION OF PROPOSED CULVERT, AND ROADWAY CONSTRUCTION

THIS PROJECT CONSISTS OF EARTH EXCAVATION, STRUCTURE EXCAVATION, CONCRETE STRUCTURES CURB AND GUTTER, NEW STORM SEWER AND INLETS, PAVEMENT ITEMS, AND OTHER MISCELLANEOUS (g) ITEMS OF CONSTRUCTION

DESCRIPTION OF INTENDED SEQUENCE OF ACTIVITIES:

THE SEQUENCE OF EVENTS ARE AS FOLLOW: EARTH EXCAVATION, STORM SEWER
INSTALLATION, INSTALLATION OF INLET AND PIPE PROTECTION, STRUCTURE EXCAVATION,
CONCRETE STRUCTURES, AGGREGATE BASE, BITUMINOUS SURFACE AND RELATED APPURTENANCES,
PLACEMENT OF PERMANENT EROSION CONTROL INCLUDING SEEDING

TOTAL CONSTRUCTION SITE (CONSTRUCTION LIMIT TO CONSTRUCTION LIMIT) <u>0.47</u> ACRES PROPOSED WORK PERMIT AND PERMANENT EASEMENT AREA <u>0.21</u> ACRES SEED AREA 0.25 ACRES

SUPPORTING REPORTS AND PLANS

THE FOLLOWING ASSISTED IN DEVELOPING THE EROSION CONTROL PLAN AS REFERENCED DOCUMENTS: USGS DRAINAGE MAPS, PROJECT PLAN DOCUMENTS

AND THE ILLINOIS URBAN MANUAL

DRAINAGE TRIBUTARIES RECEIVING WATER FROM CONSTRUCTION SITE: TRIBUTARY OF ROCK RUN

EROSION CONTROLS AND SEDIMENT CONTROL PROCEDURES
STABILIZATION PRACTICES AT THE BEGINNING OF CONSTRUCTION:
PERIMETER EROSION EARRIER & INLET PROTECTION

STABILIZATION PRACTICES DURING CONSTRUCTION:

- (d) WITHIN THE CONSTRUCTION LIMITS, AREAS WHICH MAY BE SUSCEPTIBLE TO EROSION AS DETERMINED BY THE ENGINEER SHALL REMAIN UNDISTURBED UNTIL FULL SCALE CONSTRUCTION IS UNDERWAY TO PREVENT UNNECESSARY SOIL EROSION.
- (b) STOCKPILES OF SOIL AND OTHER BUILDING MATERIALS TO REMAIN IN PLACE MORE THAN THREE (3) DAYS SHALL BE FURNISHED WITH EROSION AND SEDIMENT CONTROL MEASURES (I.E. PERIMETER EROSION BARRIER). STOCKPILES TO REMAIN IN PLACE FOR 30 DAYS OR MORE SHALL RECEIVE TEMPORARY SEEDING.
- (c) AS CONSTRUCTION PROCEEDS, THE CONTRACTOR SHALL INSTITUTE THE FOLLOWING AS DIRECTED BY THE ENGINEER:
 - I. PLACE TEMPORARY EROSION CONTROL FACILITIES AT LOCATIONS SHOWN ON
 - II. TEMPORARILY SEED ERODABLE BARE EARTH ON A WEEKLY BASIS TO MINIMIZE THE AMOUNT OF ERODABLE SURFACE AREA WITHIN THE CONTRACT LIMITS.
- d) EXCAVATED AREAS AND EMBANKMENT SHALL BE PERMANENTLY SEEDED IMMEDIATELY AFTER FINAL GRADING. IF NOT, THEY SHALL BE TEMPORARILY SEEDED IF NO CONSTRUCTION ACTIVITY IN THE AREA IS PLANNED FOR SEVEN DAYS.
- (e) CONSTRUCTION EQUIPMENT SHALL BE STORED AND FUELED ONLY AT DESIGNED LOCATIONS.
 ALL NECESSARY MEASURES SHALL BE TAKEN TO CONTAIN ANY FUEL OR OTHER POLLUTANT
 IN ACCORDANCE WITH EPA WATER QUALITY REGULATIONS. LEAKING EQUIPMENT OR
 SUPPLIES SHALL BE IMMEDIATELY REPAIRED OR REMOVED FROM THE SITE.
- (f) THE RESIDENT ENGINEER SHALL INSPECT THE PROJECT DAILY DURING CONSTRUCTION

 ACTIVITIES. INSPECTION SHALL ALSO BE DONE WEEKLY AND AFTER RAINS OF ½ INCH OR

 GREATER OR EQUIVALENT SNOWFALL AND DURING THE WINTER SHUTDOWN PERIOD. THE

 PROJECT SHALL ADDITIONALLY BE INSPECTED BY THE CONSTRUCTION FIELD ENGINEER ON

 A BI-WEEKLY BASIS TO DETERMINE THAT EROSION CONTROL EFFORTS ARE IN PLACE AND

 EFFECTIVE AND IF OTHER EROSION CONTROL WORK IS NECESSARY.
- SEDIMENT CCLLECTED DURING CONSTRUCTION OF THE VARIOUS TEMPORARY EROSION CONTROL SYSTEMS SHALL BE DISPOSED OF ON THE SITE ON A REGULAR BASIS AS DIRECTED BY THE ENGINEER. THE COST OF THIS MAINTENANCE SHALL BE INCLUDED IN THE UNIT BID PRICE FOR EARTH EXCAVATION.
- (h) ALL MATERI/LS USED FOR TEMPORARY CONSTRUCTION ACTIVITIES WILL BE REMOVED TO UPLAND AREAS IMME)IATELY FOLLOWING COMPLETION OF THE CONSTRUCTION ACTIVITIES. THE COST OF THIS REMOV/L SHALL BE INCLUDED IN THE UNIT BID PRICE FOR VARIOUS TEMPORARY EROSION CONTROL PAY ITEMS.
- (1) EROSION CONTROL BLANKET SHALL BE INSTALLED TO ALL DISTURBED AREAS WITH SLOPES EQUAL TO OR GREATER THAN 1V:5H AND IN CRITICAL AREAS (1.0. DETENTION BASIN PERIMETERS, STREAMBANKS, BERMS, ETC.) IMMEDIATELY UPON FINAL GRADING
- (J) ALL ADJACENT STREETS MUST BE KEPT CLEAR OF DEBRIS, INSPECTED DAILY AND CLEANED WHEN NECESSARY.
- (k) THE USE OF GREEN DYE IN THE EROSION CONTROL BLANKET IS NOT ACCEPTABLE.
- (I) THE USE OF ASPHALT AS A BINDER IS NOT ACCEPTABLE.
- (m) MULCH SHALL BE PLACED OVER THE ENTIRE SEEDED REGION.
- n) EROSION CCNTROL BLANKET SHALL BE PLACED AS SHOWN ON THIS EROSION CONTROL PLAN SHEET AND IN ACCORDANCE WITH SECTION 251 OF THE STANDARD SPECIFICATIONS FOR ROAD / ND BRIDGE CONSTRUCTION.
- (o) SEE SPECIAL PROVISIONS FOR SEEDING AND SODDING.

THE CONTRACTOR SHALL CONTACT THE CORPS OF ENGINEERS WITH A PROPOSED COFFERDAM PLAN MEETING THE STANDARDS LISTED BELOW. MEANS AND METHODS FOR COMPLETING WORK WITHIN A WATERWAY MUST BE APPROVED BY THE CORPS PRIOR TO COMMENCEMENT OF WORK. THE CORPS WILL APPROVE THE COFFERDAM PLAN TO ENSURE IT MEETS EROSION AND SEDIMENT CONTROL STANDARDS. HOWEVER, IT IS INCUMBENT UPON THE CONTRACTOR TO ENSURE THAT ALL COFFERDAMS ARE CONSTRUCTED TO WITHSTAND EXPECTED FLOWS.

WORK WITHIN THE WATERWAY MUST MEET THE FOLLOWING STANDARDS:

- (g) WORK IN THE WATERWAY SHALL BE TIMED TO TAKE PLACE DURING LOW OR NO-FLOW CONDITIONS.
- (b) WATER SHALL BE ISOLATED FROM THE IN-STREAM WORK AREA USING A NON-ERODIBLE COFFERDAM (STEEL SHEETS, AQUA BARRIERS, ETC.). EARTHEN COFFERDAMS ARE NOT PERMISSIBLE.
- (o) WORK MAY NOT BE PERFORMED IN THE WATER, EXCEPT FOR MATERIALS NECESSARY FOR THE CONSTRUCTION OF THE COFFERDAM. THE COFFERDAM MUST BE CONSTRUCTED FROM THE UPLAND BUFFER AREA AND NO EQUIPMENT MAY ENTER THE WATER AT ANY TIME. ONCE THE COFFERDAM IS IN PLACE AND THE ISOLATED AREA IS DEWATERED, EQUIPMENT MAY ENTER THE COFFERED AREA TO PERFORM THE REQUIRED WORK.
- (d) IF BYPASS PUMPING IS NECESSARY, THE PUMP SHALL BE PLACED ON A STABLE SURFACE OR FLOATED TO PREVENT SEDIMENT FROM BEING SUCKED INTO THE HOSE. THE BYPASS DISCHARGE SHALL BE PLACED ON A NON-ERODIBLE, ENERGY DISSIPATING SURFACE PRIOR TO REJOINING THE STREAM FLOW AND SHALL NOT CAUSE EROSION OF DOWNSTREAM AREAS. CLEANING OR FILTERING OF BYPASS WATER IS NOT NECESSARY UNLESS OTHERWISE REQUIRED.
- (0) DURING DEWATERING OF THE COFFERED AREA, ALL WATER MUST BE FILTERED TO REMOVE SEDIMENT. POSSIBLE OPTIONS FOR SEDIMENT REMOVAL INCLUDE BAFFLE SYSTEMS, ANIONIC POLYMERS, DEWATERING BAGS, OR OTHER APPROPRIATE METHODS. WATER SHALL HAVE SEDIMENT REMOVED PRIOR TO BEING RE-INTRODUCED TO THE DOWNSTREAM WATERWAY. DISCHARGE WATER IS CONSIDERED CLEAN IF IT DOES NOT RESULT IN A VISUALLY IDENTIFIABLE DEGRADATION OF WATER CLARITY.
- (f) THE SIDE SLOPES SHALL BE RESEEDED AND STABILIZED WITH AN APPROPRIATE EROSION CONTROL BLANKET PRIOR TO ACCEPTING FLOWS. THE SUBSTRATE SHALL BE RESTORED TO PRE-CONSTRUCTION CONDITIONS AND STABLE ENOUGH TO ACCEPT FLOWS.

MAINTENANCE AFTER FINAL GRADING

TEMPORARY EROSION CONTROL SYSTEMS SHALL BE LEFT IN PLACE WITH PROPER MAINTENANCE UNTIL PERMANENT EROSION CONTROL IS IN PLACE AND WORKING PROPERLY AND ALL PROPOSED TURF AREAS SEEDED AND ESTABLISHED WITH THE PROPER STAND.


USER NAME =	DESIGNED	-	L.G.N.	REVISED	-
	CHECKED	-	G.F.S.	REVISED	-
PLOT SCALE =	DRAWN		L.G.N.	REVISED	-
PLOT DATE =	CHECKED	-	G.F.S.	REVISED	-


ILLINOIS DEPARTMENT OF TRANSPORTATION BARNEY DRIVE OVER TRIBUTARY OF ROCK RUN STATION 20+00


 EROSION CONTROL PLAN
 F.A.U. SECTION
 COUNTY SHEETS NO.
 STRUCTURE NO. 099-6474


 STRUCTURE NO. 2 DE 2 SHEETS
 0330
 08-00413-00-BR
 WILL
 33
 13

 SHEET NO. 2 DE 2 SHEETS
 10 DEBUGGE DE 10 DEBUGGE D









STAGE I REMOVAL

Looking North
Dimensions at Rt. Anglos to © Barney Drive


STAGE CONSTRUCTION SEQUENCE

- 1.) Install required traffic control items & close roadway. See Roadway Plans,
- 2.) Install temporary pedestrian safety fence alongside East Sidewalk.
- 3.) Excavate behind existing Stage I box culvert per cross-section; provide sawcut per Structural Sheet 6 of 11 at limits of proposed downstream channel end treatment.
- 4.) Remove existing box culvert, pavement, sidewalk, handrall, and curb & gutter within the Stage I Removal Limits.
- 5.) Relocate/Construct/Install any necessary utility items (e.g. watermain & storm sewer pipes) within the Stage I Construction limits.
- 6.) Construct proposed Stage I box culvert and aluminum railing as shown per plans.
- 7.) Backfill around sides of proposed Stage I box culvert.
- 8.) Construct downstream revetment mat, concrete streambed, sidewalk, and pipe handrail.
- 9.) Relocate temporary pedestrian safety fence and install alongside West Sidewalk.
- 10.) See Structural Sheet 4 of 11.

NOTES:

Hatched area indicates existing structure removal.


Temporary chainlink fence shall be provided for Stage Construction. See Roadway Plans.



STAGE I CONSTRUCTION


Looking North
Dimensions at Rt. Angles to © Barney Drive

USER NAME =	DESIGNED -	PETER PASCUA	REVISED -	ILLINOIS DEPARTMENT OF TRANSPORTATION	CONSTRUCTION STAGING DETAILS - STAGE I	F.A.U.	SECTION	COUNTY	TOTAL SHEET
	CHECKED -	BRIAN CONVERSE	REVISED -	BARNEY DRIVE OVER TRIBUTARY OF ROCK RUN		0330	08-00413-00-BR	WILL	33 17
PLOT SCALE =	DRAWN -	RON ALLEN	REVISED -	STATION 20+00	SINUCIONE NU. 033-04/4		WHA# 1201D10	CONTRACT	NO. 63571
PLOT DATE =	CHECKED -	BRIAN CONVERSE	REVISED ~	STATION 20+00	STRUCTURAL SHEET NO. 3 OF 11 SHEETS		ILLINOIS FED. A	ID PROJECT BRM-	-9003(162)



STAGE II REMOVAL

Looking North
Dimensions at Rt. Angles to © Barney Drive



STAGE II CONSTRUCTION

Looking North
Dimensions at Rt. Angles to © Barney Drive

USER NAME = DESIGNED - PETER PASCUA REVISED ~ ILLINOIS DEPARTMENT OF TRANSPORTATION CONSTRUCTION STAGING DETAILS - STAGE II CHECKED - BRIAN CONVERSE REVISED WILL 33 18 CONTRACT NO. 63571 BARNEY DRIVE OVER TRIBUTARY OF ROCK RUN 08-00413-00-BR STRUCTURE NO. 099-6474 PLOT SCALE = DRAWN RON ALLEN REVISED WHA# 1201D10 STATION 20+00 BRIAN CONVERSE STRUCTURAL SHEET NO. 4 OF 11 SHEETS ILLINOIS FED. AID PROJECT BRM-9003(162


STAGE CONSTRUCTION SEQUENCE


- 1.) Excavate behind existing Stage II box culvert per cross-section.
- 2.) Remove existing box culvert, pavement, sidewalk, and curb & gutter within the Stage II Removal Limits.
- 3.) Relocate/Construct/Install any necessary utility items (e.g. watermain & storm sewer pipes) within the Stage II construction limits.
- 4.) Construct proposed Stage II box culvert and aluminum railing as shown per plans.
- 5.) Backfill around sides of proposed Stage II box culvert.
- 6.) Construct proposed upstream revetment mat, streambed concrete, sidewalk, and pipe handrall.
- 7.) Construct proposed roadway pavement/traffic lane and curb & gutter.
- 8.) Remove temporary pedestrian safety fence,


NOTES:


Hatched area indicates existing structure removal.

Temporary chainlink fence shall be provided for Stage Construction. See Roadway Plans.









STANDARD BAR SPLICER ASSEMBLY

Minimum Lap Lengths									
Bar size to be spliced	Table 1	Table 2	Table 3	Table 4	Table 5				
3, 4	1'-5''	1'-11''	2'-1"	2'-4''	2'-3"				
5	1'-9''	2'-5''	-2'-7"	2'-11''	2'-10''				
6	2'-1"	2'-11''	3'-1''	3'-6''	3'-4''				
7	2'-9''	3'-10''	4'-2"	4'-8''	4'-6''				
8	3′-8′′	5′-1′′	5′-5″	6'-2"	5'-10''				
9	4'-7"	6′-5′′	6'-10''	7'-9''	7'-5"				

Table 1: Black bar, 0.8 Class C

PLOT SCALE =

Table 2: Black bar, Top bar lap, 0.8 Class C

Table 3: Epoxy bar, 0.8 Class C


Table 4: Epoxy bar, Top bar lap, 0.8 Class C

Table 5: Epoxy bar, Top bar lap, Class B

Threaded splicer bar length = min. lap length + $1_2^{\prime\prime}$ + thread length

* Epoxy not required on Bar Splicer Assembly components used in conjunction with black bars.


Bar size	No. assemblies required	Table for minimum lap length		
#4	33	Table 3		
#5	107	Table 3		
	LLD 44.7			




INSTALLATION AND SETTING METHODS

"A": Set bar splicer assembly by means of a template bolt.
"B": Set bar splicer assembly by nailing to wood forms or cementing to steel forms.

(E): Indicates epoxy coating.





NOTES.

Splicer bars shall be deformed with threaded ends and have a minimum 60 ksi yield strength.


All reinforcement shall be lapped and tied to the splicer bars.


Bar splicer assemblies shall be epoxy coated according to the requirements for reinforcement bars. See Section 508 of the Standard Specifications.


See special provision for Mechanical Splicers.


See approved list of bar splicer assemblies and mechanical splicers for alternatives.

DESIGNED -	PETER PASCUA	REVISED -	ILLINOIS DEPARTMENT OF TRANSPORTATION	BAR SPLICER ASSEMBLY AND MECHANICAL SPLICER DETAILS	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CHECKED -	BRIAN CONVERSE	REVISED -	BARNEY DRIVE OVER TRIBUTARY OF ROCK RUN	STRUCTURE NO. 099-6474	0330	08-00413-00-BR	WILL	33	22
DRAWN -	RON ALLEN	REVISED -	STATION 20+00	011100101E 110. 033-0474		WHA# 1201D10	CONTRACT	NO. 63	571
CHECKED ~	BRIAN CONVERSE	REVISED -	STATION 20+00	STRUCTURAL SHEET NO. 8 OF 11 SHEETS	ILLINOIS FED. AID		.D PROJECT BRM-9003(162)		











INLETS, SPECIAL RT STA 20+38





LONGITUDINAL SECTION

SECTION A-A

NOTES:

SLAB ON 3" SAND CUSHION

THE INLET SHALL BE CAST IN PLACE OR PRECAST, EXCEPT AS NOTED HERE, ON INLET SPECIAL SHALL BE CONSTRUCTED IN ACCORDANCE WITH SECTION 602 OF THE STANDARD SPECIFICATIONS. THE CONTRACT UNIT PRICE EACH FOR INLETS, SPECIAL SHALL INCLUDE THE COST OF FURNISHING AND INSTALLING THE INLET WITH SAND CUSHION IF REQUIRED. CLASS SI CONCRETE OR PRECAST CONCRETE SHALL BE USED THROUGHOUT. THE SIDEWALLS MAY BE BUILT AS PRECAST SEGMENTAL SECTIONS. THE HEIGHT OF THE BOX MAY BE CONSTRUCTED 6" SHORT TO ALLOW FOR FIELD ADJUSTMENTS. THE WALL ADJUSTMENTS SHALL BE MADE WITH CONCRETE BUILDING BRICK OR CLASS SI CONCRETE.

FRAME AND GRATE TO WEIGHT APPOROXIMATELY 525 LBS.


(NEENAH R-3246 W/TYPE C GRATE OR EQUAL)


ILLINOIS DEPARTMENT OF TRANSPORTATION
BARNEY DRIVE OVER TRIBUTARY OF ROCK RUN
STATION 20+00

INLETS, SPECIAL DETAIL
STRUCTURE NO. 099-6474
SHEET NO. 1 OF 2 SHEETS

| F.A.U. | SECTION | COUNTY | TOTAL | SHEET: NO. | COUNTY | SHEET: NO. | COUNTY | SHEET: NO. | COUNTRACT | NO. | COUNTRA

INLETS, SPECIAL LT STA 20+38





6" CLASS SI CONCRETE OR 4" PRECAST REINF. CONC. SLAB ON 3" SAND CUSHION

LONGITUDINAL SECTION

SECTION A-A

NOTES:

THE INLET SHALL BE CAST IN PLACE OR PRECAST, EXCEPT AS NOTED HEREIN, AND SHALL BE CONSTRUCTED IN ACCORDANCE WITH SECTION 602 OF THE STANDARD SPECIFICATIONS. THE CONTRACT UNIT PRICE EACH FOR INLETS, SPECIAL SHALL INCLUDE THE COST OF FURNISHING AND INSTALLING THE INLET WITH SAND CUSHION IF REQUIRED. CLASS SI CONCRETE OR PRECAST CONCRETE SHALL BE USED THROUGHOUT. THE SIDEWALLS MAY BE BUILT AS PRECAST SEGMENTAL SECTIONS. THE HEIGHT OF THE BOX MAY BE CONSTRUCTED 6" SHORT TO ALLOW FOR FIELD ADJUSTMENTS. THE WALL ADJUSTMENTS SHALL BE MADE WITH CONCRETE BUILDING BRICK OR CLASS SI CONCRETE.

FRAME AND GRATE TO WEIGHT APPOROXIMATELY 525 LBS.

(NEENAH R-3246 W/TYPE C GRATE OR EQUAL)

U9	SER NAME =	DESIGNED ~ L.G.N.	REVISED -	ILLINOIS DEPARTMENT OF TRANSPORTATION BARNEY DRIVE OVER TRIBUTARY OF ROCK RUN	INLETS, SPECIAL DETAIL	F.A.U.	SECTION	COUNTY	TOTAL SHEET
P		CHECKED - G.F.S.	REVISED -		STRUCTURE NO. 099-6474	0330	08-00413-00-BR	WILL	33 28
	OT SCALE =	DRAWN - L.G.N.	REVISED -		51KUCTURE NU. 033-04/4	WHA# 1201D10		CONTRACT NO. 63571	
PL	OT DATE =	CHECKED - G.F.S.	REVISED -	STATION 20+00	SHEET NO. 2 OF 2 SHEETS	ILLINOIS FED. AID F) PROJECT BRM-9003(162)	

