

COPYRIGHT © 2011 BY BAXTER & WOODMAN, INC.
 STATE OF ILLINOIS PROFESSIONAL ENGINEERING
 LICENSE NO. 184-00023 - EXPIRES 4/30/2013
 522R.km 4/13/2011 09:50:45 PM
 \\dotp1\p1\work\2011\201104\1011...ACADD-SURVEY\VP_015\015093\FB1
 I:\C:\yaf\all\line\MCCDD\015093.Dwg VAF BT\CADD SURVEY\NUMBERS\LOGS\015093-500.dwg

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE	
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	PEDESTRIAN 0028	
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	10	10	
20101100	TREE TRUNK PROTECTION	EACH	7	7	
20101200	TREE ROOT PRUNING	EACH	7	7	
20200100	EARTH EXCAVATION	CU YD	990	990	
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	950	950	
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	6,404	6,404	
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	1,405	1,405	
25000200	SEEDING, CLASS 2	ACRE	3.1	3.1	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	280	280	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	280	280	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	280	280	
25100105	MULCH, METHOD 1	ACRE	3.1	3.1	
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	15,002	15,002	
25200200	SUPPLEMENTAL WATERING	UNIT	92	92	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	310	310	
28000305	TEMPORARY DITCH CHECKS	FOOT	3	3	
28000400	PERIMETER EROSION BARRIER	FOOT	4,730	4,730	
28000510	INLET FILTERS	EACH	1	1	
35101800	AGGREGATE BASE COURSE, TYPE B 6"	SQ YD	5,502	5,502	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	6	6	
40600300	AGGREGATE (PRIME COAT)	TON	19	19	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	652	652	
42001300	PROTECTIVE COAT	SQ YD	179	179	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	1,380	1,380	
42400800	DETECTABLE WARNINGS	SQ FT	120	120	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	140	140	
44000600	SIDEWALK REMOVAL	SQ FT	384	384	
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	140	140	
67100100	MOBILIZATION	L SUM	1	1	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	

* INDICATES SPECIALTY ITEM

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE	
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	PEDESTRIAN 0028	
70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	
72000100	SIGN PANEL - TYPE 1	SQ FT	220	220	
72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	633	633	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	180	180	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	178	178	
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	403	403	
* 78001100	PAINT PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	105	105	
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	4,405	4,405	
* 78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	30	30	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	14	14	
A2004820	TREE, GLEDITSIA TRIACANTHOS INERMIS SKYLINE (SKYLINE THORNLESS COMMON HONEYLOCUST), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	1	1	
Z0019600	DUST CONTROL WATERING	UNIT	118	118	
Z0022800	FENCE REMOVAL	FOOT	40	40	
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	208	208	
Z0042002	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	950	950	
X0350805	FOLD DOWN BOLLARDS	EACH	21	21	
X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	6	6	

* INDICATES SPECIALTY ITEM



USER NAME = 522r.km 522r.km	DESIGNED - AEB	REVISED - PER IDOT 3/25/11
FILE NAME = 2\90593-500.dwg	DRAWN - RKM	REVISED - PER IDOT 4/11/11
PLOT DATE = 4/13/2011	CHECKED - MDW	REVISED -
	DATE - 1/26/11	REVISED -

McHENRY COUNTY CONSERVATION DISTRICT
RIDGEFIELD TRACE EXTENSION
BICYCLE PATH

SUMMARY OF QUANTITIES		
SCALE:	STA.	TO STA.

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
N/A	00-C2000-03-BT	McHENRY	25	4
JOB NO: C-91-711-10		CONTRACT NO. 63578		
FED. ROAD DIST. NO. 1 ILLINOIS		FED. AID PROJECT NO: CMM-9003 (680)		
McHENRY COUNTY CONSERVATION DISTRICT BID #0311.09.01				