

Drawing file: W:\Projects\61210000 - Montrose Ave LAPP (Horham to Soyre)\Quantities-MontroseAve.dwg Apr 05, 2011 - 9:12am

**SUMMARY OF QUANTITIES**

CODE	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
				RESURFACING 005	80% FEDERAL 20% STATE
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	500	500	
25200100	SODDING	SQ YD	500	500	
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	6900	6900	
40600300	AGGREGATE (PRIME COAT)	TON	140	140	
40600895	CONSTRUCTING TEST STRIP	EACH	2	2	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	360	360	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	4000	4000	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	15	15	
42101300	PROTECTIVE COAT	SQ YD	1125	1125	
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	SQ YD	250	250	
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	40	40	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	3100	3100	
42400800	DETECTABLE WARNINGS	SQ FT	560	560	
44000160	HOT-MIX ASPHALT SURFACE REMOVAL, 2 3/4"	SQ YD	34500	34500	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	360	360	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1900	1900	
44000600	SIDEWALK REMOVAL	SQ FT	3700	3700	
44201737	CLASS D PATCHES, TYPE I, 8 INCH	SQ YD	30	30	
44201741	CLASS D PATCHES, TYPE II, 8 INCH	SQ YD	60	60	
44201745	CLASS D PATCHES, TYPE III, 8 INCH	SQ YD	100	100	
44201747	CLASS D PATCHES, TYPE IV, 8 INCH	SQ YD	150	150	

**SUMMARY OF QUANTITIES**

CODE	PAY ITEM	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE	
				RESURFACING 005	80% FEDERAL 20% STATE
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	15	15	
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	55	55	
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	25	25	
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	40	40	
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	825	825	
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	1075	1075	
67100100	MOBILIZATION	L SUM	1	1	
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1	
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1	
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1	
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1	
70300100	SHORT TERM PAVEMENT MARKING	FOOT	8000	8000	
★ 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	475	475	
★ 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	21500	21500	
★ 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1800	1800	
★ 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	750	750	
★ 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	400	400	
★ 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	160	160	
★ 78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	100	100	
★ 88600600	DETECTOR LOOP REPLACEMENT	FOOT	700	700	
X4060826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2000	2000	
X6030310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	78	78	

★ DENOTES SPECIALTY ITEM



♦ Civil Engineers  
 ♦ Municipal Consultants  
 ♦ Established 1911

9533 Roosevelt Road  
 Westchester, Illinois 60154-3780  
 Phone: 708/665-0390  
 Fax: 708/665-1212

DESIGNED - -	REVISED - -
DRAWN - -	REVISED - -
CHECKED - -	REVISED - -
DATE - - 03/25/11	REVISED - -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: NONE SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2729	10-00060-00-RS	COOK	17	3
FED. ROAD DIST. NO. 1 ILLINOIS			CONTRACT NO. 63582	
FED. AID PROJECT				